PREFACE

Thank you for purchasing the LT integrated development software, "LT Editor Ver. 2.0", hereafter referred to as the "LT Editor".

Please read this manual carefully in order to use this software properly, and be sure to keep this manual handy for future reference.

NOTES

(1) The copyrights to all programs and manuals included in the LT Editor Ver. 2.0 Operation Manual - Screen Creation Guide (hereinafter referred to as "this product") are reserved by the Digital Electronics Corporation. Digital grants the use of this product to its users as described in the "Software Operating License Conditions" documentation, included with this product's CD-ROM. Any actions violating the above-mentioned conditions are prohibited by both Japanese and foreign regulations.

(2) The contents of this manual have been thoroughly inspected. However, if you should find any errors or omissions in this manual, please inform your local LT Editor representative of your findings.

(3) Regardless of article (2), the Digital Electronics Corporation shall not be held responsible for any damages or third party claims resulting from the use of this product.

(4) Differences may occur between the descriptions found in this manual and the actual functioning of this product. Therefore, the latest information on this product is provided in data files (i.e. Readme.txt files, etc.) and in separate documents. Please consult these sources as well as this manual prior to using the product.

(5) Even though the information contained in and displayed by this product may be related to intangible or intellectual properties of the Digital Electronics Corporation or third parties, the Digital Electronics Corporation shall not warrant or grant the use of said properties to any users and/or other third parties. Digital Electronics Corporation accepts no liability for issues related to the intellectual property rights of third parties or any issues related to the use of the information contained in or displayed by this product.

(6) The specifications set out in this manual are for overseas products only. As a result, some differences may exist between the specifications given here and for those of the identical Japanese product.

The LogiTouch is referred to as "LT" in this manual.

For the rights to trademarks and trade names, see "TRADEMARK RIGHTS".

TRADEMARK RIGHTS

All company or product names used in this manual are the trade names, trademarks (including registered trademarks), or service marks of their respective companies.

This product omits individual descriptions of each of these rights.

Trademark / Trade Name	Right Holder
Microsoft, MS, MS-DOS, Windows, Windows 95, Windows 98, Windows Me, Windows NT, Windows 2000, Windows XP, Windows Explorer, Microsoft Excel 95	Microsoft Corporation, USA
Intel, Pentium	Intel Corporation, USA
Pro-face, Flex Network	Digital Electronics Corporation (in Japan and other countries)
Ethernet	Western Digital Electric Corporation, USA
IBM, VGA, PC/AT	International Business Machines Corporation (IBM), USA

The following terms differ from the above mentioned formal trade names and trademarks.

Term used in this manual	Formal Trade Name or Trademark
Windows 95	Microsoft® Windows®95 Operating System
Windows 98	Microsoft® Windows®98 Operating System
Windows Me	Microsoft® Windows®Me Operating System
Windows NT	Microsoft® Windows NT® Operating System
Windows 2000	Microsoft® Windows®2000 Operating System
Windows XP	Microsoft® Windows®XP Operating System
MS-DOS	Microsoft® MS-DOS® Operating System

Version Upgrade Information

The LT Editor Ver. 2.0 features a range of new functions upgraded from the LT Editor Ver. 1.0, including Multi-language Display function, Extended Function of Keypad Input Display, and Parts Palette function. The following briefly describes each function.

◆ **Parts Palette**

The parts are displayed in a palette on the Screen Editor. The desired part can be set up on the screen simply by selecting it from the Parts Palette and positioning it at the desired point using the drag & drop operation.

▼ *Reference* ▲ *1.3.1 Screen Editor Item Names and Functions*

◆ **Extended Function of Keypad Input Display**

This function allows you to configure the interlock setting of the pop-up keypad. In addition, this function enables extended display format, allowing you to select the input style using alarm and barcode reader, and display style including the Shift Left/Shift Right and Zero Suppress modes.

▼ *Reference* ▲ *2.1.14 Keypad Input Display*

◆ **Extended Function of Numeric Displays**

This function allows you to select the display style of the Numeric display including the Shift Left/Shift Right and Zero Suppress modes.

▼ *Reference* ▲ *2.1.21 Numeric Displays*

◆ **Extended Function of Trend Graphs**

This function displays the trend data stored in a sequence of contiguous word addresses on a single trend graph.

▼ *Reference* ▲ *2.1.12 Trend Graphs*

◆ **Keypad Parts**

Some new Keypad Parts have been added.

▼ *Reference* ▲ *2.1.13 Keypad Display*

◆ **Window Registration Function on Window Screen and Window Parts**

Windows registered on the Window (U) Screen can be displayed on the Base (B) Screen as a window. The display can be selected from Local and Global modes. Use Window Parts to call up a window.

▼ *Reference* ▲ *2.1.20 Window Parts, 3.3 Window Display-Window Screen*

◆ **Multi-language Display Function**

The text display used for drawing/Part's Label/Message Display/Alarm Display (Index text) can be switched while operating the LT by using the Index text registered via the Text Table Editor. This function allows you to change the language and parameters of the items displayed on the screen easily.

▼ *Reference* ▲ *4.3 Text Table Editor*

◆ **Print Function**

Connect the LT Tool connector to the serial printer using a transfer cable and conversion cable. Alarm messages, Logging data, and hard copies of screens can be printed with the Print function.

▼ Reference ◣ *6.1 Menu Setting Items: LT Setup, PLC Manual 1.1.4 Content and Range of System Data Area, LT Series User's Manual*

◆ **Address Conversion with the Global Cross Reference**

The desired address can be converted via the global cross reference that lists the address-allocation status of the entire Project file.

▼ Reference ◣ *2.9.7 Cross Reference/Global Cross Reference List*

◆ **Project Backup Function**

When saving a Project file, a backup of the most recently saved Project file is saved in a backup file (*.bak).

▼ Reference ◣ *4.2.2 Backing up a Project*

◆ **Address Conversion when changing the PLC**

When changing the PLC types selected in a Project file, the conversion pattern can be specified for the available device of the destination PLC. The addresses belong to the specified pattern can be converted by one operation. The conversion pattern can be edited and appended.

▼ Reference ◣ *4.2.8 Changing the PLC and Addresses*

■ **New PLC Protocol**

- Fenwal Controls of Japan: Temperature Controller AL Series
- JT Engineering: Moisture Meter JE-70 Series
- Yasukawa Electric: Inverter Variable Speed G7/F7 Series, VS mini V7/J7 Series
- Yokogawa M&C: UT100 Series
- Matsushita Electric Industrial: MINAS-A/S Series
- RKC Instrument: CB/REX-F/LE100 Series
- SHIMADEN: SR253/SR90/SR80/MR13/FP93/SD16/EM70 Series

▼ Reference ◣ *PLC Manual*

MANUAL SYMBOLS AND TERMINOLOGY

This manual uses the following symbols and terminology.

■ Safety Symbols and Terms

This manual uses the following symbols and terms to identify important information related to the correct and safe operation of this product.

| Symbol	Description
⚠ WARNING	Indicates a potentially hazardous situation that could result in serious injury or death.
⚠ CAUTION	Indicates a potentially hazardous situation that could result in minor injury or equipment damage.
Important	Indicates a potentially damaging action or dangerous situation that could result in abnormal equipment operation or data loss.
Careful!	Indicates instructions or procedures that must be performed to ensure correct product use.
STOP	Indicates instructions or procedures that must not be performed.

## ■ General Information Symbols and Terms

This manual uses the following symbols and terms for general information.

Symbol	Description
Note:	Provides hints on correct product use, or supplementary information.
▼Reference◀	Indicates an item's related information (manual name, page number).
Esc Ctrl	Refers to keys on the computer keyboard. ▼Reference◀ ■ Keyboard Compatibility List
External Device	Indicates an external device (temperature controller, inverter, etc.) connected via serial communications. Does not include devices connected via the Flex Network or DIO.
LT	Generic name for the "LT" Graphic Logic Controller made by Digital Electronics Corporation.
LT Editor	Indicates LT Version 2.0 (hereinafter referred as "this product"), LT integrated development software made by Digital Electronics Corporation.

■ **Keyboard Compatibility List**

This manual uses the following symbols to indicate computer keyboard keys.

The key names used by your computer keyboard may differ. Please use the chart below for reference.

Symbol / Type	PS/2 Compatible 101 Keyboard
Esc	Esc
Tab	Tab ⇄
Ctrl	Ctrl
Shift	↑ Shift
Alt	Alt
Delete	Delete
Back space	Backspace

LT SERIES

The LT Editor supports the following LT models.

Series	Type	Product	Model
LT Series	Type-A1	GLC150B-XY32SK	GLC150-BG41-XY32SK-24V
	Type-A1	GLC150B-XY32SC	GLC150-BG41-XY32SC-24V
	Type-B	GLC150B-RSFL	GLC150-BG41-FLEX-24V
	Type-B+	GLC150B-XY32KF	GLC150-BG41-XY32KF-24V
	Type-C	GLC150B-XY32SK	GLC150-BG41-RSFL-24V
	Type H1	GLC150B-ADK	GLC150-BG41-ADK-24V
		GLC150B-ADPK	GLC150-BG41-ADPK-24V
		GLC150B-ADTK	GLC150-BG41-ADTK-24V
	Type H2	GLC150B-ADC	GLC150-BG41-ADC-24V
		GLC150B-ADPC	GLC150-BG41-ADPC-24V
		GLC150B-ADTC	GLC150-BG41-ADTC-24V
	Type D	GLC150B-DNM	GLC150-BG41-DNM-24V

Note: **For the types of Device/PLCs supported by the LT Editor, please refer to the "Device/PLC Connection Manual".**

▼*Reference*◢ *HOW TO USE THIS MANUAL*

HOW TO USE THIS MANUAL

■ Structure of the Manual

The "LT Editor Ver. 2.0 Operation Manual - Screen Creation Guide" is the second in a series of manuals for this product and explains how to use the LT Editor. There are three other manuals in the series as well as online help. Please refer to "Chapter 1 LT EDITOR FUNDAMENTALS" for an overview of this product.

▼*Reference*▲ *1.6 LT Editor Manuals and Help*

In addition to these manuals, data files containing supplemental information on updated functions are also provided.To read these additional data files, click on the [Start] button in your Windows OS main screen and select the [Programs]→[Pro-face]→[LT Editor] menu. Then, click on the [Readme] selection.

For detailed information on LT series of operator interfaces, please refer to the "LT Series User's Manual". (Separately sold)

Included on CD-Rom	**LT Editor Operation Manual (this manual)**	Describes the operating procedures for the LT Editor and all functions except for Logic Program development (provided as a PDF file).
	LT Editor Programming Manual	Describes logic program development. The manual consists of two parts, "Programming" which focuses on the tutorial lesson to help users to learn the operation procedures, and "Functions" which explains the software settings required for the combination of the LT main unit and the LT Editor (provided as a PDF file).
	Parts List	Describes the LT Editor's pre-made Parts and symbols (provided as PDF data).
	Device/PLC Connection Manual	Describes the methods for connecting the Device/PLC of various manufacturers (provided as a PDF file).
Available on the LT Editor screen	**Online Help**	Describes the methods for setting the LT Editor's windows and dialog boxes, instructions and functions of logic programs as well as how to set each driver.

Note:
- **Address settings described in these manuals are for explanatory purposes only. Appropriate addresses must be set according to your requirements.**

  ▼*Reference*▲ *Device/PLCs Connection Manual*
- **If you have any questions about the contents of this manual, please contact your local LT distributor. LT distributors will answer to your technical inquiries and provide you with technical consultation.**

  ▼*Reference*▲ *Software Trouble Report*

  If you have any question about your personal computer or Microsoft® Windows®, please contact your PC distributor or manufacturer.

PREFACE

■ Chapter Breakdown

This manual contains 10 chapters and an appendix.
The following is a general description of each chapter:

◆ CHAPTER 1: LT EDITOR FUNDAMENTALS

This chapter describes the operation of the LT Editor from start to finish. It also explains the overall structure of the LT Editor Project Manager, Logic Program Editor, and Screen Editor areas.

◆ CHAPTER 2: CREATING BASE SCREENS

This chapter describes the basic operations and terminology used for drawing functions, such as "Part", "Library", and "D-Script".

◆ CHAPTER 3: DRAWING APPLICATIONS: CREATING AND USING SCREENS

This chapter describes the procedures for creating and using various screens, such as the M (Mark) Screen and I (Image Library) screens, which enable you to create high-quality images and provide advanced-level functionality.

◆ CHAPTER 4: SCREEN AND PROJECT MANAGEMENT

This chapter describes the procedures for editing and saving created screens and project files, and information management procedure.

◆ CHAPTER 5: CREATING AND EDITING ALARMS

This chapter describes the alarm creating and editing procedures.

◆ CHAPTER 6: LT INITIAL AND SYSTEM SETTINGS

This chapter describes the initial setup procedure required to use the LT display unit. For details, please refer to the online help or the users' manual for the LT main unit.

◆ CHAPTER 7: TRANSFERRING DATA

This chapter describes the procedures for sending screens and logic programs created with the LT Editor to an LT display unit.

◆ CHAPTER 8: SIMULATION

This chapter describes the procedures for simulating the operation between an LT and LT Editor.

◆ CHAPTER 9: PRINTING

This chapter describes the procedure for printing created screens.

◆ CHAPTER 10: ADVANCED FEATURES

This chapter describes the procedures for using the LT Editor's advanced functions such as filing data (recipe) and logging functions.

◆ **APPENDIX**

• **Error Messages**

Lists the error messages, causes of the errors and solutions that will be displayed during operation of LT Editor.

• **Troubleshooting**

Provides information for diagnosis and corrective actions for dealing with errors or abnormal operation.

• **Address Conversion Tables**

Lists the addresses for each manufacturer's product.

• **Software Trouble Report**

This is a form in which you can write down any trouble you might have with the LT Editor and your LT Editor's operating conditions that can then be sent to us by facsimile. If you have any inquires about the LT Editor, please use this form.

PRECAUTIONS

■ CD-ROM Usage Precautions

To prevent CD-ROM damage or malfunctions, please observe the following instructions:

STOP

- Do not remove the CD-ROM from the CD-ROM drive while the drive's operation lamp is lit.

- Do not touch the CD-ROM recording surface.

- Do not place CD-ROMs in a place where they may be exposed to extremely high or low temperatures, high humidity, or dust.

■ Product Usage Precautions

To prevent program malfunction or accidents, be sure to observe the following instructions:

⚠ Warning

Touch panel switches should NOT be used for a device's Emergency Stop Switch. Generally speaking, all industrial machinery/systems must be equipped with a mechanical, manually operated emergency stop switch. Also, for other kinds of systems, similar mechanical switches must be provided to ensure safe operation of those systems.

STOP

- Do not turn off your personal computer's power switch during the execution of a program.

- Do not change the contents of this product's project files using the Text Editor software.

◆ **Drawing**

- The LT Editor's display screen and descriptions used in the manuals are based on the color display when the LT main unit is in the "REVERSE" LCD mode. Please note that white/black color on the LT Editor screen and LT main unit screen will be reversed when the LCD is in the "NORMAL" mode.

  ▼Reference◣ *LT Series User's Manual*

- When arranging characters on a tiling pattern, the dot patterns of character may overlap with the tiling pattern; as the result, the characters will not be displayed properly on the LT when the same color is selected for the characters and the tiling pattern. In such a case, re-arrange the characters by displacing the position by 1 dot.

- When an LT unit is vertically installed, the panel's coordinates will differ from those used on the screen editor software. Therefore, when you enter screen coordinates using tags or D-Script, please consider the LT's orientation.

(0. 0) on the screen editor software

(0. 0) on the LT series' panel

◆ **Functions and Settings**

- Certain functions and settings supported by the LT unit are not supported by the LT Editor program, and vice versa.

  [Setting and functions set via the LT unit (Not by LT Editor)]

    - Language Font selection
    - LT Date/Time settings
    - LT Self-Diagnosis Function

  [Functions and settings supported by LT Editor only (Not by the LT unit)]

  The following settings are included in the "LT System Settings" area:
    - "Checksum Verification" settings
    - Screen Change Order in hierarchical display mode
    - Screen Change according to standby mode time
    - Shift to OFFLINE mode settings
    - Setting the frequency of Keypad Display processing performed per scanning time
    - LT unit's internal memory (LS area) backup function settings
    - "Error Display Reset" settings
    - "Watch Dog" settings (Communication monitoring between the LT and the Device/PLC)
    - Communication Monitoring Period settings (Designate transmission wait time)
    - Printing settings (Settings for printing functions with Tool connector)

◆ **Logic Program Restrictions**

- Variables (Logic symbols) are processed in 32-bit order.

- Values different from the input values may display during monitoring due to the difference in the real number accuracy between a personal computer and the LT.

- If the LT's logic time (scan time) becomes too long, the sampling time designated for the trend graph may not be accurately maintained.

- All LT Retentive Variable data is retained by SRAM backup memory that uses a lithium battery. The battery's back up period lasts approximately 60 days in its initial condition (fully charged), and approximately 6 days when the battery life is almost finished. If you need to back up data for a longer period, you need to either use back up data in your host computer, or configure the Editor system so that the Editor can back up data.

TABLE OF CONTENTS

PREFACE

PREFACE

CHAPTER 3: DRAWING APPLICATIONS - CREATING and USING SCREENS

CHAPTER 4: SCREEN AND PROJECT MANAGEMENT

PREFACE

CHAPTER 10: ADVANCED FEATURES

APPENDICES

1 LT EDITOR FUNDAMENTALS

This chapter describes LT Editor basic operations such as how to start and quit the software. It also explains the Project Manager and Screen Editor areas, which are used for the majority of screen creation work. Also, a number of tools are introduced here, such as online help, which provide explanations of LT Editor functions and operations.

1.1 ▶ Overview

The LT provides I/O control functions and can also be used as an operating swich and a display.

LT Editor is the LT integrated development software, providing both an LT Logic Programming environment and screen creation and editing capabilities for creating LT display screens.

■ Programming Functions

Utilizing Window's easy-to-use interface, you can quickly and easily develop logic programs that conform to the IEC 61131-3 standard .

LT Editor provides I/O drivers that can be selected according to the LT type.

Logic programs are developed with the LT Editor's Logic Program Editor.

For more information on the Logic Program Editor, please refer to the online help. Also, the "Logic Programming Operation Manual" provides tutorials for learning logic programming procedures as well as providing lists of instructions and variables used in Logic Programs. It also explains the operation of the LT main unit.

■ Drawing Functions

You can create a screen by drawing objects and placing Parts.

A large variety of pre-made Parts and D-Scripts allow you to quickly display various operations and objects.

A set of logic programs created with the Logic Program Editor and a Part's display function enable you to make a drawing that corresponds to logic program operations. For example, you can show the variables on the LT screen and set a value to the variable using a touch panel switch.

1.1.1   Prior to Operating the LT

Follow the procedure below to create projects for the LT unit.

1. Preparation – Before using the LT, make sure that you have all the required hardware and have read all the specifications, wiring, and installation information.

▽Reference△ *LT Series User's Manual, Chapter 2 – "Specifications" and Chapter 3 – "Installation and Wiring"*

2. Design Screen – Design a screen layout and create a logic program.

3. Install the LT Editor – Install the LT Editor on a PC.

▽Reference△ *LT Editor CD Jacket (included with the LT Editor)*

4. Develop Logic Program – Use the LT Editor to develop a logic program and set the operation mode.

▽Reference△ *LT Editor Operation Manual – Logic Programming Guide*

5. Create Screen/Run Screen Setup – Use the LT Editor to set up the screen and parts based on your screen design.

▽Reference△ *LT Editor Operation Manual – Screen Creation Guide*

6. Transfer the Screen Data and a Logic Program – Use the LT Editor on your PC to transfer the data and a logic program to the LT unit.

▽Reference△ *LT Editor Operation Manual – Screen Creation Guide*

7. Monitor Logic Program – Check the transferred logic program through the monitor feature of the LT Editor.

▽Reference△ *LT Editor Operation Manual – Logic Programming Guide*

8. Initialize the LT – Initialize the LT, based on how you will use it.

▽Reference△ *LT Series User's Manual, Chapter 6 – "Initializing the LT" and LT Editor Device/PLC Connection Manual*

9. Operation –   Run the LT by connecting it to an Device/PLC.

▽Reference△ *LT Editor Device/PLC Connection Manual*

1.2 ▶ From Start to Finish

This section describes the LT Editor program's operation flow from start to finish.

Usage Pattern				
Start →	Create/Select a project file with the Project Manager. →	Create/Edit a Logic Program with the Logic Program Editor. →	Create/Edit a screen with the Screen Editor. →	Save the project, and quit the Project Manager.

1.2.1 ▶ Getting Started

■ Starting LT Editor

The following explanation assumes your PC is turned on and the Windows desktop has appeared.

PROCEDURE	REMARKS
(1) Click on the [Start] button, and point to the [Programs] - [Pro-face] - [LT Editor] menu. Then, click on the [1. Project Manager] command. Pro-face ▶ LT Editor ▶ 1.Project Manager Programs · Accessories · 2.Rebuild Favorites · StartUp · 3.Pack Tool Documents · MS-DOS Prompt · ReadMe Settings · Microsoft Word · Uninstall Find · Windows Explorer Help Run... Shut Down... Windows98 Start	If you double-click directly on a previously made project file (*.lte file) in Windows Explorer, LT Editor will automatically start.
(2) The Project Manager starts. The Tips screen appears upon the startups. This screen displays one-point descriptions on the new features. Tips ☒ Did you know that... Multi-language tables allow you to easily switch between different languages. — **Tips screen** ☑ Show at Startup Next Tip Close	To hide the Tips screen, remove the checkmark from the "Show at Startup checkbox), and click the [Close] button.

PROCEDURE	REMARKS
	When 256 colors is selected on the [Display Properties] screen of the Control Panel, the display of the Project Manager may change, but its functioning will not be affected.

1.2.2 Creating/Selecting/Saving a Project

A project file (LTE file) normally contains multiple screens and a logic program intended for the operation of a certain system. LT Editor creates one project file for the operation of one system, enabling system management by project file units.

After you have transferred a project file and set up an LT, you can transfer updated logic programs individually to the LT.

■ Creating a New Project

When you create a new project, you must designate the LT and Device/PLC information, according to your current application.

◆ LT Type

Select your type of LT.

▼**Reference**▲ *LT Series*

If your LT will be installed vertically instead of horizontally, be sure to select a vertical type LT. The Screen Editor will automatically create a vertical drawing area for you.

LT machine type	LT type of project
Type A1	Type A
Type A2	
Type B	Type B/B+
Type B+	
Type C	Type C
Type H1	Type H
Type H2	

◆ **Device/PLC Type**

Select the type of Device/PLC to be connected to your LT unit.

This setting is required only when the LT is a Type-C.

▼ **Reference** ▲ *Device/PLC Connection Manual*

PROCEDURE	REMARKS
(1) Select the Project Manger's [Project] menu - [New] command, or click on [New].	
(2) Enter a description and select the LT (Display) and Device/PLC. Then, click on [OK].	When entering a description, you can use up to 60 single-byte characters. ▼ **Reference** ▲ To set the Device/PLC, refer to *"LT Editor Device/PLC Connection Manual"*.
(3)The LT Editor will then ask you if you wish to create a logic program or a screen. If you click on the [Edit LogicProgram] **button, the Logic Program Editor will start. If you click on the** [Edit Screen] **button, the Screen Editor will start. If you click on the** [Cancel] **button, you will go back to the Project Manager Screen.**	▼ **Reference** ▲ *1.2.3 Creating/Editing/Saving a Logic Program, 1.2.4 Opening/Closing/Saving a screen.*

Note: **If you attempt to create another project file without saving a newly created project file, the system asks if you wish to save the current file. If you click on the** | Yes | **button, the [Save As] dialog box appears. If you click on the** | No | **button, the system opens a new screen without saving the current project file.**

▼Reference◢ *1.2.2 ■ Saving a Project File under a Different Name*

■ Selecting an Existing Project

Select the Project Manger's [Project] menu - [Select] command, or click on

[Select] icon . When you select a project, the following setting screen appears:

Used to select the folder containing the target project file

Lists the current folder and existing project files

Displays the project file name selected from the list.
You can specify the project file by typing the file name.

Displays the project file's comment and the selected LT unit and Device/PLC

Used to select the project file type desired

◆ File Types

The only project file that can be selected is the one created with the LT Editor (*.lte).

Note: **Double-clicking on the file (project file: *.lte) itself in Explorer automatically starts LT Editor and opens the file.**

PROCEDURE	REMARKS
(1) Select the Project Manger [Project] menu's [Select] command, or click on [Select] **.**	
(2) Select a project file from the list that appears, or type the project file name. Select **"Factory A"** To type a file name via the keyboard, type the file name here.	To select a project file located in another folder, find a desired file from the "Look in: (File location)".
(3) Click on the [Open] **button to open the selected file.**	When you double-click on the file name selected in step (2), you can skip the [Open] command. ▽**Reference**△ To create a screen, refer to *1.2.4 Opening/Closing/ Saving a Screen.*

■ **Saving a Project**

When the data of an existing project file is changed, the changes will be automatically saved.

However, if you attempt to create a another new project file without first saving your current project file, the LT Editor will ask if you wish to save the current file. If you click on the [Yes] button, the [Save As] dialog box will appear.

▽**Reference**△ *1.2.2* ■ *Saving a Project File under a Different Name*

■ **Saving a Project File under a Different Name**

You can save an existing project file under a different name or with different LT type/Device/PLC settings.

PROCEDURE	REMARKS
(1) Select the [Project] menu - [Save As] command in the Project Manager.	
(2) The comment, LT type and Device/PLC of the currently opened project file are displayed. Enter the desired file name, and enter the items to be changed.	The file name can contain up to 255 characters (including the path-name and extension.) ⚠ **Important** ***Before changing the LT type, check the preset data, since the drawing area and functions vary depending on the type of the LT unit.*** ▼ Reference ◣ *4.2.6 Changing a Project's LT Type* ⚠ **Important** ***Once the Device/PLC is changed, you must change the addresses of the Parts, D-Scripts and alarms, and perform the LT system setup again.*** ▼ Reference ◣ *4.2.8 Changing Your Project's Device/PLC* ▼ Reference ◣ To open another project file, refer to *1.2.2 ■ Creating a New Project or ■ Selecting an Existing Project.* ▼ Reference ◣ To close LT EDITOR for Windows, refer to *1.2.5 Quitting LT Editor for Windows.*
(3) Click on the [Save] **button to save the file.** If a project file with the same name exists, LT Editor will ask if you want to replace (overwrite) the existing project file with the project file you are attempting to save. If so, click on the [Yes] button. If you do not wish to overwrite the existing project file, click on the [No] button.	

• **When a Vertical LT unit is replaced with the horizontal type, or vice-versa, the displayed screen will rotate 90° relative to the original data. In this case, you must edit the displayed data using the [Rotate] command. After editing, be sure to check the displayed data.**

Important

Example)

Horizontal type   **Vertical type**

1.2.3   Creating/Editing/Saving a Logic Program

To create a logic program, you must move from the Project Manager to the Logic Program Editor. Only one logic program can be created for one project.

■ Creating/Editing a Logic Program

When the Logic Program Editor is started, the logic program being created in the current project file is displayed.

PROCEDURE	REMARKS
(1) Select the Project Manager's [Control] menu-[Create/Edit Controls] command, or click on **.** The Logic Program Editor starts. 	
(2) Create/Edit a logic program. You can insert a rung and instructions as well as set I/O configuration. 	For details on logic program development, refer to the ***Logic Programming Operation Manual***.

■ **Saving a Logic Program**

PROCEDURE	REMARKS
(1) Select the Logic Program Editor's [File] menu-[Save(s)] command, or click on 🖫 . The logic program you are saving will replace the existing program.	After saving the program, the Logic Program Editor remains open. When saving a logic program, variables registered with the Logic Program Editor will be registered with the Symbol Editor as Logic symbols. ▼Reference▲ *4.2.6 Symbol Editor* ⚠ *Important* ***When variables are used in a drawing, be sure to make a drawing after saving a logic program.***

■ **Closing a Logic Program**

PROCEDURE	REMARKS
(1) Select the Logic Program Editor's [File] menu - [Exit] command.	You can also close the logic program by clicking on the x button at the upper right corner of the Logic Program Editor.
(2) The Logic Program Editor will close. If you attempt to close an updated logic program without saving it, the system asks if you wish to save the current program. If you click on the [Yes] button, the system saves the updated data. If you click on the [No] button, the system closes the Logic Program Editor without saving the updated data. ※ C:\Program Files\Pro-face\LT\database\A Manufacturing System ☒ (?) Do you want to save the changes to "C:\Program Files\Pro-face\LT\database\A Manufacturing System"? [Yes] [No] [Cancel] [Help]	When saving a logic program, variables registered with the Logic Program Editor will be registered with the Symbol Editor as Logic symbols. ▼Reference▲ *4.2.6 Symbol Editor* ⚠ *Important* ***When variables are used in a drawing, be sure to make a drawing after saving a logic program.***

> ### 1.2.4   Opening/Closing/Saving a Screen

To create a screen, you must switch from the Project Manager to the Screen Editor, and open a screen. This section describes the procedures for opening, closing, and saving a screen.

■ Opening a New Screen

PROCEDURE	REMARKS
(1) Select the Project Manger's [Screen/Setup] menu - [Editor] command, or click on [Screen]. The Screen Editor's opening screen will appear. 	When the Screen Editor has already been started, skip step (1).
(2) Select the Screen Editor [Screen] menu's - [New] command, or click on [ ]. **(3) Select the screen type.** 	Selecting the [Screen] menu's - [Open] command or clicking on [ ] and entering an unregistered screen number can also be used to open a new screen. Enter the screen number and title when saving the screen. ▼*Reference*▲ *1.2.4 ■ Saving a Screen under a Different Name*
(4) Click on the [OK] button to create the desired type of screen. A screen corresponding to the designated LT type will appear. 	Up to twenty screens can be simultaneously opened. Multiple types of windows can be opened on any one screen at the same time.

■ **Opening a Previously Saved Screen**

PROCEDURE	REMARKS
(1) Select the [Screen/Setup] menu's - [Editor] command, or click on 🖥 in the Project Manager. The Screen Editor's opening screen will appear.	When the Screen Editor has already been started, skip step (1).
(2) Select the [Screen] menu's - [Open] command or click on 📂.	
(3) Use this screen to select a screen name from the list, or select the screen type and enter the screen number. When checking the [Preview] check box, the selected screen image can be viewed in the dialog box.	When you double-click on the desired screen number in step (3), you can skip the operation of the OK button. If you enter a screen number that has not been registered in the list, a new screen will be opened and that number will be assigned to it. When selecting multiple screens, a screen with the smallest screen number of them will be displayed.

Preview Check Box

PROCEDURE	REMARKS

(4) Click on the [Open] **button to open the screen.**

The selected screen will open.

Note: **Up to twenty screens can be open at the same time.**
To select several screens simultaneously, while pressing the [Shift] **key, click on a screen and drag the mouse over desired adjacent screens; or, you can select screens individually by clicking on them while pressing the** [Ctrl] **key.**

■ **Saving a Screen**

PROCEDURE	R E M A R K S
(1) Select the [Screen] menu- [Save] command, or click on 🖫 in the Screen Editor The current screen will be saved, overwriting the previous one.	After the screen is saved, it will remain open. When you attempt to save a new screen, the [Save As] dialog box will appear. ▼Reference▲ *1.2.4 ■ Saving a Screen under a Different Name*

■ **Saving a Screen under a Different Name**

PROCEDURE	R E M A R K S
(1) Select the [Screen] menu - [Save As] command in the Screen Editor.	
(2) The type, number, and title of the current screen is displayed. You can change the setting of a desired item; however, the screen's type cannot be changed.	A "," (comma) cannot be used in a description.
(3) Click on the [OK] button to register the above settings. If a screen with the same number exists, the system asks if you want to replace the existing screen with the screen you are attempting to save. If so, click on the [OK] button. If you do not wish to overwrite the existing screen, click on the [Cancel] button.	After the screen is saved, it will remain open. If the screen is saved as a different screen number, the screen of the updated number will be displayed.

■ **Closing a Screen**

PROCEDURE	REMARKS
(1) Select the [Screen] menu - [Close] command in the Screen Editor. **(2) The screen will close.** If you attempt to close an updated screen without saving it, the system asks if you wish to save the current screen. If you click on the ⌈ Yes ⌉ button, the system saves the updated data. If you click on the ⌈ No ⌉ button, the system closes the screen without saving the updated data.	You can also close the screen by clicking on the ⊠ button at the upper right corner of the window (drawing area). When you attempt to save a new screen, the [Save As] dialog box appears. ▼*Reference*▲ *1.2.4 ■ Saving a Screen under a Different Name*

■ **Quitting the Screen Editor**

PROCEDURE	REMARKS
(1) Select the [Screen] menu - [Exit] command, or click on in the Screen Editor. **(2) The Screen Editor will close.** If you attempt to close the Screen Editor without first saving the currently edited screen, LT Editor asks if you wish to save the updated screen. If you click on the ⌈ Yes ⌉ button, LT Editor saves the updated data. If you click on the ⌈ No ⌉ button, LT Editor quits the Screen Editor without saving the updated data.	When you save a new screen, the [Save As] dialog box appears. ▼*Reference*▲ *1.2.4 ■ Saving a Screen under a Different Name*

1.2.5	**Quitting LT Editor**

■ Quitting LT Editor

P ROCEDURE	R EMARKS
(1) Select the [Project] menu - [Exit] command, or click on ⬚ Exit **in the Project Manager.** **(2) The Project Manger will quit.** If you attempt to close the Project Manager without saving the currently opened screen's updated data, LT Editor asks if you wish to save your project's data. If you click on the ⬚ Yes button, LT Editor saves the updated data. If you click on the ⬚ No button, LT Editor quits (closes) without saving the updated data. **Saving the screen** **Saving the Logic Program**	When you are working on the Screen Editor or the Logic Program Editor, quit the Screen Editor or the Logic Program Editor, or select the Project Manager. ▼*Reference*▲ *1.2.4 ■ Quiting the Screen Editor*

1.3   Project Manager

All LT Editor system level settings and functions are controlled via the Project Manager.

1.3.1   Project Manager Areas and Functions

Here, each of the Project Manager's features is explained. To begin working with LT Editor, simply click on the desired button.

a. **Title Bar:**

Displays the current project's file name and title.

b. **Menu Bar:**

Displays the menus used for the operation of LT Editor. When you select a desired menu using the mouse or keyboard, one of the pull-down menus described below will appear.

c. **Pull-Down Menu:**

When you select a desired item on the menu bar, its pull-down menu appears. These menus includes a variety of commands.

d. **Status Bar:**

Displays LT and Device/PLC as well as LT Editor operation related messages.

e. Function Buttons

These buttons indicate the LT Editor program's main functions (e.g. creating screens, alarms, printing, etc.). You can start each function by simply clicking on that function's button. You can also start these functions by selecting the corresponding command from the Project Manager's pull-down menu.

Creates a new project   Selects an existing project

Makes initial setting of the LT main unit

Monitors the logic program

Project

Creates a logic program with the Logic Program Editor

Logic Program

Displays a list of variables

Sets I/O configuration

Editor

Creates a screen with the Screen Editor

Creates alarms with the Alarm Editor

Transfer

Transmits screen and logic program to the LT   Quits the LT Editor

1.4   Logic Program Editor

Logic programs are created with the Logic Program Editor.

The online help provides you with detailed information on the Logic Program Editor.

Also, the "Logic Programming Operation Manual" explains procedures using tutorials. It also explains instructions and settings required for combining the LT main unit with the LT Editor.

1.4.1   Logic Program Editor Item Names and Functions

Here, basic item names and functions of the Logic Program Editor main window are explained.

▼*Reference*▲ *For details, refer to online help.*

a. Title Bar

Displays the project file name, screen number and title.

b. Menu Bar

Displays the menus used to operate LT Editor. When you select a desired menu using the mouse or keypad, the pull-down menu (c) appears.

c. Pull-down Menu

When you select a desired menu from the menu bar, the pull-down menu appears. This menu includes various commands.

d. Tool Bar

The Tool Bar provides icons representing such commands as Creating/Editing a Logic Program and RUN/STOP. Clicking one of these icons performs that command. The Tool Bar can either be hidden or displayed.

e. Programming Area

Creates a logic program.
The entire program may not display depending on the size of the window or program. In such cases, use the window's scroll bar to change the display area.

f. Status Bar

Displays information on the edited logic program and messages concerning the operation.

1.5 Screen Editor

To create a screen, start the Screen Editor via the Project Manager.

There are three types of screens used for different purposes; Base Screen, Mark Screen and Image Screen.

Screen Type	Screen Number	Contents	Maximum Size per Screen
Base(B) Screen	B1 to B8999	This screen is displayed when the LT is in RUN mode. Shared drawings and Active images loaded on another base screen can be used. One part of a Base Screen can be registered as a window.	Approx. 16 KB
Mark (M) Screen	M1 to M8999	Used to create marks and foreign characters on a 48 x 48 dot screen. These marks and foreign characters are displayed as still or Active images on a Base Screen.	Approx. 576 bytes
Image (I) Screen	I1 to I8999	Bitmap image data can be registered here as LT screen data. Image screens are displayed as still or Active images on a Base Screen.	Approx. 58 KB
Window (U) Screen	U1 to U8999	This screen is used to register screens you want to display in the window. The window is displayed on the base screen.	Approx. 16 KB

Note:
- *Although screen files can be numbered from 1 to 8999, the maximum number of screens that can be created for and used by a LT depends on your PC's hard disk capacity and the amount of RAM (memory) available.*
- *The number of screens that can be transferred to the LT will depend on how much internal memory the LT has. The actual screen size and total number of transferable screens can be viewed in the "Project Manager" window by selecting the [Project] menu, and then [Project Information].*

▼Reference▲ *4.4.1 ■ Project Information*

> **1.5.1**   **Screen Editor Item Names and Functions**

The names and functions of the LT Editor editor's screen items are as follows:

a. Title Bar

a. Title Bar

Displays the project file name, screen number and title.

b. Menu Bar

Displays the menus used to operate LT Editor. When you select a desired menu using the mouse or keypad, the pull-down menu (c) appears.

c. Pull-down Menu

When you select a desired menu from the menu bar, the pull-down menu appears. This menu includes various commands.

d. Drawing Area

Here, you can create a screen for your LT unit. The size of the screen you see here is designated via the "Display Type" setting you entered when you first created the project file.
Depending on the size of your PC's display, the screen's entire display area may not be displayed. In this case, simply scroll up or down to view the entire screen.

e. Screen Center Mark

Indicates the center of the screen. This mark is not displayed when the data is sent to the LT unit.

f. Grid Points

Used as reference points when you draw or paste an object in the drawing mode. Grid points will not be displayed on the LT unit's screen. The Option area's "Snap" function allows you to position your screen objects using a pre-made grid. You can also set the interval and display ON/OFF status of the grid points.

▽ *Reference* △ *2.7.1 Grid/Snap*

g. Status Bar

Displays information related to the current screen and provides messages explaining the screen operation you are currently performing.

Coordinates of current mouse position

Amount of Screen memory currently used (Ratio of used screen area to entire screen)

Description of the currently selected command

Project's Device/ PLC

Display area's magnification/ reduction ratio

h. Tool Bar

The Tool Bar provides easy to use icons for drawing and editing. Clicking on one of these icons performs that command. The Tool Bar can either be hidden or displayed, and individual Tool Bar areas can be moved freely around the Screen Editor screen, i.e. top, bottom, left, or right.

The following Tool Bar areas are available:

> Main Tool Bar
> Edit Tool Bar
> Draw Tool Bar
> Option Tool Bar
> Grid/Snap Tool Bar
> Parts Tool Bar
> Parts State Change Tool Bar

i. Zoom Box

Shows the cursor's current position at three times magnification.

j. Selection Tool Box

Used to select objects to be edited (Parts and figures). Using the commands included in this tool box, you can select objects using a variety of methods.

k. Screen Data List

Lists the settings and layout conditions of the objects (Parts and figures) that have been arranged on the screen. You can select a desired object from the list.

l. Parts Palette

Parts such as switches, lamps and graphs are placed on a tabbed palette (except for the keypad, alarms, File Name Display, Logging Display, Picture Display, and Window parts).

To place parts on the drawing screen, simply select the desired part from the palette and place it on the screen with drag & drop operation. Only one part can be selected per operation.

1.5.2   Display Area (50%, 100%, 200%)

You can enlarge or reduce the drawing area by selecting a magnification/reduction ratio.

To change the display area, select the ⊕ or ⊖ icon on the tool bar, or select the [50%], [100%], or [200%] command from the [View] menu.

Zoom out   Zoom in

Zoom out: Used to reduce the current display area to 50%.

Zoom in: Used to enlarge the current display area to 200%.

Note: **In the [50%] display mode, the created screen data is reduced. In this case, the displayed screen data may be different from the actual data. We recommend you to use a [100%] or larger display area.**

1.5.3   Tool/Icon Display

The Parts tool box, tool bar, status bar, and parts palette can be designated as either shown (displayed) or not shown (not displayed). Each time you select the [View] menu's [Screen Data Box], [Status Bar], [Zoom Box], or [Parts Palette] as well as the [Tool Bar] command's [Main], [Edit], [Draw], [Option], [Grid/Snap], [Parts], [Parts State Change], or [String Table] subcommands, these View/Hide settings will toggle ON or OFF.

1.6 LT Editor Manuals and Help

While you are learning how to use the LT Editor software, please refer to the following learning aids:

· Related User Manuals
· On-line Help Topics
· Tips Screen
· Digital's Home Page

For the help concerning the operation of the Windows operating system, see the Windows software's manuals and help screens.

■ Using LT Editor Manuals

The following manuals have been created for the LT Editor software.

CD Jacket: Describes LT Editor's installation procedures and system requirements.

Drawing Operation Manual:Provides detailed explanation of operating procedures for all LT Editor's commands except those for logic program development.

Logic Programming Operation Manual: Provides tutorials to help you to learn operating procedures of Logic Program Editor. Also describes operation of the LT main unit as well as instructions and variables used in logic programs.

Parts List: Describes the LT Editor's pre-made Parts and symbols.

Device/PLC Connection Manual: Describes the methods for connecting the LT to the external devices of various manufacturers and system requirements.

■ Using the Help Feature

If you have any problems or questions during LT Editor operation, you can view the explanations for each feature and setting via each window's Help button, or from the main menu's Help feature.

The Help explains settings of each window and dialog box, instructions and functions of a logic program as well as each driver's setting.

■ Using the Tips Screen

The Tips screen displays one-point descriptions of the new features upon the startups of the LT Editor.

■ Using the Home Page

You can obtain the latest LT Editor information by addressing the Digital Electronics Corporation Home Page on the LT Editor screen.

1.6.1   Browsing Help Topics

To display the help screen, select the [Help] menu or click on the [Help] button in the dialog box.

> ⚠️ **Important**
>
> · *When multiple screens are loaded or many Parts have been registered on the screens, the PC's system memory may not be sufficient to display the help screen.*
>
> · *If you jump from one topic to another on the help screen, an error message may be displayed. When this happens, simply quit and then re-start help.*

■ Searching for a Topic and then Display Help

Select the [Help Topics] command from the [Help] menu, or press the [F1] key. A list of help topics will be displayed.

You can search for a topic by either trying to find it from the table of contents, or entering a keyword for that topic.

◆ Searching for a Topic from the Contents Menu

To select a topic from the contents menu, double-click on the [Contents] tab. Follow the screen instructions to search for a desired topic.

◆ **Searching for a Topic by a Keyword**

To enter a keyword, click on the [Index] tab.
Search for a desired topic according to the instruction indicated on the
screen.
(When you enter initial characters of the keyword, the topics specified with
these initial characters are also automatically listed)

■ Calling up Help from a Dialog Box

When you click on the [Help] button in the dialog box or press the [F1]
key during execution of a command, a description of the currently-executed
command will be displayed.

  1.6.2   Viewing the Tips Screen

To view the Tips screen, select the [Tips] option from the [Help] menu on
the Project Manager or the Screen Editor.

1.6.3   **Browsing the Home Page**

The procedure to connect to Digital Electronic Corporation's home page is described here.

> ⚠ **Important**
>
> · **To browse the home page, you must have hardware environment to access the Internet. You also must have a browser to view the home page, and subscribe to an Internet provider.**
>
> · **Please understand that Digital Electronics Corporation cannot respond to any questions about your Internet connection.**

Operating procedures

[Help] → [Connect to Home Page] → Add/Edit/Delete → Click on the `Connect home page` button.

Overview of the Home Page Connection screen:

Used to add a home page address

Used to edit a registered home page address and title

Used to delete a registered home page address

Displays the registered home page address (title)

Used to connect to the specified home page

■ Registering a Home Page Address

The address of Digital Electronics Corporation's Home Page has been preregistered in your LT Editor software. When you click on the `Add List` button, the address setting dialog box appears.

▽ **Reference** △ *■ How to Register a Home Page Address*

■ Deleting a Home Page Address

Any registered home page address can be deleted. When you select the home page address to be deleted and click on the `Delete` button, the confirmation dialog box appears. If you click on the `OK` button, the selected home page address will be deleted. If you click on the `Cancel` button, the deleting operation will be canceled.

■ **Editing a Home Page Address**

The registered home page address or title can be changed. When you select the home page address to be edited and click on the ⬚ Edit ⬚ button, the address setting dialog box appears (same as for the home page addition procedure), enabling you to change the title and address of the home page. If Digital Electronics Corporation's home page address is changed in the future, please edit the currently registered address.

■ **Connecting to the Home Page**

PROCEDURE	REMARKS
(1) Select the [Help] menu - [Connect to Home Page] command in the Project Manager.	
(2) Select the target home page address.	
(3) Click on the ⬚ Connect home page ⬚ **button to start connection.** The browser is started, and you will be connected to the home page.	If a browser has not been specified, the following dialog box appears. Specify a browser, and re-start the connecting procedure.

■ **How To Register a Home Page Address**

Procedure	Remarks
(1) Select the [Help] menu - [Connect to Home Page] command in the Project Manager.	

(2) Click on the [Add List] button.

(3) Enter a home page title and address to be registered and click on [OK].

The specified home page address will be registered.

Memo

2 ▶ CREATING BASE SCREENS

To create Base screens, the Editor area's Part, Draw and Menu Bar commands can all be used. Also, Edit commands can be used to modify any Parts or objects that you have created. In addition to editing these screen objects, the procedures for registering Library Items and Windows are also explained.

2.1 Parts

Parts such as Switches, Lamps, and Graphs can be placed on Base screens.

Each Part's attributes such as setting Addresses and colors will be designated via the dialog box. Switches and Lamps can be selected while viewing their images via the Browser. After designating all the necessary Part attributes, decide their position and size on the object drawing area.

Parts can be placed on the drawing screen simply by selecting the desired part from the palette and placing it on the screen with drag & drop operation.

The [Parts] menu's commands are effective only on Base screens.

Usage Pattern

•[Parts] → Decide on a type of Part → Select the specific Part from the Browser → Specify its Attributes → Place it on the Screen

or → Select a desired icon from the Parts Tool Bar.

•Parts Palette → Select the desired part → Place the part on the Screen with drag & drop operation → Specify the Attributes

---

■ LT Editor Part Type Summary

Each of the Parts used in LT Editor is listed below.

Icon	Name	Function	Reference
	Bit Switch	Used to change a External Device's Bit Address data.	2.1.1 Bit Switches
	Word Switch	Changes a External Device's Word Address data.	2.1.2 Word Switches
	Function Switch	Used to go back to the previous screen, to switch screens, and to reset the LT.	2.1.3 Function Switches
	Lamp	Turns ON or OFF, according to whether the External Device's Monitor Bit is ON or OFF.	2.1.4 Lamps
	Bar Graph	Displays the External Device's Word Address data in a bar graph.	2.1.5 Bar Graphs
	Pie Graph	Displays the External Device's Word Address data in a pie graph.	2.1.6 Pie Graphs
	Half-Pie Graph	Displays the External Device's Word Address data in a Half-Pie graph.	2.1.7 Half-Pie Graphs
	Meter	Displays the External Device's Word Address data in a Meter graph.	2.1.8 Meters
	Trend Graph	Displays the External Device's Word Address data as absolute values in a trend graph.	2.1.9 Trend Graphs
	Keypad	Used to enter a External Device's Word Address data.	2.1.10 Keypads
	Keypad Input Display	Displays data input via the keypad.	2.1.11 Keypad Display

Icon	Name	Function	Reference
	Alarm Display	When monitored Bits are turned ON, a list of "Basic" Alarm summary messages appear that have been previously registered in the Alarm Editor.	2.1.12 Alarm Displays
	Filing Data Display	Displays data registered in the Filing Data list by specifying the corresponding file number.	2.1.13 File Name Display
	Logging Display	Displays External Device data loaded in the data logging settings by specifying the address for the corresponding block number.	2.1.14 Data Logging Display
	Numeric Display	Displays the External Device's Word Address numeric data as an absolute value.	2.1.15 Numeric Displays
	Message Display	Displays a previously registered message, according to External Device Word Address data changes. A maximum of 16 messages can be displayed in a single Message Display.	2.1.16 Message Displays
	Date Display	Displays the current date, using the LT's internal calendar.	2.1.17 Date Displays
	Time Display	Displays the current time, using the LT's internal clock.	2.1.18 Time Displays
	Picture Display	Displays a single registered Library image (only graphic data), according to External Device Word Address data changes. A maximum of 16 different Library images can be displayed in a single Picture Display. (One at a time)	2.1.19 Picture Displays
	Window Parts	Windows created on the Window Screen (U) can be called up on the Base Screen (B).	2.1.20 Window Parts

■ **Entering a Comment**

If desired, a comment can be entered for a Part.

Up to 20 alphanumeric (single-byte) characters can be entered

Applies the device comment

◆ **Reflection of a Device Comment**

If you click on the ▦ [Apply Device Comment] button after entering an address, the device comment entered using the Symbol Editor is automatically searched for, and the comment corresponding to the entered device appears in the Description field.

▽ *Reference* △ *4.2.6 Symbol Editor*

■ **Entering Addresses**

Here, Addresses that are operated for Parts' functions and that are monitored are designated.

A variable to be used in a logic program (Logic symbol) can be designated as a Part's address.

▼Reference◣ *4.2.6 Symbol Editor*

! *Important* ***When a function requires consecutive addresses and a variable (Logic symbol) is used as a start address, an integer array must be designated.***
For an integer array, an appropriate size required for consecutive addresses needs to be allocated.

Enter the address data here

Note: • **The address to be entered varies depending on your LT and external device. Note that the sample configuration in this manual is just an example.**

◆ **Entering from a keyboard**

Click on the address entering field, and the cursor will appear there, which indicates data entry is now effective. Then, enter device and address data via the keyboard.

◆ **Entering from a pull-down list**

Click on the 🔽 box next to the Address entering field, and a pull-down list appears including symbols and Logic symbols selected via the Symbol Editor and device comments together with corresponding Addresses. Selecting a symbol, Logic symbol or device comment from the list designates an Address.

◆ **Entering from the Address Keypad**

Click on the [Address Keypad] icon, and the Address Keypad will appear, allowing you to enter numeric data and addresses on the screen via the mouse.

When designating a variable for a logic program (Logic symbol) by bit, use the Logic Symbol Keypad that will be displayed by clicking the [Logic] button in the Address Keypad window.

Activates the Address Keypad

[Address Keypad]

To move the Address keypad to the desired position, drag its title bar.

To close the pop-up keypad, click here.

To display the device names in a list, click here.

Display

Backspace key

Clear key

Hexadecimal number entry key

Enter key

Displays the Logic Symbol Keypad

[Logic Symbol Keypad]

A pull down list shows Logic symbols.

Designates a Logic symbol by bit

Returns to the Address Keypad

The Logic symbol will be accepted with a click on the Enter key.

Note: **A Part's specified address can be entered so that it is displayed during Base screen creation.**

▼*Reference*◣ *2.7.2 Property Settings*

Regardless of whether addresses are designated as either displayed or not displayed during Base screen creation, they will not be displayed on the LT panel after screen transfer.

■ **Selecting a Part Shape**

Click on the General Settings Area's [Browser...] button in the dialog box, and the Shape Browser (hereafter called "Browser") will be displayed. The Browser's Part Shapes are stored in a Part File (PDB file), separate from the main Project File (LTE file). Searching through different pre-made Part files allows you to easily find useful Part Shapes for almost any application.

Click on a Part number and then the [OK] button, or double-click directly on the Part number to select a Part Shape. (Browser disappears)

Note: **Part File and Part Shape lists for each file are included in the LT Editor Parts List Manual.**

The ID number of the Part Shape is displayed here. Reverse video (highlighting) indicates it is selected

Clicking here scrolls through the Part Shapes in this file

Calls up a list of the other Part files

Shows the ID number of the currently selected Part Shape

Shows the Path-name of the currently open Part File

◆ **Parts Files**

Click on the [Parts File...] button, and a list of the Part files will appear. After clicking on a Part File, the information displayed will change to reflect that file. Next, click on the [Open] button and the selected PDB File's Part Shapes will appear in the Browser.

Moves to the next higher file directory level

Creates a new folder

Shows the currently open folder

Displays file names and details

Lists the names of all the PDB files in this folder

Displays file names in summary form

Shows the currently selected PDB file's comment

Shows the name of the currently selected PDB file. A name can also be entered here to select a file

Note: **When the LT Editor software is first installed, all Part Files will be included in a folder named PDB and automatically installed in the same directory/ folder as the LT Editor program. If desired, these Part Files can be moved to other folders and, to find a Part File that has been moved, use the [Look in:] area to display Part Files located in other folders.**

■ Selecting Colors

Specify Part colors using the Shape/Color setting screen. The setting items will differ depending on the Part, i.e. the border type, ON/OFF states, graphs, and label colors.

Tiling patterns can be selected for some of the Parts, Lamps, and Graphs.

◆ Colors

There are 8 colors available in the color bar. Use this bar to select the foreground (Fg), background (Bg) and other colors.

Note: **On a monochrome LT screen, black, blue, green, and cyan will be displayed as black (same as background); red, magenta, yellow, and white will be displayed as white.**

	BK	BL	GR	CY	RD	MG	YL	WH
Color LT unit	BK	BL	GR	CY	RD	MG	YL	WH
Monochrome LT unit	**Black (not displayed)**				**White (displayed)**			

◆ **Blink**

When the Blink (Blk) Check Box checked ☑ , the color bar is displayed in a darker color and the specified Part will blink on the LT's screen.

Fg ■■■◻◻■■◻◻ (Blk ☑) ──── **Blink Check Box**
Bg ■■■◻◻■■◻◻ Blk◻

Note: **When either text characters or Mark backgrounds (Bg) are specified as Black, and the Blk (Blink) feature is turned on, they will become transparent; so that even when overlaid on other objects, the rear object's color is also visible. This function is useful when overlaying text on Switches, Lamps, and other objects.**

For example:

Label

Switch→ RUN ⇨ RUN

Bg ■■■◻◻■■◻◻ Blk◻   Bg ◻■■■■■■■◻ Blk ☑

Specifying a Label's background color as Black does not allow you to see the background color.

However, specifying the Label's background color as Black and turning on Blk (blink), causes the background color to become visible.

◆ **States**

Only Parts which can have two states are displayed with this feature. Display colors for Parts can be specified separately for each state. Click on either state button to select it, and specify that state's color using the color bar.

■ Alarm Settings

In both graph and numeric value displays, Alarms can be set up.
First, click on the [Alarm Settings] tab at the top of the Dialog box. When checking the Alarm Display box (Check mark ☑ appears), the Alarm setting items will appear.

Sets the Alarm value's Format to fixed or variable

Sets the minimum and maximum Alarm values

Sets the Alarm colors used

◆ Alarm Type

The Alarm value can be specified as either direct (fixed value) or indirect (variable value) by simply clicking on the appropriate circle.

◆ Alarm Range

Here, you can specify the maximum and minimum Alarm values.
When the Alarm value has been specified as indirect, the maximum and minimum values can also be specified as indirect. In this case, the Word Address number used to store these values will be automatically assigned continuously from the Word Address currently specified.
The following example uses "n" to denote where the Word Address' display data is stored:

<Relationship between display data's storage address and Alarm register address>

With 16 Bit data

n	Display Data
n+1	Data value - Max.
n+2	Data value - Min.

With 32 Bit data

n	Display Data
n+1	
n+2	Data value - Max.
n+3	
n+4	Data value - Min.
n+5	

(e.g.) When the Word Address is set to "D00000"

Word Addresses are automatically allocated in sequence, starting from the Address designated

(e.g.) When the Word Address is set to "Symbol" (Logic Symbol)

⚠ Important ***When a variable (Logic symbol) is used as a start address, an integer array must be designated. For an integer array, an appropriate size required for consecutive addresses needs to be allocated.***

◆ **Alarm Color**

Here, you can select the colors used for an Alarm display.

▽**Reference**△ *2.1 Parts* ■ *Selecting Colors*

■ Creating Labels

Here, a Label means the text characters shown on the faces of the Switch and Lamp button Parts. Labels can be registered via the Part's Setting dialog box.

As with Parts, Label display colors can be created for each of a 2-state Part's states; up to 4 lines of text can be used for each state.

<OFF state>   **<ON state>**

When a lamp's Text Display changes
(This Switch's ON/OFF colors are also selected)

Note: **The Part must be large enough to display the entire Label.**

When the Part has two states, the appropriate Label can be selected with these buttons switched On/Off.

Enter the characters here

Copies the characters in the Description field to the label for the selected state.

Copies the characters to the label for the Off state.

Select the character's size

Selects the character's type

Settings required only when the text extends to more than one line.

Select the label's color here

◆ **Label**

Here, you can type in the text displayed on a button. When typing in text, press the ⏎ key to move to a new line. When the [Tracking] check box is checked ☑ (enabled), after the Part has been placed on the screen, if the Label's size or position is changed, for either state, the alternate state's Label size and position will be also changed. If, however, the Label's size and position need to be specified independently for each state, DO NOT check ☐ this box.

▽ **Reference** △ *2.3.3 Scaling Up/Down*

◆ **Copy from Description**

The characters entered in the Description field are copied to the label in the selected state without changing the character size.

◆ **Copy to Off (On) state**

When the state is On, the characters entered in the label are copied to the label in the Off state without changing the character size. When Off, the characters are copied to the label in the On state.

◆ **State**

States are displayed only for Lamps, and for those switches with two states (ON and OFF). The text displayed for each state can be specified independently. Simply click on either state button to specify its text and colors.

◆ **Character Size**

Specifies the size of character.

▽ **Reference** △ *2.2.9 Text*

◆ **Style (Font)**

Specifies the type of character (Normal, Bold, Raised) used in each Label.

▽ **Reference** △ *2.2.9 Text*

◆ **Text Color (ON/OFF)**

Specifies Label colors.
The default settings are Fg: White, and Bg: Transparent mode (Black + Blk).

◆ **Line space**

When the text extends to more than one line, set the line space.

◆ **Alignment (Justification)**

When the text input for a Label exceeds one line, the Alignment icons will appear. Select Left, or Right justification, or Centering.

Left-justified Centered Right-justified

■ **ID Numbers**

When creating a Part, an ID number is automatically assigned to the Part before it is placed on the screen. This number shows how many of that kind of Part were previously placed on the current screen. When a Part is deleted from a screen, all following Part numbers will be adjusted downwards.

Example of an ID number

BS-010

Indicates that this Part is a Bit Switch (Varies according to the Part)

Indicates the placement/ creation order of the Part; in this case, it is the 10th.

The ID number is displayed in the title bar at the top of the Setting dialog box.

Note: **The ID number can be entered so that it is displayed during Base screen drawing.**

▽ *Reference* △ *2.7.2 Screen Property Settings*

Even if the ID number is entered to be displayed during Base screen drawing, it will not be displayed on the LT panel after screen data transfer.

<ID Number List>

Part Name	ID Number
Bit Switch	BS-**
Word Switch	WS-***
Function Switch	FS-***
Lamp	LA-***
Bar Graph	BA-***
Pie Graph	PI-***
Half-Pie Graph	HP-***
Meter	MT-***
Trend Graph	TR-***
Keypad	KE-***
Keypad Input Display	KD-***
Alarm Display	AL-***
File Name Display	FD-***
Data Logging Display	LG-***
Numeric Display	ND-***
Message Display (Operation Mode: Bit)	MB-***
Message Display (Operation Mode: Word)	MW-***
Date Display	DD-***
Time Display	TD-***
Picture Display (Motion mode: Bit)	LB-***
Picture Display (Motion mode: Word)	LW-***
Window Parts	WI-***

■ Maximum Number of Automatically Created Part Libraries

When a Part is used in a project, a Part Library will be automatically created in preparation for data transfer. The number of Part Library items are limited to 6000 per project. If this number exceeds 6000, all Parts in excess of 6000 cannot be transferred to the LT. To avoid this, please remember the following:

1. Automatic Library creation will be performed follows: (per screen)

     Switches: 2 (only switches with the Monitor function selected)
     Lamps: 2
     Messages: 2 to 16 (depending on the number of states used)
     Picture Displays : 2 to 16 (depending on the number of states used)
     Trends: 1 to 20 (depending on the number of channels)

   However, Part Libraries using the same Parts (i.e. Part's that are the same size, same attributes, and without labels or other items) will be used commonly.

   For example:

     When 30 Switches (Monitor function is selected) and 20 Lamps are placed on a single Base screen, $(30 \times 2) + (20 \times 2) = 100$ Part Library items will be automatically created. Therefore, 60 of these size screens can be used in one project('s data).

2. When using the same Parts for multiple Base screens, register the Part on one Base screen and then place it other Base screens using the Load Screen function. Thus, when multiple Base screens use those Parts, only one Part Library will be used, thereby reducing the Project File's size.

■ Placing a Part in Position

After all of a Part's attributes have been entered or selected, click on the desired position on the screen to place the Part.

PROCEDURE	REMARKS
(1)After all of a Part's attributes have been entered or selected, click on the [Place] **button.** The Part's outline will appear on the Base screen, next to your cursor. [Place] [Cancel] [Help]	
(2)Click on the point where the Part's top left corner is to be placed. The selected Part will then appear on the screen.	
(3)Adjust the Part's size, if desired. Click on the Part to select it, and drag any one of the handles to change the size of the Part. To change the size of a Part, move the cursor to a Part "handle" and click, then drag the "handle" to re-size the Part, and click again.	▽*Reference*△ *2.3.3 Scaling Up/Down* After placing the Part, double-clicking on it automatically brings up its Attribute Setting dialog box. ▽*Reference*△ *2.3.15 Changing Attributes*

Note: **Depending on the Part, when scaling up or down, one dot error may occur in the frame width.**

E.g.)   9   10

12345

> **2.1.1**   **Bit Switches**

Here, the creation of a touch panel switch, used for turning a specified Bit ON or OFF, is explained.

⚠️ *Important*   ***If the LT unit is Type C, Bit Switches with the Monitor function selected will not be displayed on the LT unit after the Project File transferred unless the LT has been connected to a external device.***

■ **Bit Switch [General Settings] Attributes**

Enter comment data here

Image of the currently se-lected Part Shape

Calls up the Part Shape Browser, where different Part Shapes can be selected

Sets the switch's function

Enter the Bit Switch Address

When creating a Bit Switch with two states, check this box and enter the alternate Bit Switch Address below

◆ **Operation Bit Address**

Here, the Bit Address data controlled by the Switch is input.

◆ **Monitor Bit Address**

Only after the Monitor check box is checked can the Monitor Bit Address used to change the Switch's display setting be entered. The Switch's state (ON/OFF) display can be specified so that it will change according to changes in this Bit Address. Addresses input in the Bit Address area can also be done here.

Appears only when creating a Bit Switch with two states. Toggles the switch's state either ON or OFF, allowing you to set the attributes of each state.

After entering the Bit Address, if you attempt to perform another area's operation before entering the Monitor Bit's address data, the dialog box shown below will appear. Clicking on the [Yes] button automatically inputs the Bit Address's data into the Monitor Bit Address. To enter a different address, click on the [No] button and input the desired address.

◆ Function

The Bit Switch functions are as follows.

Bit Set:	When the Bit Switch is pressed, the Device/PLC's designated Bit Address is turned ON. This state continues (i.e. remains ON) even after the switch is released.
Bit Reset:	When the Bit Switch is pressed, the Device/PLC's designated Bit Address is turned OFF. This state continues (i.e. remains OFF) even after the switch is released.
Momentary:	Only while the Bit Switch is pressed and held is the specified Device/PLC Bit Address turned ON. Thus, when the switch is released, the specified Bit Address is turned OFF.
Bit Invert:	Every time the Bit Switch is pressed, the Device/PLC's designated Bit Address state is changed (from ON to OFF, or from OFF to ON).

■ Bit Switch [Shape/Color] Attributes

Here, the Switch's border color (Frame), ON/OFF state colors (On Color, Off Color), and pattern can be selected.

▼**Reference**▲ *2.1 Parts* ■ *Selecting Colors*

The color and pattern settings available will differ depending on the switch's settings.

■ Bit Switch [Label] Attributes

Here, the text of the Label to be displayed on the Switch button is entered.

▼**Reference**▲ *2.1 Parts* ■ *Creating Labels*

■ Bit Switch [Extend] Attributes

Set up the Interlock and Buzzer functions.

◆ Interlock

Only when a bit designated via Interlock Address is in a state that has been selected via [Touch available condition], the switch becomes effective. Whether the switch is effective in ON state or in OFF state is selectable here.

Touch Available Condition	Interlock Address Status	Touch Available/ Not Available
Bit ON	ON	Touch Available
	OFF	Touch Not Available
Bit OFF	ON	Touch Not Available
	OFF	Touch Available

◆ Buzzer

Select ON or OFF for the buzzer sound.

When buzzer setting is enabled, the buzzer sounds while the touch switch is being pressed.

◆ One-Shot

Enable/disable the "One-Shot" feature.

This setting can be enabled only when "Momentary" mode is selected in the "Function" area in the "General Settings" tab. When the "One-Shot" feature is enabled, the buzzer will sound briefly only at the moment the touch switch is pressed.

■ **Placing a Bit Switch**

An example of how to place a Bit Invert switch is shown below.

First press of the Switch sets M0016   **The next press resets M0016**

| PROCEDURE	REMARKS
(1) Select the [Parts] menu - [Bit Switch] command, or click on the ▤ icon.	
(2) In the [General Settings] screen, input the Bit Address and select the Bit's Function.	When the Change State function selected, after entering the Bit Address, if you attempt to perform another area's operation before entering the Monitor Bit Address, the dialog box shown below will appear. Click on the [Yes] button to input the same address as used for the Bit Address. To enter a different address, click on the [No] button and input the desired address.

Enter **M0016**

When the switch's state can change, click here

Select the **Bit Invert** function

(3) Select a Part Shape from the Browser.
Specify settings for Shape/Color, Label and Extension Settings if necessary.

▼ Reference ▲ *2.1 Parts* ■ *Selecting a Part Shape*

(4) After all of a Part's attributes have been entered or selected, click on the [Place] button.

The Switch's outline will appear on the Base screen, next to your cursor.

PROCEDURE	REMARKS
(5) Click on the point where the Switch's top left corner is to be placed. If desired, use the Switch's handles to alter its size.	To cancel the placement, click on the ⌴ icon. ▽ *Reference* △ To change the Part's size, refer to *2.3.3 Scaling Up/Down.* Double-clicking on any Part placed on the screen automatically calls up that Part's Attribute Setting dialog box. ▽ *Reference* △ *2.3.15 Changing Attributes*

2.1.2 **Word Switches**

Here, a touch panel switch for setting data to a specified Word Address can be created.

■ **Word Switch [General Settings] Attributes**

Enter Comment data here

The Word Switch's image appears here

Calls up the Part Shape Browser. Parts can be selected directly from the Browser

Enter the Word Address you wish to use

Enter the data for the Switch to send to the Word Address

Select the Switch's function

◆ **Word Address**

Here, the desired Word Address is entered.

◆ **Constant**

Here, number registered to the Word Address is input. The data format is Decimal (Base 10), and the input range is from -32768 to 32767.

◆ **Function**

The Word Switch's functions are as follows:

Word Set: When the Word Switch is pressed, constant data is written to the Device/PLC's designated Word Address. Fixed or default values will be written to the timer, counter, etc.

Add/Sub: Every time the Word Switch is pressed, the Data value is added to the data currently in the Device/PLC's designated Word Address, and the result is then written to the Device/PLC's address. If a Data value is positive, the function will increment, and if it is negative, it will decrement.

Digit (ADD): Every time the Word Switch is pressed, the designated decimal place's data will be added by the Constant's value. The result will not be carried up to the next digit, so "9" simply rolls around to "0". Select the data format from Bin and BCD.

Digit (SUB): Every time the Word Switch is pressed, the designated decimal place's data will be subtracted by the Constant's value. The result will not be carried down to the lower digit, so "9" simply rolls around "0". Select the data format from Bin and BCD.

■ **Word Switch [Shape/Color] Attributes**

Here, a Word Switch's color, and pattern can be selected.

▽ *Reference* △   *2.1 Parts* ■ *Selecting Colors*

The color and pattern settings available will differ depending on the Switch's settings, such as its shape and Change State condition.

■ **Word Switch [Label] Attributes**

Here, the text characters shown (engraved) on the Switch button face are input.

▽ *Reference* △   *2.1 Parts* ■ *Creating Labels*

■**Word Switch [Extend] Attributes**

Here, the interlock and the buzzer can be set as shown below.

Select the Interlock function state

◆ **Interlock**

Only when a bit designated via Interlock Address is in a state that has been selected via [Touch available condition], the switch becomes effective. Whether the switch is effective in ON state or in OFF sate is selectable here.

Touch Available Condition	Interlock Address Status	Touch Available/ Not Available
Bit ON	ON	Touch Available
	OFF	Touch Not Available
Bit OFF	ON	Touch Not Available
	OFF	Touch Available

◆ **Buzzer**

Sets the buzzer to ON/OFF

■ Placing a Word Switch

An example of how to place a Word Set Switch is shown below.

When the button is pressed, 34 is sent to D00001

PROCEDURE	REMARKS
(1)Select the [Parts] menu - [Word Switch] command, or click on the ▓ icon.	
(2)In the [General Settings] area, input the Word Address and Constant data, and select a function. Enter **D00001** Enter **34** Select **Word Set**	
(3)Select a Part Shape from the Browser. Specify settings for Shape/Color, Label and Extension Settings if necessary.	▼*Reference*▲ *2.1 Parts ■ Selecting a Part Shape*
(4)After all of the Part's attributes have been entered or selected, click on the ⎡ Place ⎤ **button.** The Switch's outline will appear on the Base screen, next to your cursor.	

P ROCEDURE	R EMARKS
(5)Click on the point where the Switch's top left corner is to be placed. If desired, use the Switch's handles to alter its size.	To cancel the placement, click on the ⌧ icon. ▼ **Reference** △ To change the Part's size, refer to ***2.3.3 Scaling Up/Down*** Double-clicking on any Part placed on the screen automatically calls up that Part's attribute settings. ▼ **Reference** △ ***2.3.15 Changing Attributes***

2.1.3   **Function Switches**

Here, a touch panel with special functions can be created.

■ **Function Switch [General Settings] Attributes**

Enter Comment data here

The Function Switch's image appears here

**Calls up the Part Shape Browser. Parts can be selected directly from the Browser**

Select the Switch's operation

When "Go To Screen" is selected, the (Go To) screen's number and data format must be entered

◆ **Function (Switch Operation)**

The Function Switch's attributes are as follows:

Previous Screen:	When the Switch is pressed, the currently displayed screen on the LT will change to the previously displayed one.
Go To Screen:	When the Switch is pressed, the currently displayed screen on the LT will change to the specified screen. Input the screen number to be changed (jumped) to. The Data Format can be either Bin or BCD.

Note: **If a screen number is specified in the BCD data format to place the corresponding screen, it is still displayed in the BIN data format when the screen is closed and then opened.**

Reset LT: When the Switch is pressed, the LT will be reset to the save status as when the LT's power was turned ON.

⚠ Important ***Resetting the LT turns the I/O signal off. Consider this when designing your system.***

File Name Key: This is a function switch corresponding to the File Name Display and is the same as the one that is automatically placed together with the File Name Display.
Designate the same ID number as the one of the File Name Display and select a operation mode.

▽*Reference*△ *2.1.13   File Name Display*

Data Logging Key: This is a function switch corresponding to the Data Logging Display and is the same as the one that is automatically placed together with the Data Logging Display. Designate the scroll direction and the number of lines being rolled up or down.

▽*Reference*△ *2.1.14   Data Logging Display*

Off line: When this switch is pressed, the LT enters the OFFLINE mode.

■ **Function Switch [Shape/Color] Attributes**

The Switch's color, and pattern are selected here.

▽*Reference*△ *2.1 Parts* ■ *Selecting Colors*
The color and pattern settings available will differ depending on the switch shape.

■ **Function Switch [Label] Attributes**

Here, the characters shown (drawn) on the Switch button face are entered.

▽*Reference*△ *2.1 Parts* ■ *Creating Labels*

■ Function Switch [Extend] Attributes

Here, the interlock and the buzzer are set.

Select the Interlock function state

◆ Interlock

Only when a bit designated via Interlock Address is in a state that has been selected via [Touch available condition], the switch becomes effective. Whether the switch is effective in ON state or in OFF sate is selectable here.

Touch Available Condition	Interlock Address Status	Touch Available/ Not Available
Bit ON	ON	Touch Available
	OFF	Touch Not Available
Bit OFF	ON	Touch Not Available
	OFF	Touch Available

◆ Buzzer

Sets the buzzer to ON/OFF.

■ **Placing a Function Switch**

The Screen Switching (Function) Switch's placement procedure is shown below.

Pressing this button, shifts to screen B10.

PROCEDURE	**R** E M A R K S
(1)Select the [Parts] menu - [Function Switch] command, or click on the ▦ **icon.**	
(2)Designate the [Function] on the [General Settings] tab.	
(3)Select a Part Shape from the Browser. Specify settings for Shape/Color, Label and Extension Settings if necessary.	▼Reference◤ *2.1 Part* ■ *Selecting a Part Shape*
(4)After all of Part's attributes have been entered or selected, click on the [Place] **button.** The Switch's outline will appear in the Base screen, next to your cursor.	

P ROCEDURE	R EMARKS
(5) Click on the point where the Switch's top left corner is to be placed. If necessary, use the Switch's handles to alter its size.	To cancel the placement, click on the 🔄 icon. ▼*Reference*◣ To change the Part's size, refer to ***2.3.3 Scaling Up/ Down*** Double-clicking on any Part placed on the screen calls up that Part's Attribute Setting dialog box. ▼*Reference*◣ ***2.3.15 Changing Attributes***

2.1.4	**Lamps**

Here a lamp is created, which turns ON or OFF according to the Device/ PLC's Monitor Bit Address state.

⚠ **!** *Important*

· **When the LT is Type C, the lamp that specifies the address of the Device/PLC. will not display on the LT unless the LT has been connected to the Device/PLC.**

· **When placing a Lamp, DO NOT overlap it with other objects. If you do so, it may not be displayed correctly.**

■ **Lamp [General Setting] Attributes**

Enter comment data here

Displays the currently selected Part

Calls up the Part Shape Browser. Part Shapes can be selected directly from here

Enter the desired Bit Address here

Changes the state of the dialog box's switch display to either ON or OFF

◆ **Bit Address**

The Bit Address to be monitored is entered here.

■ **Lamp [Shape/Color] Attributes**

Here, border colors for both ON and OFF states, and Lamp's colors and tiling pattern in each state can be selected.

▼**Reference**▲ *2.1 Parts* ■ *Selecting Colors*

The color and pattern settings available will differ depending on each lamp shape.

■ **Lamp [Label] Attributes**

Here, the text characters shown on a Lamp button's face are entered.

▼**Reference**▲ *2.1 Parts* ■ *Creating Labels*

■ **Placing a Lamp**

The procedures for creating and placing a Lamp are shown below.

When X00017 is ON...   **the Lamp lights up.**   **When X00017 is OFF...**   **the Lamp turns off.**

P ROCEDURE	R E M A R K S
(1)Select the [Parts] menu - [Lamp] command, or click on the 📷 icon.	
(2)In the [General Settings] area, enter a Bit Address.	
Enter **X00017** here	
(3)Select a Part Shape from the Browser. Select Colors and input a Label, if desired.	▼**Reference**▲ *2.1 Parts* ■ *Selecting a Part Shape*

PROCEDURE	REMARKS
(4) Switch the state of the lamp with the On/Off buttons, and then select Colors and input a Label.	With the Blink check box checked ☑, and if the Bit is turned ON, the Lamp will blink. Lamp blinking can also be seen via the pull down menu [View]'s [Preview] command.

Lamp Settings [LA_001]

General Settings / Shape/Color / Label

Description

Bit Address: XC0'7

State ON OFF

Browser..

Place Cancel Help

Switches the lamp On/Off | ▽Reference△ *2.7.3 Preview Screen* |
| **(5) After all of the Lamp's attributes have been entered or selected, click on the [Place] button.**

The Lamp's outline will appear in the Base screen, next to your cursor. | |
| **(6) Click on the point where the Lamp's top left corner is to be placed.**

If necessary, use the Lamp's handles to alter its size. | To cancel the placement, click on the icon.

▽Reference△ To change the Part's size, refer to *2.3.3 Scaling Up/Down*

Double-clicking on any Part placed on the screen automatically calls up that Part's attribute settings.

▽Reference△ *2.3.15 Changing Attributes* |

| 2.1.5 | Bar Graphs |

Bar Graphs are used to display Device/PLC's Word Address numeric data in absolute or relative values. This graph's display will change according to Word Address data changes.

■ Bar Graph [General Settings] Attributes

<When displaying Word Address numeric data in absolute values>

Select absolute or relative value display

Enter comment data here

Displays the currently selected Part

Calls up the Part Shape Browser. Part Shapes can be selected directly from here

Enter the desired Word Address to store graph data here

Select the display data's data format

◆ **Absolute**

Data stored in the Word Address is displayed in absolute values from 0 to 100 (with Display Mode +/- selected, -100 to 100).

◆ **Word Address**

Here, enter the Word Address used for storing the Bar Graph's data.

◆ **Data Format**

The display data's format can be either Bin or BCD.
When Bin is selected, negative numeric data can also be displayed. In that case, check ☑ the Display Mode +/- check box.

<When displaying Device/PLC Word Address numeric data in relative values>

Select the Relative value display

Enter comment data here

Used to store the graph's data. Enter the desired Word Address

Displays the currently se-lected Part

Select the display data's format

Calls up the Part Shape Browser. Part Shapes can be selected di-rectly from here

Select the data's Input Code

Specifies data's Bit Length

Specifies data Input Range

◆ **Relative**

According to the Input Range designated for the Word Address' data, the data is converted and displayed as relative values.

◆ **Word Address**

Here, enter the Word Address used for storing the Bar Graph's data.

◆ **Display Mode+/-**

When this check box is checked, negative numeric data can also be displayed.

◆ **Bit Length**

Specifies the Bit Length of data stored in the Word Address.

◆ **Input Range**

Specifies the data's Input Range.

◆ **Input Code**

When No Code is selected, only positive data can be entered. To enter negative number data, select +/-2's Complement or +/-MSB.

■ **Bar Graph [Graph Settings] Attributes**

Select the graph's display direction

Only when a graph with graduations has been selected will this box appear. Enter the number of divisions desired here

◆ **Direction**

The graph's display direction can be specified as either Up, Left, Down, or Right.

◆ **Axis Divisions**

For a graph which has graduations, the number of divisions are entered here. If the number of the divisions is specified to 10, then 11 division lines are used. When graduations are not necessary, specify the number of the divisions as 0.

Note: **Whether the graduations are necessary or not will differ depending on the Part's shape.**

■ **Bar Graph [Shape/Color] Attributes**

The graph's border color, division color (Axis Color), display data color (Graph Color), and display data patterns are selected here.

▼Reference◤ *2.1 Parts* ■ *Selecting Colors*

■ **Bar Graph [Alarm Settings] Attribute**

If desired, an Alarm can be setup here by toggling the Alarm check box.

▼Reference◤ *2.1 Parts* ■ *Setting Alarms*

■ **Placing a Bar Graph**

An example of the Bar Graph's creation and placement procedures are shown below.

> **Data stored in D00102 displays on the Bar Graph**
>
> **When the value 34 (22h) is stored in D00102, the graph will look like this:**

PROCEDURE	REMARKS
(1)Select the [Parts] menu - [Bar Graph] command, or click on the ▥ icon.	
(2)In the [General Settings] tab, input a Word Address and select a Data Format.	

Enter **D00102** here

Select **BCD**

(3)Select a Part Shape that has graduations from the Browser.
Here, you can enter Alarm settings and select Colors, if desired.

▼*Reference*▲   *2.1 Parts* ■ *Selecting a Part Shape*

If the Bar Graph's Alarm value is specified as Variable, a pointer showing levels will be displayed. This pointer's position will move according to the specified Alarm value.

Level pointer

PROCEDURE	REMARKS
(4)In the [Graph Settings] tab, select the graph's display direction and input the number of Axis Divisions.	The area to enter the number of the divisions will appear only for a graph type which has axis divisions.

Bar Graph Settings [BA_001]

General Settings | Graph Settings | Shape/Color | Alarm Settings

Display Direction   Axis Divisions
○ Up   10
○ Left
○ Down
○ Right

Place   Cancel   Help

— Enter **10** here

— Select **Up**

(5)After all of the graph's attributes have been entered or selected, click on the Place button.

The Bar Graph's outline will appear on the Base screen, next to your cursor.

(6)Click on the point where the Bar Graph's top left corner is to be placed.

If necessary, use the Bar Graph's handles to adjust its size.

To cancel the placement, click on the 🖘 icon.

▼*Reference*▲ To change the Part's size, refer to *2.3.3 Scaling Up/Down*

Double-clicking on any Part placed on the screen automatically calls up that Part's attribute settings.

▼*Reference*▲ *2.3.15 Changing Attributes*

The Bar Graph's sizing handles are located inside the graph.

2.1.6   Pie Graphs

Pie Graphs create an area where a Device/PLC's Word Address data is displayed as absolute values. The graph's display will change to reflect changes in the designated Word Address data.

■ Pie Graph [General Settings] Attributes

<When displaying the data using absolute values>

Select Absolute or Relative display

Enter comment data here

The currently selected Pie Graph's image appears here

Calls up the Part Shape Browser. Parts can be selected directly from the Browser

Enter the Word Address used to store graph data

Select the desired Data Format

◆ **Absolute**

Data stored in the designated Word Address is displayed in absolute values, from 0 to 100 (with Display Mode +/- selected, -100 to 100).

◆ **Word Address**

Here, the Word Address' location data is entered to show where the desired data is stored.

◆ **Data Format**

Select either the Bin and BCD display formats.

◆ **Display Mode +/-**

With this check box ☑ checked and the Bin data format is selected, a negative numeric data can also be displayed.

\<When displaying the data using relative values\>

Select Absolute or Relative display

Enter comment data here

The currently selected Pie Graph's image appears here

Calls up the Part Shape Browser. Parts can be selected directly from the Browser

Enter the Word Address to store graph data

Select the desired Data Format

Specifies the data Input Code

Specifies the data's effective Bit Length

Specifies the data Input Range

◆ **Relative**

According to the Input Range designated for the Word Address Data, the data is converted and displayed as relative values.

◆ **Word Address**

Here, enter the Word Address used to store Pie Graph data.

◆ **Display Mode +/-**

When this check box ☑ checked, negative numeric data can also be displayed.

◆ **Bit Length**

Specifies the Bit Length of all data stored in the Word Address.

◆ **Input Range**

Specifies the data's Input Range.

◆ **Input Code**

With No Code selected, only positive numeric data can be entered. To enter negative numeric data, select either +/-2's Complement or +/-MSB.

■ Pie Graph [Graph Settings] Attributes

Select the Pie Graph's (data display) Direction

Enter the graph's number of divisions

◆ Display

Here, the graph's data display start point, either Clkws. From Top or Clkws. From Bottom, can be selected.

◆ Axis Divisions

The number of segments the Pie Graph will be divided into is entered here. If the number of Axis Divisions is specified as 10, 10 division lines will be displayed. When no divisions are necessary, simply enter 0.

■ Pie Graph [Shape/Color] Attributes

A Pie Graph's border color, division line color (Axis Color), data display color (Graph Color - Fg and Bg), and data display pattern can all be selected here.

▽*Reference*△ *2.1 Parts* ■ *Selecting Colors*

■ Pie Graph [Alarm Settings] Attributes

Clicking on the Alarm Display check box will call up the Alarm Settings.

▽*Reference*△ *2.1Parts* ■ *Setting Alarms*

■ **Placing a Pie Graph**

The procedure for placing a Pie Graph is shown below.

Data stored in D00102 displays on the Pie Graph

When the value 34 (22h) is stored in D00102, the graph appears like this:

| PROCEDURE	REMARKS
(1)Select the [Parts] menu - [Pie Graph] command, or click on the ⚙ icon.	
(2)In the [General Settings] area, input a Word Address and select a Data Format.	
Enter **D00102** here Select **BCD**	
(3)Select a Part Shape from the Browser. You can also use the Alarm Settings area to choose an Alarm and select Colors, if desired.	▼Reference▲ *2.1 ■ Selecting a Part Shape*

PROCEDURE	REMARKS
(4)In the [Graph Settings] tab, select the display direction and input the number of Axis Divisions. Pie Graph Settings [PI_001] General Settings / Graph Settings / Shape/Color / Alarm Settings Display Direction Axis Divisions ⊙ Clkws. From Top 10 ○ Clkws. From Bottom Place Cancel Help Enter **10** Select **Clkws. From Top**	The area to enter the number of the divisions will appear only for a graph type which has axis divisions.
(5)After all of the Graph's attributes have been entered or selected, click on the ⎡ Place ⎤ **button.** A Pie Graph's outline will appear on the Base screen, next to the cursor.	
(6)Click on the point where the Pie Graph's top left corner is to be placed. If desired, use the Pie Graph's handles to alter its size.	To cancel the placement, click on the 🖎 icon. ▽*Reference*△ To change the Part's size, refer to *2.3.3 Scaling Up/Down* Double-clicking on any Part placed on the screen automatically calls up that Part's attribute settings. ▽*Reference*△ *2.3.15 Changing Attributes*

2.1.7   **Half Pie Graphs**

This graph displays a Word Address' numeric data (received from a Device/PLC) as absolute or relative values in a Half-Pie graph. The graph's display will also change to reflect Word Address data changes.

■ **Half Pie Graph [General Settings] Attributes**

<When displaying the data in absolute values>

Select Absolute or Relative display

Enter comment data here

The currently selected Half Pie Graph's image appears here

Calls up the Part Shape Browser. Parts can be selected directly from the Browser

Enter the Word Address to store graph data

Select the desired Data Format

◆ **Absolute**

Data stored in the designated Word Address is displayed as absolute values, from 0 to 100 (with Display Mode +/- selected, -100 to 100).

◆ **Word Address**

Enter the Word Address where the data will be stored.

◆ **Data Format**

Select the display data format from Bin and BCD.

◆ **Display Mode +/-**

When this check box is checked and Bin data format is selected, negative numeric data can be displayed.

<When displaying the data in relative values>

Select Absolute or
Relative display

Enter comment
data here

Enter the
Word Ad-
dress used to
store graph
data

The currently
selected Half Pie
Graph's image
appears here

Calls up the Part
Shape Browser.
Parts can be
selected directly
from the Browser

Selects the
desired Data
Format

Specifies the
data's Input
Code

Specifies the data's
effective Bit Length

Specifies the data's
Input Range

◆ **Relative**

According to the Input Range designated for the Word Address Data the
data is converted and displayed as relative values.

◆ **Word Address**

Here, enter the Word Address used to store Half Pie Graph data.

◆ **Display Mode +/-**

When this check box ☑ checked, negative number data can be displayed.

◆ **Bit Length**

Specifies the Bit Length of all data stored in the Word Address.

◆ **Input Range**

Specifies the data's Input Range.

◆ **Input Code**

With No Code selected, only positive numeric data can be entered. To enter
negative numeric data, select either +/-2's Complement or +/-MSB.

■ **Half Pie Graph [Graph Settings] Attributes**

The Half Pie graph's display direction is fixed to clock-wise.

Enter the graph's number of divisions

◆ **Display Direction**

Here, the Half Pie graph's display direction is fixed to clockwise.

◆ **Axis Divisions**

The data entered here determines how many pieces a Half Pie Graph is divided into. If the number of Axis Divisions is specified as 10, 11 division lines are displayed. When no divisions are necessary, specify the number of divisions as 0.

■ **Half Pie Graph [Shape/Color] Attributes**

Here, a Half Pie graph's border color, division color (Axis Color), display data color (Graph Color - Fg & Bg), and display data pattern are all selected.

▽**Reference**△   *2.1 Parts* ■ *Selecting Colors*

■ **Half Pie Graph [Alarm Settings] Attributes**

If desired, Alarm settings can be set here.

▽**Reference**△   *2.1 Parts* ■ *Setting Alarms*

■ Placing a Half Pie Graph

The procedure for placing a Half Pie Graph is as shown below.

Data stored in D00102 displays on the Semicircle Graph

**When data 34 (22h) is stored in D00102,
the Half Pie graph will appear as follows:**

PROCEDURE	REMARKS
(1)Select the [Parts] menu - [Half Pie Graph] command, or click on the ⬚ icon.	
(2)In the [General Settings] area, input the Word Address and Data Format.	
Enter **D00102** Select **BCD**	
(3)Select a Part Shape from the Browser. You can also use the Alarm Settings area to enter Alarm settings and select Colors, if desired.	▼*Reference*▲ *2.1 Parts* ■ *Selecting a Part Shape*

PROCEDURE	REMARKS
(4)In the [Graph Settings] tab, input the number of axis divisions. Enter **10**	The area to enter the number of the divisions will appear only for a graph type which has axis divisions.
(5)After all of a Part's attributes have been entered or selected, click on the [Place] **button.** The Half Pie graph's outline will appear on the Base screen, next to your cursor.	
(6)Click on the point where the Half Pie Graph's top left corner is to be placed. If desired, use the Half Pie graph's handles to alter its size.	To cancel the placement, click on the icon. ▼Reference▲ To change the Part's size, refer to *2.3.3 Scaling Up/Down* Double-clicking on any Part placed on the screen automatically calls up that Part's attribute settings. ▼Reference▲ *2.3.15 Changing Attributes*

2.1.8	Meter Graphs

Meter Graphs create an area where a Device/PLC's Word Address' numeric data is displayed as absolute or relative values in a Meter Graph (i.e. a needle moves to show the value). The graph's display will change to reflect Device/PLC Word Address data changes.

■ **Meter Graph [General Settings] Attributes**

<When displaying data in absolute values>

Select Absolute or Relative display

Enter comment data here

The currently selected Meter Graph's image appears here

Calls up the Part Shape Browser; Parts Shapes can be selected directly from the Browser.

Enter the desired Word Address data

Select the desired Data Format

◆ **Absolute**

Data stored in the designated Word Address is displayed as absolute values, from 0 to 100 (with Display Mode +/- selected, -100 to 100).

◆ **Word Address**

Enter the Word Address where the data will be stored.

◆ **Data Format**

Select the display data format from Bin and BCD.

◆ **Display Mode +/-**

When this check box is checked and Bin data format is selected, negative numeric data can be displayed.

\<When displaying data in relative values\>

Select Absolute or
Relative display

Enter comment
data here

Enter the
Word Address
used to store
display data

The currently
selected Meter's
image appears
here

Calls up the Part
Shape Browser.
Parts Shapes
can be selected
directly from the
Browser

Select the
desired Data
Format

Specifies the
data's Input
Code

Specifies the data's
effective Bit Length

Specifies the
data's Input
Range

◆ **Relative**

According to the Input Range designated for the Word Address Data, the
data is converted and displayed as relative values.

◆ **Word Address**

Here, enter the Word Address used to store Meter data.

◆ **Display Mode +/-**

When this check box ☑ checked, negative numeric data can also be dis-
played.

◆ **Bit Length**

Specifies the Bit Length of all data stored in the Word Address.

◆ **Input Range**

Specifies the data's Input Range.

◆ **Input Code**

With No Code selected, only positive numeric data can be entered. To enter
negative numeric data, select either +/-2's Complement or +/-MSB.

■ **Meter Graph [Graph Settings] Attributes**

Select the Meter's (data display) Direction

Only when a graph type which has divisions is selected, will this selection appear

◆ **Display Direction**

Here, the Meter's display direction, either Clockwise or Counterclockwise can be selected.

◆ **Axis Divisions**

Here, the Meter increments are entered. If the number of Divisions is specified as 10, 11 division lines are displayed. When no divisions are necessary, simply enter "0".

■ **Meter Graph [Shape/Color] Attributes**

Here, a Meter's border color, division color (Axis Color), and needle color (Meter Color) can be selected.

▽ Reference △   *2.1 Parts* ■ *Selecting Colors*

■ **Meter Graph [Alarm Settings] Attributes**

If desired, an Alarm's settings can be set here.

▽ Reference △   *2.1 Parts* ■ *Setting Alarms*

■ **Placing a Meter Graph**

The procedure for placing a Meter Graph is as shown below.

Data stored in D00102 displays on the Tank Graph

**When data 34 (22h) is stored in D00102,
the Meter will appear as follows:**

PROCEDURE	REMARKS
(1)Select the [Parts] menu - [Meter Graph] command, or click on the ☒ icon.	
(2)In the [General Settings] area, input the Word Address and Data Format.	

Enter
D00102

Select **BCD**

(3)Select a Part Shape from the Browser.
You can also use the Alarm Settings area to enter Alarm settings and select Colors, if desired.

▼*Reference*▲   *2.1 Parts* ■ *Selecting a Part Shape*

P ROCEDURE	R EMARKS
(4)In the [Graph Settings] area, input the number of divisions and data display direction. Meter Graph Settings [MT_001] General Settings / Graph Settings / Color/Shape / Alarm Setting Display Direction Axis Divisions ⊙ Clockwise 10 — Enter **10** ○ Counterclockwise — Select **Clockwise** Place Cancel Help	The Axis Divisions will appear only when Absolute display is selected.
(5)After all of a Part's attributes have been entered or selected, click on the ⌷ Place ⌷ **button.** The Meter's outline will appear on the Base screen, next to your cursor.	
(6)Click on the point where the Meter's top left corner is to be placed. If desired, use the Meter's handle to alter its size.	To cancel the placement, click on the 🖻 icon. ▽**Reference**△ To change the Part's size, refer to **2.3.3 Scaling Up/Down.** Double-clicking on any Part placed on the screen automatically calls up that Part's attribute settings. ▽**Reference**△ **2.3.15 Changing Attributes**

2.1.9   Trend Graphs

This Part displays Word Address numeric data as absolute values on a Trend (line) graph. The graph's display will then change to reflect Word Address data changes.

■ Trend Graph [General Settings] Attributes

Enter comment data here

The currently selected Trend Graph Shape appears here

Calls up the Part Shape Browser, displaying a list of pre-made Trend Graph Shapes. Part Shapes can be selected directly from the Browser.

Select the desired Data Format

◆ Data Format

Here, the display data format is specified as either Bin or BCD. With the Display Mode +/- check box ☑ checked, and Bin data format selected, negative numeric data can also be displayed.

■ Trend Graph [Graph Settings] Attributes

Select a graph type

Select the data display direction

Enter the number of X and Y divisions

Enter the No. of Samples, Scroll value, and Sampling Time

◆ Graph Settings

Using "Normal":   The specified Word Address's data changes are displayed over time in a Trend Graph. Display data always starts at the "0" point. As each (time) sampling period elapses, the latest data is added in the specified display Direction. When the graph's poly(gonal) line reaches the limit of the Trend Graph, the graph is shifted in the display Direction for the number units specified in "Scroll".

E.g.) Display Direction: Right, Scroll: 4

**Enter screen scrolls
at this point**

Begin
Display | 30 | 25 | 60 | 40 | 20

Using "Pen-Recorder":

A specified Word Address's data changes are displayed over time in a Trend Graph. The data's display always begins with "0". As each sampling period elapses, the graph's poly(gonal) line is shifted one division opposite the specified display Direction. The latest data is always displayed at the very limit (in this example, the right side) of the Trend Graph's display area.

E.g.) Display direction: Right

Begin Display | 30 | 25 | 60 | 40 | 20

■ Block (Display Mode)

All the data in consecutive word addresses are sampled at the designated time, then graphed as a single trend line. Data changes in multiple word addresses can be monitored as a single block by the graph. Enter address numbers to control the ON/OFF display of the graph.

0 *1	1	2	2	1	3
5 *2	5	5	5	5	5
30	30	30	40	40	20
25	25	25	60	60	50
60	60	60	25	25	50
40	40	40	30	30	70
20	20	20	75	75	40
	Status 1 displays the graph.	Status 2 deletes the graph.	Data Change	Status 1 displays the graph.	Status 3 clears old graph and displays new one.

*1 Control Status (address for controlling display)
*2 Number of address data to display

To perform Block Display, keep the areas for the number of addresses specified below, beginning from the specified Word Address.

■ Block Display Word Address

The LS Area (from LS0020) or the PLC Word Address is specified. There is speed difference between when the LS Area is used and when the PLC Word Address is used. Refer to the following:

◆ When using the LS Area

When specifying the LS Area, designate "Read Area Size". The Read Area constantly reads out data from the external device to the LT, regardless of screen display status. For Block Display, "Control", "Data Count", and "Data" are required to be specified for the Read Area. Since this area always reads out data, the time from Control bit turning On to graph display will be shorter than when using the PLC Word Address. However, when the Read Area size is large, the entire screen display time will be slower than when using the PLC Word Address. Also, the Read Area size is limited up to 256 words.

◆ When using the PLC Word Address

When the PLC Word Address is used, "Control", "Data Count" and "Data" are constantly read out from the PLC to the LT, regardless of screen display. The time from the "Control" display bit turning ON to graph display to read out "Data" will be longer than the time when the LS Area is used. However, when graph display is not performed, time required to display data of the entire screen will be shorter than when using the LS Area. This function is also useful when data for more than 256 words is required to display multiple graphs via the Block Display function.

Note: • **When the PLC Word Address is used, to increase the entire screen data display speed to display multiple graphs via Block Display function, the following method is useful.**
Specify the Offset of all graphs displayed via the Block Display function, and then designate each graph's "Control", "Data Count", and "Offset" with consecutive address.

Control	
Data Count (n)	**First Data Unit**
Offset	
Control	
Data Count (n)	**Second Data Unit**
Offset	
:	
:	
:	

◆ **Word Address's setting items**

The Word Address setting items for Block Display is as follows:

The Offset setting is valid only when the PLC Word Address is used.

	Without Offset Control
+0	**Control**
+1	**Data Count (n)**
+2	
	Data "n"(units)

	With Offset Control
+0	**Control**
+1	**Data Count (n)**
+2	**Offset (m)**
+m	
	Data "n"(units)
+(m+n-1)	

◆ **Control**

The role of each bit in the Control Status word is described in the following passages.

- To begin the graph display, turn bit 00 ON.

- To clear the entire graph, turn bit 01 ON.

- To clear the graph, then re-draw it, turn both bit 00 and bit 01 ON.

◆ **Data Count**

Defines the number of data values to display on the graph. To display a graph like the one shown below, set the Data Count to 7.

• To display the graph, delay Control Status setting by a time longer than the communication cycle time, after storing the data count and data values.

• After displaying the graph, the Control Status resets to 0. To display the graph again, store the data in the same Control Status word. However, be sure to delay at least 50 ms after the Control Status changes from 1 to 0.

• The Scale value setup in the Graph Settings dialogue box refers to the number of trend line segments ("6" in the Data Count graph on the previous page), and the Data Count for the block display trend graph refers to the number of data points.

• To display the graph with the LS area setting, delay Control Status setting by a time longer than the communication cycle time, after storing the data count and data values.

• To display the graph with the PLC Word Address setting, delay Control Status setting by a time longer than the communication cycle time, after storing the data count and data values.

◆ **Offset**

The area where the data for a trend graph is stored is indicated. When the PLC Word Address is used, this setting is valid.

◆ **Data**

This area stores the data for a trend graph.

■ **Setting Example (when the offset setting is not used:)**

◆ **When using only the display**

When "1" is entered to the Control Status word, bit 00 turns ON and the new graph overlays the previous display.

◆ **When clearing the display**

When "2" is entered to the Control Status word, bit 01 turns ON and the new graph display is cleared.

◆ **When clearing then displaying the graph again**

When "3" is entered to the Control Status word, both bits 00 and 01 turn ON, and after the graph display is cleared, the current data is used to display the graph again.

◆ **Data Samples**

Data Samples: The number of data "units" to be displayed in a single Trend Graph. Up to 638 can be used.

Scroll: The number of data units to be scrolled when the polygonal line reaches the limit of the Trend Graph's display area. The field is enabled when the graph type is set to "Normal".

Sampling Time: The data read interval (from the host Device/PLC) is input in seconds. The field is enabled when the graph type is designated as "Normal" or "Pen-Recorder". This option cannot be specified when the graph type is designated as "Block".

◆ **Display Direction**

Select the Trend Graph's display direction, either Up, Left, Down, or Right.

◆ **Axis Scale**

Enter the number of units that the X and Y axes are to be divided into. When no divisions are necessary, input "0".

■ **Trend Graph [Channel Settings] Attributes**

Designates or enters the number of data lines (channels) to be displayed on the Trend Graph

Designates the channel being currently selected

Enters the Word Address used to store the current channel's display data

Selects the color and type of line used for the current channel

◆ **Number of Channels**

Enter the number of channels used in the Trend Graph. Use the "Current Channel" area to select which channel is being specified. Up to 20 channels can be entered in a Project file (LTE file, including the Data sampling frequency number).

◆ **Word Address**

Enter the Word Address used to indicate where the Trend graph's data is stored.

■ **Trend Graph [Shape/Color] Attributes**

The Trend Graph's border color, division color (Axis Color), and Trend Graph's display area color (Graph Area Color) can be selected.

▼*Reference*▲ *2.1 Part* ■ *Selecting Colors*

■ **Trend Graph [Alarm Settings] Attributes**

If desired, an alarm's settings can be set here.

▼*Reference*▲ *2.1 Part* ■ *Setting Alarms*

■ **Placing a Trend Graph**

An example of a Trend Graph (scrolling left to right) is shown below.

Data stored in D00102 is displayed on the Trend Graph

When 34 (22h) is stored in D00102 the graph will look like this:

← 34

Axis Settings
* Sample   20
* Scroll   19
* Sampling Time   10 sec
* Axis Div. (Ver.) 10
  "   "   (Hor.) 10

PROCEDURE	REMARKS
(1)Select the [Parts] menu - [Trend Graph] command, or click on the ▨ icon. **(2)After clicking on the [General Settings] tab, select the data format.** Select **Bin** **(3)Select a Part Shape from the Browser.** You can also use the Alarm Settings area to enter Alarm settings and select Colors, if desired.	Data in the range of 0 to 100 can be displayed on the Trend Graph. When the data range is from -100 to 100, check the Display Mode +/- check box. ▼**Reference**▲ *2.1 Parts* ■ *Selecting a Part Shape*

PROCEDURE	REMARKS

(4)In the [Graph Settings] area, select the Graph Type and Direction, and enter the number of Data Samples and Axis Divisions.

Select **Normal**

Enter **20**

Enter **19**

Enter **10**

Enter **10**

Enter **10**

Select **Right**

(5)In the Channel Setting area, enter the Number of Channels, then enter each channel's Word Address and select the desired colors.

In this example, since the Number of the Channels is "1", you only need to enter one Word Address.

Enter **D00102**

If the more than one channel is used, be sure to enter the Word Address and select the Color for each channel before placement.

Important

A Trend Graph's channel Word Addresses should not be the same as other Part addresses, otherwise, it will cause a LT error.

Up to 20 channels can be designated for a Project file (including the Data Sampling frequency number).

Up to 8 Trend Graph display areas can be placed on a single screen.

(6)After all of Part's attributes have been entered or selected, click on the [Place] button.

The Trend Graph's outline will appear in the Base screen, next to your cursor.

To cancel the placement, click on the icon.

(7)Click on the point where the Trend Graph's top left corner is to be placed.

If desired, use the Trend Graph's handles to alter its size, after placement.

▼*Reference*◣ To change a Part's size, refer to ***2.3.3 Scaling Up/ Down***
Double-clicking on any Part placed on the screen automatically calls up that Part's attribute settings.
▼*Reference*◣ ***2.3.15 Changing Attributes***

2.1.10	Keypads

Here, pre-made keypads are used to enter data to a designated Word Address. In order to input data via the keypad, it is necessary to first create a Keypad Input display.

▼*Reference*◣ *2.1.14 Keypad Display*

■ **Keypad [Description] Attributes**

Displays the currently selected Keypad's image

Calls up the Part Shape Browser. Parts can be selected directly from the Browser

Select the Keypad's data format

Select the Keypad's border color

◆ **Keypad Type**

First, a Keypad type needs to be selected that will be suitable for the data format specified. To select a Keypad type, simply click on the Browser and the selection of available Keypads will be displayed.

◆ **Pad Color**

The Keypad's border color (Pad Color) can be selected here.

■ **Keypad Key Functions**

The various Keypad Key functions are shown in the table below.

Decimal	Hexadecimal
Keypad Specs	

Common Keys	Numeric value keys (for Hex, the keys are 0 to F). Inputs the corresponding value in the display.	
	Delete key Deletes the character above the cursor.	
	Clear key Clears the entire display. If the CLR is pressed after clearing, 0 is stored in the PLC Word Address.	
	Enter key Registers the set value and writes it to the PLC Storage Address. Then, the cursor moves to the next display and awaits next input.	
	Cursor keys Moves the cursor right and left within the display.	
	Jump keys Moves to the next Key Display without entering the set value. You can use these keys to jump to the area where you wish to enter data.	
Dec. Only keys	Negative key Only available for Dec(imal) and +/- format.	
	Decimal Point key Valid when Decimal Places have been entered for Decimal and BCD numbers.	

■ **Placing a Keypad**

The procedure for creating and placing a keypad is shown below.

When the Trigger Bit M0080 turns ON, ...	KD_1 to 3 (Word Address D0050 to D0052) can receive...	Input data from the Keypad

▽*Reference*△ For how to create the display area for the keypad shown here, refer to *2.1.12 Keypad Display.*

PROCEDURE	REMARKS
(1)Select the [Parts] menu - [Keypad] command, or click on the ▦ icon. **(2)Select a Keypad Data Format Type.** **(3)Select a Keypad Shape from the Browser.** If desired, select a color from the Shape/Color area. 	 ▽*Reference*△ *2.1 Parts* ■ *Selecting a Part Shape*

> ### 2.1.11 Keypad Display

Here, the area used to display Pop-up Keypad data is created. When the Keypad Display is touched, a Pop-up Keypad appears, allowing you to enter a value.

When not using the pop-up keypad, place an additional keypad separately from the Keypad Display.

Note:
- **When the Keypad display is placed, the Pop-up Keypad will automatically be set. You don't have to place a new keypad for entering numerical data.**
- **The Keypad Display cannot be set up simultaneously with the Logging Display.**

■ Keypad Display [General Settings] Attributes

Enter comment data here

The currently selected Part's image will appear here

Calls up the Part Shape Browser. Parts can be selected directly from the Browser

Keypad Input Display Settings [KD_001]

General Settings | Display Format | Shape/Color | Alarm Settings | Extend

Description

Word Address
01/C00000

Trigger Bit Address
01/C0000000

☑ Use Pop-up Keypad

Browser...

Place   Cancel   Help

Enter the Word Address used to store display data

Enter the Trigger Bit Address to allow you to perform data settings via the Keypad

Select this option to display a keypad when the LT screen's Keypad Input Display is touched.

◆ **Word Address**

The Word Address is used to store the keypad display's data.

◆ **Trigger Bit Address (When not using the Pop-up keypad feature.)**

When this bit is turned ON, the Keypad's data entry area becomes active.

◆ **Use Pop-up Keypad**

When this option is selected, touching the Keypad Display will automatically display the pop-up keypad on the screen. When this option is selected, the Trigger Bit Address is disabled.

When "Text" is selected on the [Display Format] tab, the "Use pop-up keypad" option is disabled.

■ Keypad Display [Display Format] Attributes

Keypad Input Display Settings [KD_001]

General Settings | Display Format | Shape/Color | Alarm Settings | Extend

○ Absolute   ○ Relative   ○ Char. String — **Select the data to be displayed.**

Enter the No. of Display Digits

□ Code +/-

□ Round Up

Display & Write Data Format

16 Bit	32 Bit
○ Decimal	○ Decimal
○ Hex	○ Hex
○ BCD	○ BCD
○ Octal	○ Bin
○ Bin	○ Float

— **Select the Data Length and Data Format here.**

The decimal point is not included in the display digits.

No. of Display Digits 5

Decimal Places 0

Character Size

8x16 — **Character size can be selected here**

Enter the No. of Digits after the decimal point

Place   Cancel   Help

◆ Absolute

16-bit or 32-bit data can be processed. Configure the "Data Display Format" and "Code +/-" parameters. When "Dec" is selected, checking the "Code +/-" checkbox will enable the display of data with negative values.

Select "Oct" to process only 16-bit data, and "Float" to process only 32-bit data (IEEE754 format). Errors may occur with the "Float" mode.

When "Float" is selected, the Round Off option will round off the value according to the No. of Display Digit setting. When "Float" is not selected, the all digits to the right of the specified digit will be discarded.

> **Example:** When Decimal Places is set to "2"
> Value: 1.9999....
> When "Round Off " is selected: 2.00
> When "Round Off" is not selected: 1.99

Note: **When using a Logic Symbol to Word Address or Trigger Bit Address, select "32 Bit" data display format.**

◆ Relative

32-bit data can be processed.

Configure the Bit Length, Data Display Format, Input Sign, and Code +/- settings. When "Dec" is selected, putting a checkmark to the "Code +/-" checkbox will enable the display of data with negative values.

The Input Code can be selected from the following three types:

No Sign

Processes data of positive numbers only.

+/- 2's complement numbers

Negative values are processed with two's complement numbers.

+/- MSB sign

Negative values are processed with MSB signs.

When using Relative data, the data written to the host (PLC) is converted automatically based on the Input Range settings.

A data calculation program in the host (PLC) can be omitted.

The Input range (the range of data stored in the Word Address) varies depending on the "Input Sign" setting. The "Display range" (the range to which the data is converted and displayed) varies depending on the cardinal number of the data and "Code +/-" setting. Make sure that the Display range will not exceed the Input range; otherwise, the entered data may not be displayed due to an error processing the function.

<Minimum and Maximum Range Values>

Data Format			Input Range		Display Range	
	Code Input	**Code +/-**				
Dec	No Code	+/-	0 - 65535		-32768 - 32767	
		+			0 - 65535	
	2's complement	+/-	-32768 - 32767		-32768 - 32767	
		+			0 - 65535	
	MSB	+/-	-32767 - 32767		-32768 - 32767	
		+			0 - 65535	
Hex	No Code		0 - 65535		0 - FFFF (h)	
	2's complement		-32768 - 32767		0 - FFFF (h)	
	MSB		-32767 - 32767		0 - FFFF (h)	
Oct	No Code		0 - 65535		0 - 177777 (o)	
	2's complement		-32768 - 32767		0 - 177777 (o)	
	MSB		-32767 - 32767		0 - 177777 (o)	

The "Round Off" operation rounds off the values in decimal places that are generated in the range conversion of relative values. When this option is not selected, the fractions will be discarded.

◆**Text**

Text data can be processed. The data will be written to the PLC in ASCII code or Shift JIS code. Specify the maximum length of the text to be stored.

Designate the maximum number of characters for the "No. of Display Characters" setting. Up to 80 characters (single-byte) can be displayed. One word of the data storage address is able to store two single-byte characters or one double-byte character. When the No. of Display Characters exceeds "2" , a sequence of contiguous word addresses will be automatically occupied in the specified data storage address by the number of the words that store the excess characters.

Note:
- **The possible number of display lines and characters is determined by the LT screen size and orientation, and the text size setting.**

- **If the number of characters entered is less than the number designated for No.of Display Character, spaces (20H) which will balance the number will be stored.**

   <When No.of Display Character is 6, and 4 characters are entered>

'A'	'B'	'C'	'D'	␣	␣	

- **If the No. of Display Character cannot be divided by 2 (When PLC's one device is 16-bit length), or if the No. of Display Character cannot be divided by 4 (when PLC's one device is 32-bit length), NULL(00H) will be stored at the end.**

   <When No.of Display Character is 5, and 4 characters are entered :when PLC's one device is 16-bit length>

'A'	'B'	'C'	'D'	␣	NULL	

◆ **No. of Display Digits**

Here, the number of digits displayed, to the right of the decimal point, is input.

◆ **Decimal Places**

Here, the number of digits to the right of the decimal point is input.

Each data format available is listed in the table below.

Data Format		Code	Data Length	Display Digits	Decimal Places
Data Values	Dec	+/-	16 bit	1-5	0-4
	Hex	+		1-4	
	BCD	+		1-4	0-3
	Oct	+		1-6	
	Dec	+/-	32 bit	1-10	0-9
	Hex	+		1-8	
	BCD	+		1-8	0-7
Char. Col.			No. of Char.	1-80	

When using 32 bit data, the relationship between the top and bottom of the Word Address will differ depending on the Device/PLC used.

▽ *Reference* △   *Device/PLC Connection Manual*

Note: **When the No. of Display Digits is set to 5 and the Decimal Places is set to 2, a value appears on the Keypad Input Display as shown below.**

◆ **Character Size**

The label's character size is selected here.

▽ *Reference* △   *2.2.9 Text*

■ **Keypad Display [Color/Shape] Attributes**

The Keypad Display's border color, data display color (Text), and interior color (Plate) are selected here.

▽ *Reference* △   *2.1 Parts ■ Selecting Colors*

■ **Keypad Input Display [Alarm Settings] Attributes**

Set up alarms if necessary.

▽ *Reference* △   *2.1 Parts ■ Selecting Alarms*

■ **Keypad Display [Extend] Attributes**

Use this tab to designate the Input Style, Display Style, and Interlock function.

Specify the Display Style.

Specify the ON/OFF status of the Interlock function. (This function can be set up only when the pop-up keypad is used.)

◆ **Input Style**

• **Auto Clear OFF**

The previous input is not cleared and displayed in the input area. The new input is appended to existing data. To clear the existing values, enter "CLR" from the Touch Keypad.

• **Auto Clear ON**

The previous input is cleared when the first character (except the cursor keys, ENT, DEL and BS keys) is entered.

• **Auto Clear & Input Check**

When barcode input is performed in this mode, the Auto Clear function is enabled and the input data are monitored so that it matches the No. Display Digit. If the data length is inappropriate, it is not written into the word address. When data is input from the Touch Keypad, only the Auto Clear function is enabled.

• **Bar Code Input**

Selecting this feature enables input from the Touch Keypad and barcode readers. Touch Keypad input enables the entry of numeric data. Barcode Reader input enables the entry of text strings.

Using the Bar Code reader [*1] connected to the LT, data can be read then written to the data storage address setup, prohibiting data input from barcode reader.

When inputting data using the barcode reader input...

- Data read using the barcode reader is written automatically to the data storage address. It is unnecessary to use the ENT key on the touch keyboard.

---

*[*1] Usable barcode readers are restricted to those recommended in your User's Manual.*

- If you enter a change screen command during barcode input, because the screen change priority is higher, the data being input will be ignored, so please use with caution.
- Ending data write causes the System Area's Status 03 bit to reverse. Using this, you can figure out the data write timing.

◆ **Display Style**

• **Shift Left**
• **Shift Right**

Select the display style from the Shift Left and Shift Right. The data will appear, starting from the side designated here. The Shift Right is selected by default.

• **Zero Suppress**

Select this option to omit the leading zeros of display data. E.g. When the Display Length is 4 and the Zero Suppress is NOT selected, 25 appears as 0025.

• **Zero Display**

When this option is clicked, and the host (PLC) data is 0, the value 0 will not display.

◆ **Interlock (Only when the pop-up keypad is used)**

Only when a bit designated via Interlock Address is in a state that has been selected via [Touch available condition], the pop-up keypad becomes effective. Whether the pop-up keypad is effective in ON state or in OFF state is selectable here.

Touch Available Condition	Interlock Address Status	Touch Available/ Not Available
Bit ON	ON	Touch Available
Bit ON	OFF	Touch Not Available
Bit OFF	ON	Touch Not Available
Bit OFF	OFF	Touch Available

■ **Placing a Keypad Display**

The Keypad Display's placement procedures are shown below.

PROCEDURE	REMARKS
(1)Select the [Parts] menu - [Keypad Input Display] command, or click on the ▣ **icon.**	
(2)Make the following settings on the [General Settings] tab. **[When using the Pop-up Keypad]** **Place a check mark in the [Use Pop-up keypad] box.**	When [Use Pop-up keypad] is selected, the Trigger Bit Address is disabled.

[When not using the Pop-up keypad]
Remove the check mark from the [Use Pop-up Keypad] box, and enter the word address and trigger bit address.

Enter **D00050**

Enter **M0080**

P ROCEDURE	R EMARKS

(3)Select a Part Shape from the Browser.

If desired, select colors from the [Shape/Color] area and input the extension settings.

▽ *Reference* △ *2.1 Parts* ■ *Selecting a Part Shape*

(4)In the [Display Format] area, specify the Data Display Format, No. of Display Digits, and Decimal Places (i.e. number of the digits after the decimal point) to be used. If desired, select the Character Size.

Enter **4**

Do not enter anything here (i.e. "0")

(5)After all of the Keypad Display's attributes have been entered and selected, click on the [Place] **button.**

The Keypad Display's outline will appear on the Base screen, next to your cursor.

When placing the Keypad Input Display, do not rotate it. Doing so will cause the Pop-up keypad to display in the incorrect orientation.

PROCEDURE	REMARKS
(6) Click on the point where the Keypad Display's top left corner is to be placed. If desired, use the Keypad Display's handles to alter its size. Even though the set value display area is scaled up or down, the character size will not change. To change the character size or position, directly select the characters inside the border.	To cancel the placement, click on the ⟲ icon. ▽Reference△ To change the Part's size, refer to **2.4.3 Scaling Up/Down** Double-clicking on any Part placed on the screen automatically calls up that Part's attribute settings. ▽Reference△ **2.4.14 Changing Attributes**
(7) Repeat from step (1) to create Keypad Displays with Word Addresses "D00051" and "D00052". Except for the addresses, all settings should be the same.	If the Ctrl key is pressed when the display area's border is scaled up or down, its interior characters are also scaled.

■ **Using a Keypad to Input Values**

◆ **When not using the Pop-up keypad**

The procedures for entering setting values via a Keypad on the LT screen are shown below.

PROCEDURE	REMARKS
(1) Here, three Keypad Display have been set to share a common start bit. **ID No.** KD _1 KD _2 KD _3 (2) Then, when the PLC's internal Trigger Bit M0080 turns ON, PLC (3) First, the Keypad Display KD_1's display reverses (highlights) and waits for input. The square box shown below represents the cursor's position.	▼*Reference*◣ For how to create a Keypad, refer to *2.1.13 Keypads*. ▼*Reference*◣ For how to create a Keypad Display, refer to *2.1.14 Keypad Display* ■ *Placing a Keypad Display.*

P ROCEDURE	R EMARKS
(4)Press the Keypad's keys to input the desired value. **(5)Press the [ENT] key to register the value.** **(6)The registered value will then be stored in Word Address D0050, which was designated in KD_1. Next, KD_2 will be highlighted and be ready to receive input.**	Set value display areas having a common Trigger Bit will enter a wait state in order, from the lowest ID number upwards. After the first value has been registered, the next value's display area will automatically be ready to receive input.

■ **When using the Pop-up Keypad**

The procedures for entering setting values via a Pop-up Keypad on the LT screen are shown below.

PROCEDURE	**R**EMARKS
(1)Here, the Keypad Display KD_1 has been set on the LT screen. **ID No.** KD _1 **(2)When the Keypad Display KD_1 is touched,** KD _1 **(3)A Pop-up Keyboard appears. At the same time, the Keypad Display KD_1's display reverses (highlights) and waits for input.** The square box shown below represents the cursor's position.	▼ *Reference* ◢　For how to create a Keypad, refer to ***2.1.11 Placing a Keypad Display.*** When the Keypad display is placed, the Pop-up Keyboard will automatically be set. In the following two cases, the pop-up keypad will disappear with no confirmation of the input during data input: ・When the active Keypad Input Display is touched ・When another Keypad Input Display is touched during data input (only when the [Use Pop-up keypad] feature is enabled for Keypad Input Display) The Keypad Input Display that has been touched becomes active and is displayed in reverse video, calling up the pop-up keypad for display on the screen.

PROCEDURE	REMARKS
(4) Press the Pop-up Keypad's keys to input the desired value. **(5) Press the [ENT] key to register the value.** **(6) The registered value will then be stored in Word Address D0050, which was designated in KD_1. Then the Pop-up Keypad disappears.**	When [Cancel] is touched, the Pop-up Keypad closes without registering the input value.

◆ **Notes for using Pop-up Keypad**

- Do not rotate the Keypad Input Display when you position it. Otherwise, the Pop-up Keypad will not appear in the proper orientation.

◆ **Restictions for using Pop-up Keypad**

- If the trigger bit for the Keypad Input Display is set to ON, the Pop-up Keypad will not appear.

- The Pop-up Keypad will appear to the right of the Keypad Input Display.

  If there is insufficient space to the right of the Keypad Input Display to display the Pop-up Keypad, the Keypad automatically appears in a position either above, below, or to the left of the Keypad Input Display.

- If there is insufficient space in each of these positions, the Keypad will appear in the lower right corner of the screen. In this case, the Pop-up Keypad and the Keypad Input Display may overlap so that you cannot see the input value.

- The Pop-up Keypad is displayed as a local window. When two local windows are already displayed on the screen, the Pop-up Keypad does not appear even if the Keypad Input Display is touched. In this case, the Keypad Input Display will not wait for input.

- When the pop-up keypad and other windows overlap, touch the desired window to bring it to the front.

- Do not use a Keypad Input Display that uses the Pop-up Keypad for Load Screen. Otherwise, the Pop-up Keypad may not function properly, or the Keypad Input Display will not wait for input.

- The tag size of the Keypad Input Display that uses the Pop-up Keypad is greater than those without the Pop-up Keypad by 60 bytes. (When the Pop-up Keypad is used, the Keypad Input Display capacity is 276 bytes, and 216 bytes when the Pop-up Keypad is not used.)

- When the Touch Available Condition of the Interlock function is disabled, the Pop-up Keypad is not displayed.

- When the Touch Available Condition is switched to OFF while input is being made on the Keypad Input Display, the Pop-up Keypad continues to function. Continue the input, and confirm the entry with the Enter key as usual, or press the Cancel key to cancel the input. However, note that touching the Keypad Input Display will not cancel the input.

2.1.12   Alarm Display

When the External Device's Monitor Bit has been turned ON, messages registered in the Alarm Summary by the Alarm Editor can be displayed in a list.

▼*Reference*▲ *5.1 Creating and Editing Alarms*

Message display order is decided according to which Monitor Bit is in the lowest position in the Alarm Summary display area. It is recommended that Monitor Bit assignment begins from the message with the highest priority. Be sure to input only one message per line. The characters of a message that exceed one line will be truncated.

The number of the characters that can be displayed in one line will vary depending on the character size and LT type. When the size is 1 x 1, the maximum number of characters that can be displayed per line for each LT model is 40 single-byte characters.

■ Alarm Summary [General Settings] Attributes

Enter
Comment
data here

Select the
display area
border
(frame)

Enter the start
address for
each message's
Monitor Bit

Enter the
number of
Words allocated
for a Monitor Bit

◆**Border Type**

The display area frame types are No Border, Outside, and Outside + Inside.

◆ **Word Address**

The Monitor Bit's first address for the messages specified by the Alarm Editor is input. Input this address in word units.

E.g.) How to designate a Word Address using an external device:

When Word Address is set to "test <0>" (Logic symbol)

31 30   0100

test <0> 31 to test <0> 00
← **High   Low→   LSB**

In this case,"test <000>" is designated

When Word Address is set to 01/C00000

31 30   0100

01/C0000031 to 01/C0000000
← **High   Low→   LSB**

In this case,"01/C0000000" is designated

When a variable (Logic symbol) is used as an address, an integer array must be designated. For an integer array, a size required for consecutive addresses needs to be allocated. Enter a value of "2" or more to the "No. of Monitor Words" field.

! *Important*

◆ **No. of Monitor Words**

Here, the number of words a Monitor Bit is assigned and entered. Up to 100 words can be monitored.

■ **Alarm Summary [Display Format] Attributes**

Designates from which existing error message will the display begin

Designates the No. of Lines of a message that can be displayed on one screen

Designates the maximum No. of Characters per line

◆ **Display Start Line**

Among the messages whose Monitor Bit is turned ON, the Start Line designates from which message the display starts.

Note: **When the Alarm Summary display cannot fit in a single screen, only one Alarm Summary display can be placed on a screen. When the number of messages to be displayed does not fit on one screen, create Alarm Summary displays on multiple screens, so that the screens will switch to display all the messages. To display all error messages continuously, specify each screen's Start Line as follows:**

The first screen: The starting line
The second screen: The number of display lines on the first screen + 1
.
.
.
The nth screen: The number of display lines on the first screen x (n-1) + 1

◆ **No. of Display Lines**

Designates the maximum number of alarm message lines that can be displayed on one screen. Up to 50 lines can be displayed.

◆ **No. of Display Char.**

Designates the maximum number of characters that can be displayed on a line. The screen's limit is 100 characters per line. However, the maximum number of characters for each LT unit will vary depending the model.

■ **Alarm [Style/Color] Attributes**

The display area color when a message is cleared (Clear Color) is selected.

▽ **Reference** △ *2.1 Parts* ■ *Selecting Colors*

■ **Placing an Alarm Summary Display Area**

The Alarm Summary Display Area's setting procedure is shown below.

	Bit Address	Type	Message
1	M0800	Summary	ErrorCode030 Unit 0D5
2	M0801	Summary	ErrorCode040 Unit 0D5
3	M0802	Summary	ErrorCode041 Unit 0D6

ErrorCode030 Unit 0D5
ErrorCode040 Unit 0D5
ErrorCode041 Unit 0D6

100 Alarm Messages, have been assigned to bits M0800 to M0896 in the Alarm Editor

Appear on the screen in a Summary Display, at 10 lines by 30 characters per display.

PROCEDURE	REMARKS
(1) Select the [Parts] menu - [Alarm Display] command, or click on the 🔔 icon.	
(2) In the [General Settings] tab, input the Word Address, No. of Monitor Words, and select one of the Show Border options. Here, since the Word Address range is from M0800 to M0896, enter "7" for the number of Monitor Words.	▼*Reference*▲ *2.1.12 Alarm Summary Display* ■ *Alarm Summary [Description] Attribute* ◆ *Word Address*

Alarm Summary Settings [AL_001]

General Settings | Display Format | Style/Color

Description | Word Address
[   ] 🔳 [M0800 ▼] 🔢 → Enter **M0800**

Border Type
○ No Border   No. of Monitor Words [7] → Enter **7**
○ ☐
◉ ☰ → Select Border type

[Place] [Cancel] [Help]

(3) In the [Display Format] tab, input the Display Start Line, No. of Display Lines, and No. of Characters.
In the [Style/Color] tab, select the Clear(ing of Data) Color, if desired.

Alarm Summary Settings [AL_001]

General Settings | Display Format | Style/Color

Display Start Line [1] → Enter **1**

No. of Display Lines [10] → Enter **10**

No. of Display Char. [30] → Enter **30**

[Place] [Cancel] [Help]

PROCEDURE	REMARKS
(4) After all of the Part's attributes have been entered and selected, click on the ⬚ Place **button.** The Alarm Summary display area's border will appear in the Base screen, next to your cursor.	
(5) Click on the point where the Alarm Summary display area's top left corner is to be placed. If desired, use the Alarm Summary display handles to alter its size. When the Alarm Summary display is scaled up or down, the displayed character size will also change, according to the border's size.	To cancel placement, click on the 🔙 icon. ▼*Reference*◣ To change the Part size, refer to ***2.3.3 Scaling Up/ Down***. Double-clicking on any Part placed on the screen automatically calls up that Part's Attribute Settings dialog box. ▼*Reference*◣ ***2.3.15 Changing Attributes***

⚠ Important

Be sure to use the Alarm Summary's display area only for displaying Alarm Messages, i.e. never place, overlap, or overlay another Part or object in this area.

2.1.13   File Name Display

Data registered in the Filing Data settings is displayed.

▼Reference▲ *10.1.1 Filing Data (Recipe) Function*

■ File Name Display [General Settings] Attributes

Enter a description if desired

Enter the ID number for the File Name Display and its function switch

Enter the File No. of filing data to be displayed.

Specify whether or not to use the LS area

Enter the start word address of the LS area

Set up the Device/PLC Transfer Completed Bit Address.

◆   **Description**

Enter a description using a maximum of 20 single-byte characters.

◆   **ID No.**

The File Name Display is linked to its function switch (File Name Key). Specify the number to identify this link is here. This number is available up to 255.

◆   **File No.**

Enter the file number registered in the Filing Data list (1 to 2047). The names under this number are displayed when the file is opened.

▼Reference▲ *10.1.1 Filing Data (Recipe) Function*

◆   **Use LS Area**

When Filing Data is transferred between backup SRAM and the Device/PLC, it can be modified on the LT screen by routing it via the LS area (the data is stored temporarily in the LS area). If data transfer via the LS area is used, specify the LS area's start-word address where Filing Data will be stored from. The address where the data can be stored is from LS0020 to LS2031, and LS2096 to LS4095.

◆   **Device/PLC Transfer**

If set, this bit will turn ON when transfer of filing data to the Device/PLC is completed. Since this Bit does not turned OFF automatically, to use the Device/PLC Transfer Completed Bit again, turn it OFF beforehand.

Note: **When the Device/PLC Transfer Completed Bit Address has been entered, in the case where filing data cannot be transferred to the Device/PLC, the LT's special relay LS2032 Bit 10 will be turned ON.**

■ **File Name Display [Display] Attributes**

Enter the number of names being displayed

Specify the name selection method

Specify the cursor position retention

Enter the number of characters used for the names being displayed

◆ **No. of Display Lines**

Specify the number of Filing Data rows displayed on the LT. A maximum of 50 rows may be specified.

◆ **No. of Display Characters**

Specify the number of Filing Data characters used on each row. A maximum of 100 characters may be specified.

◆ **Direct Selection**

Select a File Name Display being placed on the LT by directly touching its border. If [Direct Selection] is not used, select the file name using the data scroll switches [Roll Up/Roll Down].

▼*Reference*▲ ■ *File Name Display [Switch Settings] Attributes*

◆ **Cursor Position Control**

Even when the screens are changed on the LT , the current screen's cursor position can be retained. When turning the LT's main power switch ON or resetting the LT, however, the cursor will appear in the first line.

Note: **The cursor position will be stored for each ID No. To retain the cursor position, be sure that the File Name Display ID Nos. will not be overlapped through all the screens.**

■ **File Name Display [Style/Color] Attributes**

Specify a color [display color (Fg)] for characters in the Filing Data display area, and a color [display color (Bg)] of the Filing Data display area.

▼*Reference*▲ *2.1* ■ *Selecting Colors*

■ **File Name Display [Switch Settings] Attributes**

Set the function switches that are placed automatically.

▼Reference◢ *2.1.3 Function Switches*

Switches to transfer Filing Data between the backup SRAM and the Device/PLC

Switches to scroll and select items

Switches to transfer data via the LS area. These switches are valid when "Use LS Area" is selected in [General Settings]

◆ **SRAM -> External Device**

Places the switch used to transfer Filing Data from the backup SRAM to the Device/PLC.

◆ **External Device -> SRAM**

Places the switch used to transfer Filing Data from the external device to the backup SRAM.

◆ **Roll Up**

Places the Roll Up key used to scroll through a list of items. Touching the Roll Up key once will roll up by the number specified here.

◆ **Roll Down**

Places the Roll Down key used to scroll through a list of items. Touching the Roll Down key once will roll down by the number specified here.

◆ **SRAM -> LS**

Places the switch used to transfer Filing Data from the backup SRAM to the LS area.

◆ **LS -> SRAM**

Places the switch used to transfer Filing Data from the LS area to the backup SRAM.

◆ **External Device -> LS**

Places the switch used to transfer Filing Data from the external device to the LS area.

◆ **LS -> External Device**

Places the switch used to transfer Filing Data from the LS area to the external device.

■ **File Name Display [Switch Type/Color] Attributes**

Specify colors (border colors) for the function switches which are placed automatically.

▼*Reference*◣ *2.1.3 Function Switches*

■ **Place File Name Display**

Shows how to call up the File Name Display.

~20 ℃
21 ~35℃
36℃~
SRAM →DEV   DEV→ SRAM

Registered File No. 1's filing data is displayed on the File Name Display with 3 display lines and 10 display characters.
By pressing a function key (File Name Key), filing data can be transferred from the SRAM to the external device, or from the external device to the SRAM.

▼*Reference*◣ For filing data list and registering filing data, refer to ***10.1.1 Filing Data (Recipe) Function.***

P ROCEDURE	R EMARKS
(1)Select the [Parts] menu - [File Name Display] command, or click on the [圄] icon.	
(2)In the [General Settings] tab, enter the File No. of filing data to be transferred and the File Name Display's ID No. Here, since File No. 1's data is transferred, enter "1" for the file number. The File Name Display's ID No. is "0".	▼*Reference*◣ ■ *File Name Display [General Settings] Attributes* To transfer Filing Data via the LS area, mark the check box for [Use LS Area] in the [Use LS Area].

File Display [FD_001]

General Settings | Display | Style/Color | Switch Settings | SwitchType/Color

Description

Use LS Area
☐ Use LS Area
Top Write Word Address
01/LS0020

External Device Transfer
☐ Use Transfer Completed Bit Address
Transfer Completed Bit Address
01/C000000

ID No. 0
File No. 1

Place | Cancel | Help

Enter **1**

PROCEDURE	REMARKS

(3)**In the [Display] tab, specify the No. of Display Lines, No. of Display Characters, Direct Selection, and Cursor Position Control.**
If necessary, specify the display color in the [Style/Color] tab.

Enter **3**

Enter **10**

(4)**In the [Switch Settings] tab, select the function switches which are being placed automatically, and specify the number of lines being rolled up or down.**

Select these two switches

(5)**Specify the border colors for the function switches in the [Switch Type/Color] tab.**

(6)**After setting all the attributes, click on** [Place] **.**
The frame of the File Name Display size will be displayed in the drawing area.

PROCEDURE	REMARKS
(7) **Click the mouse button where you want to place each attribute.** ![1234567890 / 2 / 3 with SRAM→DEV and DEV→SRAM buttons] (8) **Select the placed File Name Display. Then, select the [Edit] menu - [Ungroup] command, or click on the ⊠ icon to ungroup the File Name Display and alter each item's position and size.** ![1234567890 / 2 / 3 and SRAM→DEV, DEV→SRAM buttons]	To cancel the placement, click on the ⟲ icon. The File Name Displays are grouped. To change any attribute, first ungroup the File Name Displays, and then change the attribute. ▼*Reference*▲ *2.3.13 Group/Ungroup* ▼*Reference*▲ *2.3.15 Changing Attributes* If "Use LS Area" is selected, the address for the LS area can be changed after ungrouping the File Name Displays.

2.1.14	Data Logging Display

Data created in the data logging settings can be displayed and edited on the LT unit.

> **!**
> **Important**

After the data logging settings, place the Data Logging Display.

▼ Reference ◢ For registering logged data, refer to ***10.2 Logging Function.***

> **Note:**

· **Only one Data Logging Display can be placed on each screen.**

· **The Data Logging Display cannot be set simultaneously with Keypad Input Display.**

· **Data that could not be logged due to a read error is identified with "***" in a cell.**

· **Data that is not logged is not displayed.**

■ Data Logging Display [General Settings] Attributes

Enter a comment, if necessary

Specify whether the data edit function is enabled or disabled

Specify whether the interlock function is enabled or disabled

Using a word address, specify the block number of data being displayed

Using a bit address, specify the interlock address

◆   **Block Number Address**

On a block basis, specify the data being displayed. The logged data for the block number stored at the word address specified here will be displayed.

The block numbers that can be entered are between 0 and 2047, but the maximum of the effective range is [Number of Blocks] specified in [Trigger Settings] in the data logging settings. If [Number of Blocks] specified in [Trigger Settings] is 4, the block numbers are 0 to 3 (BIN values only).

> **Note:**

· **If any block number that does not exist is specified, no data will be displayed.**

· **When the loop function has been designated via [Trigger Settings] of the data logging settings, the Block Number Address will become ineffective.**

◆ **Data Edit**

The logged data can be modified by directly touching the frame of each item in the Data Logging Display placed on the LT. If Data Edit is enabled, touching the cell of data that can be modified in the table will cause the buzzer to sound and allow you to enter data. If Data Edit is disabled, this touching will be invalid and the buzzer will not sound.

Note: · **The data that can be modified is only [Date] and [Value] that have been logged.**

· **If a block or logged data is selected by changing the block number during on-screen modification of data, the data edit mode is canceled.**

· **If the cell is moved beyond the display area, using the scroll keys during the data edit mode, the data edit mode is canceled.**

◆ **Interlock**

The interlock can only be activated when the data edit capability is enabled. If the interlock is enabled, data can be modified only when the bit address for the interlock is ON. If the interlock is disabled, data can always be modified by touching it.

Note: **If the bit address for the interlock is turned OFF during on-screen modification of data, the data edit mode is canceled.**

■ **Data Logging Display [Data Type] Attributes**

Select a Border Type of the display area

Specify whether the scrolling of the total width data section is enabled or disabled

Enter the number of rows for the items displayed (0 to 40)

Enter the number of columns for the items displayed (0 to 25)

Enter a display interval (the number of dots) (0 to 10)

◆ **Border Type**

Select a border type of the display area from among three types, No Border, outer border ⊞ (1-dot lines), and outer border plus inner border ⊞ (the outer border and item use 2-dot lines, while the inner border uses 1-dot lines).

◆ **Row**

Specify the number of rows used to display logged data on the LT. A maximum of 40 rows may be specified.

◆ **Column**

Specify the number of columns used to display logged data on the LT. A maximum of 25 columns may be specified.

◆ **Spacing**

Specify spacing at which to display logged data on the LT. A maximum of 10 dots may be specified. This entry is only valid when the display area border type is specified as No. Border. Draw the border line using the drawing tool.

Note: **The gap equivalent to the specified display spacing is provided between the cell and the border line. The entire cell is filled with the clear color specified in the Data Logging Display [Color] Attributes. However, the gap is not displayed in the clear color, but its background is displayed. If No Border is selected to draw an arbitrary border, ensure that the border is drawn using the same width as the specified display interval without overlapping the cell.**

<Display Spacing>

Border (the gap between the border and the cell is not filled with the clear color)

Draw the border so that it does not overlap any cell.

Cell

◆ **Scroll Total With Data**

If the scroll data area is enabled, the totaling section is scrolled together with the data section. If the totaling section scroll is disabled, the totaling section always appears on the screen.

■ Data Logging Display [Color] Attributes

Select a color (clear color) displayed when the border of each item is cleared.

▽*Reference*△ *2.1 ■ Selecting Colors*

■ **Data Logging Display [Switch Settings] Attributes**

The number of rows and that of columns specified in [Data type] are displayed on the Data Logging Display. If any data exceeding these numbers exists in the LT, use the function switches to scroll the data.

▽Reference△ *2.1.3 Function Switches*

Select the function switch type to be placed

Enter the number of rows/columns scrolled

■ **Data Logging Display [Switch Shape/Color] Attributes**

Specify a color (border color) of each function switch.

▽Reference△ *2.1 ■ Selecting Colors*

■ **Placing the Data Logging Display**

The procedure for setting the Data Logging Display is described below:

The logged data for the block number stored at the block number designated address is displayed.

	Date	Time	Data1	
1st	98/10/16	09:14:00	144	UP
2nd	98/10/16	09:14:00	145	DN
3rd	98/10/16	09:14:01	146	
4th	98/10/16	09:14:01	147	R
5th	98/10/16	09:14:01	148	
TOTAL			730	L

D0100

15   0

If 3 is stored at D0100   **The logged data in block No. 3 will be displayed.**

PROCEDURE	REMARKS
(1)Select the [Parts] menu - [Data Logging Display] command, or click on the ▦ icon.	
(2)In the [General Settings] tab, specify the block number designated address, data edit, and whether the interlock is enabled or disabled. Specify D0100 for the block number designated address.	▼*Reference*▲ *2.1.13* ■*Data Logging Display [General Settings] Attributes* ◆*Block Number Address*

Enter **D0100**

(3)In the [Data Type] tab, specify the display settings.
If necessary, select a clear color in the [Color] tab.

Enter **7**

Enter **4**

PROCEDURE	REMARKS
(4)In the [Switch Settings] tab, select the function switch type that is to be placed automatically, and specify the number of rows, columns scrolled. If necessary, select a color for the special switch in the [Switch Shape/Color] tab. Logging display[LG_001] General Settings | Data type | Color | Switch setting | Switch Shape/Color Select Place Switch ☑ Up 1 ☑ Down 1 ☑ Right 1 ☑ Left 1 Place Cancel Help	
(5)After entering and selecting all the attributes, click on the ⬚ Place button. The border of the Data Logging Display size will be displayed in the drawing area. **(6)Click on the point where the function switch will be placed.**	To cancel the placement, click on the �I icon. The Data Logging Displays are grouped. To change any attribute, ungroup the Data Logging Displays by clicking on the 🖾 icon beforehand. ▽Reference△ *2.3.13 Group/Ungroup* If you double-click on the function switch placed on the screen, the address confirmation screen for parts will appear, enabling you to change the address. ▽Reference△ *2.3.15 Changing Attributes*

> ### 2.1.15   Numeric Displays

This Part displays host Word Address numeric data as an absolute value.

■ **Numeric Display [General Settings] Attributes**

Enter Comment data here

Displays the currently selected Part's image

Calls up the Part Shape Browser

Enter the Word Address where the display data is stored

◆ **Word Address**

Here, input the Word Address where the display data is to be stored.

■ **Numeric Display [Display Format] Attributes**

Select the Data Format and Data Length

Configure the Display Style.

Enter the total number of digits used (not including the decimal point) in the display

Enter the number of digits to be displayed after the decimal point

Select the size used for the label's characters

◆ **Data Display Format**

Here, the Data Display Format, Code, and data length are selected. Choose a data format of either Decimal (base 10), BCD, Hexadecimal (base 16), or Octal (base 8). With the Code +/- check box ☑ checked, when you select "Decimal", negative numeric data can also be displayed.

Note: **When using a Logic Symbol to Word Address or Trigger Bit Address, select "32 Bit" data display format.**

◆ **No. of Display Digits**

Here, enter the total number of digits used (not including the decimal point) in the display.

Note: **When the No. of Display Digits is set to 5 and the Decimal Places is set to 2, a value appears on the Numeric Display as shown below.**

◆ **Decimal Places**

Here, enter the number of digits to be displayed after the decimal point

The types of numeric data that can be used with each data format are listed below.

Data Format	Code	Data Length	No. of Display Digits	Decimal Places	Alarm Range	
Decimal	+/-	16 bit	1-5	0-4	+ only	0 tob 65535
					+/-	-32768 to 32767
		32 bit	1-10	0-9	+ only	0 to 4294967295
					+/-	-2147483648 to 2147483647
BCD	+	16 bit	1-4	0-3	0 to 9999	
		32 bit	1-8	0-7	0 to 99999999	
Hex	+	16 bit	1-4		0 to FFFF	
		32 bit	1-8		0 to FFFFFFFF	
Octal	+	16 bit only	1-6		0 to 177777	

The relationship between upper and lower position Word Addresses when 32 bit data is used will differ depending on each Device/PLC.

▼*Reference*▲ *Device/PLC Connection Manual*

◆ **Character Size**

The label's Character Size is selected here.

▼*Reference*▲ *2.2.9 Text*

◆ **Display Style**

• **Shift Left**

• **Shift Right**

Select the display style from the Shift Left and Shift Right. The data will appear, starting from the side designated here. The Shift Left is selected by default.

• **Zero Suppress**

Select this option to omit the leading zeros of display data. E.g. When the Display Length is 4 and the Zero Suppress is NOT selected, 25 appears as 0025.

• Zero Display

When this option is clicked, and the host (PLC) data is 0, the value 0 will not display.

■ **Numeric Display [Shape/Color] Attributes**

Here, the Numeric Display area's border color, value display color (Number color), and interior color (Plate color) are selected.

▼*Reference*◣ *2.1 ■ Selecting Colors*

■ **Numeric Display [Alarm Settings] Attributes**

If desired, specify a variety of Alarm settings.

▼*Reference*◣ *2.1 ■ Setting Alarms*

■   **Placing a Numeric Display**

The procedure for placing a Numeric Display is shown below.

Data stored in the specified Word Address is displayed in the designated Numeric Display.

D00100
D00101

When 32 bit data 65539 is stored in addresses D00100 and D00101,...

655.39

The maximum number of digits is 10, with 2 decimal places.

PROCEDURE	REMARKS
(1)Select the [Parts] menu - [Numeric Display] command, or click on the 🔢 icon. (2)In the [General Settings] tab, input the Word Address used to store the display data. Numeric Display Settings [ND_001] General Settings / Display Format / Shape/Color / Alarm Settings Description Word Address D00100 Browser... Place Cancel Help Enter **D00100**	

PROCEDURE	REMARKS
(3)Select a Part Shape from the Browser.	▽ Reference △ *2.1 Part ■ Select-*
If desired, set an Alarm and Colors from the [Alarm Settings] and [Shape/Color] area.	*ing a Part Shape*

(4)In the [Display Format] area, specify the Data Display Format, and input the No. of Display Digits and the Decimal Places.
Specify the Character Size, if desired.

(5)After all of the Part's attributes have been entered and selected, click on the [Place] **button.**
The Numeric Display's outline will appear on the Base screen, next to your cursor.

P ROCEDURE	R EMARKS
(6) Click on the point where the Numeric Display's top left corner is to be placed. If necessary, use the Numeric Display's handles to alter its size after placement. Regardless of whether the numeric data display area is scaled up or down, the character size will not change. To change the character size and position, select the characters inside the border directly.	To cancel the placement, click on the ⌖ icon. ▼Reference▲ To change a Part's size, refer to **2.3.3 Scaling Up/ Down.** Pressing the Ctrl key while re-sizing an area's border will also re-size that area's characters. Double-clicking on any Part placed on the screen automatically calls up that Part's attribute settings. ▼Reference▲ **2.3.15 Changing Attributes**

2.1.16   Message Display

This display is used to show single-line alarm messages in response to
changes in External Device's Word Address data. Select the message from
Direct Text or Index Text.

■   **Message Display [General Settings] Attributes**

Enter Comment
data here

The currently
selected Part
Shape is dis-
played here

Calls up the Part
Shape Browser;
Part Shapes can
be selected
directly from the
Browser

Select the
Word or Bit
Address to be
monitored

Select a Border
color

Select the type
of alignment
desired for the
text of the
Display

Select the
Operation
Mode

Select a
Character Size

◆   **Address**

Enter an Address to be monitored. Select either Bit Address or Word Ad-
dress according to (operation) Mode.

◆   **Border Color**

The Message Display's Border color can be selected.

▽*Reference*△ *2.1 Parts* ■ *Selecting Colors*

◆ **Alignment**

Here, the text's alignment can be selected.

Left ——— [ ][ ][ ] ——— Right

Center

◆   **Mode**

There are two methods to change messages displayed on the Message
Display, i.e. via Bit's turning ON/OFF and Word state changes. Here, select
either mode.

Mode: When selecting Bit
Messages will change according to the specified Bit Address
changes.

Mode: When selecting Word

Messages will change according to the state changes of the designated bits, consecutively from the specified Address's 00 bit. According to the number of the messages (either 2, 4, 8, or 16), a bit is automatically assigned from the specified Address's 00 bit.

Numbers of Messages	Number of Bits Used
2	1
4	2
8	3
16	4

When the value set in the No. of Messages is 16, bits 00 to 03 are used.

When the value set in the No. of Messages area is 4, bits 00 and 01 are used

03 02 01 00

When the value set in the No. of Messages area is 2, only bit 00 is used

The remaining bits can be used for other purposes

When the value set in the No. of Messages is 8, bits 00 to 02 are used

■ **Message Display [Messages] Attributes**

(Operation Mode example: When using Word Address)

Select the text type for the message entry.

Enter the message's text here

Deletes the currently selected message, and specifies the message (and its color) as undefined.

Enter the number of messages (states) here

Enter the maximum number of characters only when "Direct Text" is selected.

The state indication buttons appear according to the No. of Messages

Message Display Settings [MW_001]

General Settings | Messages
Direct | Index
No. of Messages | Display Characters | Selected Message | Delete
4 | 10 | Undefined
Message | Style | Copy from Description | Copy to All
0 1 2 3 | Normal | Bold | Raised
Color
Text Color | Blk
Plate Color | Blk
Place | Cancel | Help

Copies all the characters in the Selected Message field to all states only when "Direct Text" is selected.

Select the Character Type

Select the message's (display) Color

Copies the characters in the Description field to the Selected Message field only when "Direct Text" is selected.

◆ **Direct**

The text entered in the Selected Message field is placed directly as fixed character strings.

The message is displayed in a single line. Up to 16 types of messages can be displayed in each Message Display.

◆ **Index**

Select or add the Index Text. Two or more lines of messages can be displayed.
▽ **Reference** △ *4.5.3 ■Selecting the index character string ◆Entering the index character string*

◆ **No. of Messages**

The number of the messages (number of states) can be selected from 2, 4, 8, and 16.

◆ **Display Characters**

The maximum number of characters that can be displayed in a message can be set only when the text type is set to "Direct". Up to 40 characters can be input. If the number of a message characters exceeds the specified value, characters that do not fit in the area will be truncated.

◆ **Message**

According to the No. of Messages, designate a message for each state.

Operation Mode: Bit | Off | On |
Designate a message for each state (ON and OFF).

Operation Mode: Word | 0 | 1 | 2 | 3 |
As many buttons as the number of the specified messages will be displayed. Designate a message for each state.

◆ **Selected Message**

Message can be input only when the text type is se to "Direct". After entering a message, the message will be displayed in the selected color(s). The default value setting is "Undefined".

▽ **Reference** △ To select the "Index" option, refer to *4.6.3 ■Selecting the index character string ◆Entering the index character string*.

◆ **Color**

Here, each message's display colors can be selected.
▽ **Reference** △ *2.1 Parts*

■   **Placing a Message Display**

The Message Display setting procedure is shown below. (When using a Word Address in "Direct Text" mode)

Message No. 0: None
Message No. 1: Signal A Operation
Message No. 2: Signal B Operation
Message No. 3: Signal A & B Operation

A message from those listed above, allocated to the specified Word Address...

...displays in response to changes in the Word Address data.

PROCEDURE	REMARKS
(1)Select the [Parts] menu - [Message Display] command, or click on the 📺 icon.	
(2)In the [General Settings] tab, input a Word Address. Select the message's Border Color, Text Alignment and Character Size, if desired. 	If the message is displayed on more than one line with the Index character strings, the characters are always aligned to the center.
(3)Select a Part Shape from the Browser. 	▼Reference▲ *2.1 Parts* ■ *Selecting a Part Shape*

PROCEDURE	**R**EMARKS
(4)Enter the number of Messages and number of Display Characters with the "Direct Text" option selected in the [Message] area.	▼*Reference*◣ If selecting the "Index Text" option, refer to *4.6.3* ■*Selecting the index character string* ◆*Entering the index character string*.

Enter **16**

Enter **4**

(5)Enter your Alarm Messages.

Select the message number to be registered and enter the message. When displaying a border with no message, be sure to delete the words "Undefined". Select Colors and Character Size, if necessary.

(Example) When registering the message "A Unit Operating" as message Number 1:

Enter **A Unit operation**

Select **1**

Important

Any characters entered that are over the limit specified in step (4) will be cut from the LT's display.

If the text "Undefined" is not deleted, it will be registered and then displayed as a message.

(6)After all of the Part's attributes have been entered and selected, click on the [Place] **button.**

The Message Display's outline will appear on the Base screen, next to your cursor.

P ROCEDURE	R E M A R K S
(7) Click on the point where the Message Display's top left corner is to be placed on the Base Screen. If necessary, use the Message Display's handles to alter its size after placement. The message, corresponding to the message number designated in the Dialog box, is displayed on the Message Display. Regardless of whether the Message Display is scaled up or down, the character size will not change. To change the character size and position, directly select a character inside the text box. A Unit Operating	To cancel the placement, click on the ⟲ icon. ◣ Reference ◢ To change the Part's size, refer to **2.3.3 Scaling Up/Down.** When the Message Display is scaled up(larger), the message characters may not be displayed in the correct position. In that case, use the pull down menu [Edit] menu's [Align...] command to adjust the position. ▼ Reference ◣ **2.3.10 Align** Double-clicking on any Part placed on the screen automatically calls up that Part's Attribute Settings dialog box. Also, clicking on the message numbers allows you to view the message's display status. ▼ Reference ◣ **2.3.15 Changing Attributes**

Note: · **Changing the state via the Parts State Change Tool Bar after placing a Part allows you to check each state's Library display condition.**

· **Every time a part's screen is opened, the Part's state will be reset to 0.**

· **If a state which has not been defined is designated, the Message Display may show nothing. For example, when the number of messages is 16 and only states 0 to 3 actually have a message registered, designating states 4 to 15 displays only message frames.**

2.1.17   **Date Displays**

Date display data is created using the LT's internal calendar and formatted as: February 11th, 2001, or 01/02/11; however, the date format can be changed.

■ **Date Display [General Settings] Attributes**

Enter Comment
data here

The currently se-
lected Part's image
is displayed here

Calls up the Part
Shape Browser.
Parts can be se-
lected directly from
the Browser

Select the Data
Format

Select the
Border (frame),
Text and Plate
(background)
colors

◆ **Data Format**

The following display formats are available:

> yy/mm/dd
> dd/mm/yy
> mm/dd/yy
> 20yy/mm/dd[*1]
> dd/mm/20yy[*1]
> mm/dd/20yy[*1]
>
> (yy: year, mm: month, dd: day)

◆ **Color**

The Date Display's border color, character display color (Text), and interior color (Plate) can be selected here.

▽*Reference*△   *2.1 Parts ■ Selecting Colors*

◆ **Character Size**

The label's Character Size is selected here.

▽*Reference*△   *2.2.9 Text*

---

*1 The characters used for the display of 2000's first two characters ("20") are single-byte characters.

■ **Placing a Date Display**

The Date Display placement procedure is shown below.

Used to display the date.   `00/02/31`

PROCEDURE	REMARKS
(1) Select the [Parts] menu - [Date Display] command, or click on the 112 icon. **(2) In the [General Settings] area, select a display format.** Select the **yy/mm/dd** format **(3) Select a Part Shape from the Browser.** If desired, select Colors and Character Size. **(4) After all of the Part's attributes have been entered and selected, click on the [Place] button.** The Date Display's outline will appear in the Base screen, next to your cursor.	▼*Reference*▲ *2.1 Parts* ■ *Selecting a Part Shape*

PROCEDURE	R E M A R K S
(5) Click on the point where the Date Display's top left corner is to be placed. If desired, use the Date Display's handles to alter its size. Regardless of whether the Date Display is scaled up or down, the character size will not change. To change the character size and position, directly select the characters inside the border.	To cancel the placement, click on the ⟨icon⟩ icon. ▼**Reference**▲ To change a Part's size, refer to ***2.3.3 Scaling Up/ Down.*** Double-clicking on any Part placed on the screen automatically calls up that Part's attribute settings. ▼**Reference**▲ ***2.3.15 Changing Attributes*** When scaling up or down the display area, if the ⟨Ctrl⟩ key is pressed at the same time, the characters will scale in unison with the border.

yy/mm/dd

2.1.18   Time Displays

Time Display areas can be created, based on the LT's internal calendar function. Time will be expressed in 24 hour format.

> (E.g.) 2:25 pm > 14:25

Only one Time Display Part can be used per screen.

■ **Time Display [General Settings] Attributes**

Enter Comment data here

The currently selected item's image appears here

Calls up the Part Shape Browser. Part Shapes can be selected directly from the Browser

Select the Character Size

Select Border, Character, and Plate colors

◆ **Color**

Here, the Time Display's Border color, character display color (Text), and background color (Plate) can each be selected.

▽ *Reference* △ *2.1 Parts* ■ *Selecting Colors*

■ **Placing a Time Display**

The Time Display is placed using the following procedure.

Display the time.   09:30

PROCEDURE	REMARKS
(1)Select the [Parts] menu - [Time Display] command, or click on the ▣ icon.	
(2)Select a Part Shape from the Browser. If desired, select Colors and Character Size. 	▽ *Reference* △ *2.1 Parts* ■ *Selecting a Part Shape*
(3)After all of the Part's attributes have been entered and selected, click on the [Place] button. The Time Display Part's outline will appear on the Base screen, next to your cursor.	
(4)Click on the point where the Time Display's top left corner is to be placed. Change the size if necessary. Regardless of whether the Time Display is scaled up or down, the character size will not change. To change the character size and position, select the characters directly. 	To cancel the placement, click on the ▣ icon. ▽ *Reference* △ To change a Part's size, refer to *2.3.3 Scaling Up/Down.* When scaling up or down the display area, if the Ctrl key is pressed simultaneously, the characters are also scaled up or down together with the border. Double-clicking on any Part placed on the screen automatically calls up that Part's attribute settings. ▽ *Reference* △ *2.3.15 Changing Attributes*

2.1.19   **Picture Displays**

Registered Library items are displayed according to Device/PLC Word Address changes. Parts and Tags, however, cannot be displayed in these displays. Up to 16 different kinds of Library items can be displayed on a single Picture Display.

▼Reference▲ *2.4 Libraries*

! *Important*   ***With the LT Type C, the Picture Displays will not be displayed on the LT when transferred, if the LT has not been communicating with the external device.***

■ **Picture Display [Description] Attributes**

Enter Comment data here

Enter the Address to be monitored here

The currently selected Part State's image appears here

Selects the Operation Mode

◆ **Address**

Here, either a Bit or Word Address is entered, after first selecting a Type (either Bit or Word).

◆ **Mode**

There are two methods used to switch the Library images displayed on the Picture Display; one is Bit access and the other is Word access. Select either of these.

Mode: **When selecting Bit**

Messages will change according to the specified Bit Address changes.

Mode: **When selecting Word**
Library will change according to the state changes of the designated bits, consecutively from the specified Address's 00 bit. According to the number of the messages (either 2, 4, 8, or 16), a bit is automatically assigned from the specified Address's 00 bit.

Numbers of Messages	Number of Bits Used
2	1
4	2
8	3
16	4

When the value set in the No. of Messages is 16, bits 00 to 03 are used.

When the value set in the No. of Messages area is 4, bits 00 and 01 are used

03 02 01 00

When the value set in the No. of Messages area is 2, only bit 00 is used

The remaining bits can be used for other purposes

When the value set in the No. of Messages is 8, bits 00 to 02 are used

■ **Picture Display [Library Image] Attributes**

Displays the currently selected Library image

Reflects the currently selected item's designated state

Calls up the Library Browser. Library items can be selected directly from here

Deletes the currently selected Library item

Selects the item's background and foreground colors (used for clearing)

◆ **Browser**

When clicking on the [Browser...] button, the Library Browser (Library list) will appear. Select a desired Library from this list and drag it to the inside of the Library image display border on the Dialog box.

▼Reference▲   *2.4 Libraries*

◆ **Delete**

The selected Library item is deleted and the display will disappear.

◆ **No. of Lib.**

Displays only when Type's Word is selected. The number of Library images (number of states) to be displayed on the Picture Display can then be input. Select any of 2, 4, 8, or 16.

◆ **Library**

Here, the Library item used for each state is specified. Settings will differ depending on the Type selection.

Mode: When selecting Bit
Specify a Library item's ON and OFF states, respectively.

Mode: When selecting Word
The n.umber of buttons will match the designated number of Library items. Specify a Library item for each state.

Note: **Changing the state via the Parts State Change Tool Bar after placing a Part allows you to check each state's Library display condition.**

◆ **Color**

The background square colors (Clear Fg, Clear Bg)) and pattern (Pattern) are selected. The default settings are black. The square colors can be selected so as to match the Picture Display placement area background's color.

<Back Ground Square>
The Library item to be displayed while the LT is running needs the filled square for the background to be the rearmost, so that the items(images) do not overlay each other when they are switched. When designating a Library item, the LT Editor program will draw this colored square automatically. Right after the Library item(s) is/are placed, the background square will match the size of the largest Library item designated. After the items are placed, it can be scaled larger or smaller, independently from the Library items.
For a state with no designated Library item, only a background square will be displayed and it will become the Library's deletion screen, i.e. it will be overlaid on top of an existing item to "delete" that item.

■ Placing a Picture Display

The Picture Display's creation procedure is shown below.

State 0	**State 1**	**State 2**	**State 3**
10 : on	11: operation	12: stop	

The 3 pictures registered as libraries, as illustrated above, will change in response to changes in the state of Word Address D00250.

PROCEDURE	**R** EMARKS
(1) Select the [Parts] menu - [Picture Display] command, or click on the 📷 **icon.**	
(2) In the [General Settings] area, enter an Address and select a Mode.	

Picture Display Settings [LB_001]

General Settings | Library Image

Description
Address

Enter **D00250**

Mode
○ Bit
◉ Word

Select **Word**

Place   Cancel   Help

(3) In the [Library Image] area, input the No. of library items (No. of Lib.) used.

Picture Display Settings [LW_002]

General Settings | Library Image

Enter **4**

No. of Lib.

Library
0 1 2 3

Browser...
Delete

Erase Color:
Fg   Blk
Bg   Blk
Pattern

Place   Cancel   Help

PROCEDURE	REMARKS
(4)Select a state (to register an item as), and then click on the [Library...] **button.** Here, perform settings for state 0. Select **0**	
(5)Select a Library to be displayed for state 0 from the Browser. 	▽ *Reference* △ *2.4 Libraries* To select a Library from a file different from the currently displayed one, click on the Library Browser's ⌸ icon.
(6)Drag the selected item to the Dialog box's black item display area. Select foreground or background Colors, if desired. 	▽ *Reference* △ *2.4 Libraries*

PROCEDURE	REMARKS

(7)For States ☐1 **and** ☐2 **, repeat steps (4) to (6). Since State** ☐3 **is used to delete Library item from the screen, nothing is specified for it.**

To delete a Library item, click on the [Delete] button.

(8)After all of the item's attributes have been entered and selected, click on the [Place] **button.**
The Picture Display's outline will appear on the Base screen, next to your cursor.

(9)Click on the point where the Picture Display's top left corner is to be placed.
Here, the Picture Display's border (dotted line or filled square) and the Library item will appear. At this time, the Library item corresponding to the state currently selected in the Dialog box is displayed on the Picture Display.
Regardless of whether the Picture Display's border is scaled up or down, the Library item's size will not change. The border size is common through all the Libraries. The Library item's size and position can be altered by clicking directly on its inside border.

To cancel the placement, click on the 🔄 icon.

Double-clicking on any Part placed on the screen automatically calls up that Part's attribute settings. Also, switching the states allows you to view the Library display status.
▼**Reference**▲ *2.3.15 Changing Attributes*

Changing the state via the Parts State Change Tool Bar after placing a Part allows you to check each state's Library display condition.

🖊 *Note:* · **Every time the screen is opened, the state will be reset to 0.**

· **If a state with no Library registered is designated, nothing will be displayed on the Picture Display. For example, when the number of messages is 16 and only states 0 to 3 actually have a message registered, designating states 4 to 15 displays only background square frames.**

2.1.20   Window Parts

Calls up the window onto the Base Screen (B). Register the windows to the Window Registration via the Window Screen (U). This operation is easier than using the U-tag.

▼*Reference*◣ For the details of Window registration, refer to **3.3 Window Display-Window Screen.**

■ **Window Parts Attributes**

Enter comment data here.

This displays the Window Number of the window registered on the Window Screen (U).

Select the Window Number you want to call up onto the Base Screen (B).

Specify the Window Control Address.

Preview the window associated with the selected Window Number in this area.

◆ **Window Control Address**

Enter the address to control the Hide/Show status of the windows.

Show [0]: Hide the window

Changing the order of window layer [1]: Show the window

[0]: Touching the window will change the order of the layer.

[1]: Touching the window will NOT change the order of the layer.

▼*Reference*◣ *3.7.1 Overview of Window Display, 3.7.2 Window Registration on the U Screen*

■ **Placing Window Parts**

Procedure for placing Window Parts will be shown below.

Place a window (such as a bar graph for Window Registration on the Window Screen (U)) on the Base Screen (such as B2). (Call up the window.)

P ROCEDURE	R EMARKS
(1)Select [Window Parts] from the [Parts] menu or click the [icon] icon.	▼*Reference*◢ For Window Registration of parts on the Window Screen (U), refer to *3.7.2 Window Registration on the U Screen*.
(2)Select the window to be displayed on the Base Screen (B) from the "Window Number" field. Specify the Window Control Address as well.	
(3) Click the [Place] button after setting all attributes. The border of the window area is displayed on the drawing area.	
(4) Click on the point where the Window Part is to be placed.	When the specified area is overlapped by objects on the Base Screen, the object will be hidden while the window is displayed.

2.2 Drawing

Straight lines, rectangles, and oval objects can be drawn, using drawing tools.

An object's attributes such as line types and colors are designated in its dialog box. After designating the object's attributes, move the cursor and start to draw the object directly in the drawing area.

Usage Pattern

[Draw] → Select a drawing command → Set any attributes → Draw the object

or

Select a desired drawing icon from the Draw Tool Bar.

■ Drawing Tools

Icons contained in the Draw Tool Bar and their corresponding drawing objects are as follows:

Icon	Object Types	Icon	Object Types
·	Dot		Filled Polygon
	Line/Poly-line		Scale
	Square/Rectangle		Text
	Circle/Oval		Load Screen
	Arc/Pie		Load Mark
	Fill		

■ Selecting Line Types

10 selections are available for straight and poly-lines, and for graph divisions. 6 selections are available for rectangles, circles, arcs and pie sections.

Select one of these patterns

■ Selecting Colors

For color and blink attribute settings, use the procedure same as for Parts.

▽Reference△ *2.1 Parts* ■ *Part Attributes - Selecting Colors*

■ **Tiling Patterns**

Nine different tiling patterns are available. These patterns can be selected for squares, circles, filled squares and polygonal objects. When combining foreground (Fg) and background (Bg) colors, a variety of filled patterns can be drawn.

When a square or circle is drawn, only the line type will be displayed initially. To display the pattern selections, check the Fill check box. (check mark will appear)

2.2.1 **Dot**

Dots can be drawn in 1, 2, 3, and 5 dot units. To draw a dot, simply click on the desired point.

■ **Dot Attributes**

■ **Creating a Dot**

PROCEDURE	REMARKS
(1)Select the [Draw] menu - [Dot] command, or click on the ⬚ **icon.**	
(2)Set the attributes of a dot to be drawn. Select a dot type and colors, if desired.	
(3)Move the cursor to the drawing area. A dot will be drawn at the point clicked on.	When using the keyboard to draw a dot, move the cursor to the desired point and press the ⬚ key. To cancel/delete the dot, click on the ⬚ icon. Double-clicking on any object drawn on the screen automatically calls up that object's Attribute Settings dialog box. ▼ *Reference* ◢ *2.3.15 Changing Attributes*

2.2.2   Line/Poly-line

In order to draw a line, simply click to designate the line's start and end points. A continuous straight line can also be drawn; holding down the Ctrl key allows you to draw lines at precisely 0°, 45°, or 90° angles.

■ **Line/Polyline Attributes**

When drawing a polyline, check this box

Selects a line type (with or without arrows)

Selects a line type

The currently selected line's image appears here

Select a color, and blinking, if desired

■ **Drawing a (Straight) Line**

Pʀᴏᴄᴇᴅᴜʀᴇ	Rᴇᴍᴀʀᴋs
(1) Select the [Draw] menu - [Line/Poly-line] command, or click on the [∿] icon.	
(2) Set the attributes of a straight line to be drawn. If necessary, select the color and line type.	If an arrow (→) is selected, the line's end point will become an arrow.
(3) Move the cursor to the drawing area, click on the line's starting point and drag the mouse to the end point.	In step (4), while holding the [Ctrl] key down, a straight line at an angle of either 0, 45, or 90 degrees can also be drawn.

When using the keyboard to draw a straight line, use the arrow keys to move the cursor to the start and end points and press the [↵] key, to start and finish the line.

To cancel the placement, click on the [↺] icon. |
| **(4) Click again; a straight line is drawn (registered).** | Double-clicking on any object drawn on the screen automatically calls up that object's attribute settings.

▼Reference◢ *2.3.15 Changing Attributes* |

■ **Drawing Polylines**

When the Polyline check box is checked, Polylines can be drawn. Click on the starting point then drag the mouse, clicking the left mouse button at each point of the desired directional change of the line; and, click on the right mouse button at the end point of the line.

✎*Note:* · **When drawing, if the Keyboard's [C] key is pressed instead of clicking on the mouse right button, the start and end points of a polyline object will be automatically connected.**

· **You can draw a line that looks hand-drawn by holding down the mouse's left button when drawing a polyline.**

2.2.3   **Square/Rectangle**

To draw a square, click on and designate the diagonal two points.

To draw a regular square, perform this operation while holding down the
Ctrl key. By selecting a pattern before drawing, a filled square also can be
drawn. Both normal (non-filled) and filled squares can be beveled.

■ Square Attributes

**Check this check box when draw-
ing a filled Square/Rectangle**

**Selects the type of
Square/Rectangle**

**Selects a line
(border) type**

**Select a Color and
blinking, if desired**

**Displays the
currently se-
lected Square/
Rectangle type**

**When selecting
Corner, this
number desig-
nates the num-
ber of dots used**

<Filled Square/Rectangle Setting Screen>

**Select one of the
tiling patterns**

◆ Square Shapes and Beveling types

Square shapes and beveling types are as shown below.

☐   Not beveled.

⬡   All corners are beveled with straight lines.

▢   All corners are beveled with arcs.

When selecting Beveling, input a bevel dot number.

Rounded   Line   The dot value sets up
                                               this spacing

■ **Drawing a Square/Rectangle**

| PROCEDURE	REMARKS
(1) Select the [Draw] menu - [Square/Rectangle] command, or click on the ▢ icon.	
(2) Set the attributes of the square/rectangle to be drawn. If desired, select the colors, line types, beveling type and dot. When drawing a filled square, check the Fill check box, instead of selecting line types. Select a pattern	▼*Reference*▲ *2.2.3 ■ Square Attributes; ◆ Square Shapes and Beveling types*
(3) Move the cursor to the drawing area and click on the first of the diagonal's points, "a".	In step (4), hold down the Ctrl key to draw a square. When using the keyboard to draw a square, use the arrow keys to move the cursor to the rectangle's two diagonal points and press the ⏎ key to start and finish the rectangle. To cancel the placement, click on the 🔁 icon.
(4) Click on the diagonal's other point "b". The rectangle is automatically drawn (registered).	Double-clicking on any object drawn on the screen automatically calls up that object's attribute settings. ▼*Reference*▲ *2.3.15 Changing Attributes*

2.2.4   **Circle/Oval**

To draw a circle or an oval, click on its center point and drag the mouse to the circumference point, and click again. Holding down the Ctrl key draws a perfect circle. To draw a filled circle or oval, select the desired pattern.

■ **Circle/Oval Attributes**

Check this check box, if a filled Circle/Oval is desired

Select a Line/Border type

Select a Fg and Bg color, and blinking, if desired

Displays the currently selected Circle/Oval image

<Filled Circle/Oval Setting Screen>

Select one of the Tiling patterns

■ **Drawing a Circle/Oval**

PROCEDURE	REMARKS
(1)Select the [Draw] menu - [Circle/Oval] command, or click on the ⬡ icon. **(2)Set attributes of an oval to be drawn.** Select colors and a line type, if desired. To draw a filled oval, check the Fill check box and select a pattern, instead of selecting a line type. Select a Pattern	

PROCEDURE	REMARKS

(3)Move the cursor over the drawing area, and click on the center point, shown here by "a".

In step (3), if the Shift key is held down, you can draw an oval which contacts a specified area (i.e. the side(s) of a square). This function is useful when drawing an inscribed circle and can also be used in step (4), together with the Ctrl key.

(4)As the cursor is moved, the oval will expand or contract.
Click on the point shown by b. The drawn oval will be registered.

To draw a regular circle, hold the Ctrl key down in step (4).

When using the keyboard to draw an oval, use the arrow keys to move the cursor to the center point and then, to the point which defines its circumference (radius point), pressing the ↵ key each time.

To cancel a drawing action, click on the ⟲ icon.

Double-clicking on any object drawn on the screen automatically calls up that object's attribute settings.

▼ Reference ◢ *2.3.15 Changing Attributes*

| **2.2.5** | **Arc/Pie** |

To draw an arc or pie, a portion of a circle must be selected. You will need to first draw a circle, and then, click on the arc's beginning and end points.

■ Arc/Pie Attributes

Check this check box when drawing a Pie

Displays the currently selected Arc/Pie image

Select one of the line/border types

Select the Color and Blink settings, if desired

■ Drawing an Arc

PROCEDURE	R EMARKS
(1) Select the [Draw] menu - [Arc/Pie] command, or click on the ⟨icon⟩ icon.	
(2) Set the Arc's attributes. Select Colors and line type, if desired.	
(3) Move the cursor to the drawing area and click on the oval's center point "a".	In step (3), if the [Shift] key is held down, you can draw an oval which contacts a specified area (i.e. the side(s) of a square). This function is useful when drawing an inscribed circle and can also be used in step (4), together with the [Ctrl] key.

PROCEDURE	**R** E M A R K S
(4)Click on the oval's radius point "b". An oval will appear and the arc's base line will be displayed. 	In step (4), holding down the Ctrl key draws a circular arc.
(5)Click on the arc's start point "c" or on its elongation. **(6)Click on the arc's end point "d".** The arc will be drawn (registered). 	When using the keyboard to draw an arc, use the arrow keys to move the cursor first, to its center point, then, to another point on its circumference (radius point), and then, to its start and end points. Press the ⏎ key after specifying each of these points. To cancel the drawing action, click on the [↺] icon. Double-clicking on any object drawn on the screen automatically calls up that object's attribute settings. ▼**Reference**▲ *2.3.15 Changing Attributes*

■ **Drawing a Pie (Sector)**

Follow the same steps used for the drawing of Arcs.

When using the same procedure to draw an Arc:

| 2.2.6 | Fill |

To use the Fill command, simply left-click your cursor on top of an object's enclosed area. The selected Fill pattern will then spread outward until it reaches a boundary. A boundary can be any line or Fill that is the same color as that chosen for the Fill's foreground, background, or border.

⚠ Important **<Cautions when Filling an Object>**

Be sure that the area to be filled is completely enclosed with solid lines. Dotted lines can not be used as an enclosure.

A space of only one dot on the border of an enclosed area is enough to allow Fill to leak into other areas of the screen. Be especially careful when drawing polygon vertexes and filling an object while the display is set to 50%.

DO NOT attempt to fill objects that have been designated as blinking.

When filling an image that uses an arc, Fill may leak when that image is actually displayed on the LT panel display. To prevent this, use a line to connect any gaps in the image.

■ **Fill Attributes**

Select one of the tiling patterns

Displays the currently selected Fill type

Select a Color

📝Note: · To select the background color for all the screens used, use the [Option] menu's [Screen Settings] command.

▼**Reference**▲ *2.7.2* ■ *Settings Screen Property - [Color]*

· To cancel the application of a Fill due to a mistake, such as having designated the wrong Fill point, press the Esc key.

■ **Filling an Object**

PROCEDURE	REMARKS
(1)Select the [Draw] menu - [Fill] command, or click on the ▨ icon. **(2)Set the attributes.** Select Colors and Tiling Patterns, if desired. **(3) Move the cursor to the drawing area and click on the area to be filled.** The designated area will be filled in.	Fill spreads outward from the selected point until it reaches a border with one of the colors (Fg, Bg, Bd) selected in step (2). Select the same color for the Bd (border) Color and boundary Fg (foreground) Color. Left-clicking on a line will not cause it to be filled. Be sure to only click in an area enclosed by lines. When drawing via the PC's keyboard, press the ↵ button to indicate a fill point. Fills and fill points can be specified to either display or not display via the drawing board. ▼*Reference*▲ *2.7.2 Screen Environment Settings* To cancel Fill due to a mistake, such as designating a wrong Fill point, press the Esc key. To cancel the filling, click on the ⟲ icon. Double-clicking on a filling point of any filled object drawn on the screen automatically calls up that filled object's attribute settings. ▼*Reference*▲ *2.3.15 Changing Attributes*

2.2.7 Filled Polygon

To draw a Polygon, either Left-click or press the [↵] key to indicate the Polygon's vertices. To complete the Polygon, either right-click or press the [C] to automatically connect the beginning and end points.
Holding down the [Ctrl] key while drawing a Polygon will snap the polygon's segments to 45 degree angles.

■ Polygon Attributes

Filled Polygon

Displays the currently selected Polygon

Select one of the tiling patterns

Sets the Color and blinking, if desired

Fg Blk
Bg Blk

■ Drawing a Polygon

PROCEDURE	REMARKS
(1) Select the [Draw] menu - [Filled Polygon] command, or click on the [🔺] icon. (2) Set attributes of a polygon to be drawn. Select Colors and Tiling Pattern, if desired. **Filled Polygon** Fg Blk Bg Blk (3) Move the cursor to the drawing area and click on the start point "a".	

PROCEDURE	REMARKS
(4)Left-click to designate the positions of the Polygon's vertices. Repeat this for as many vertices as needed. Here, points b and c are also shown.	Up to 100 corners (faces) can be created. In step (4), holding the `Ctrl` key causes lines to be drawn at exactly 0, 45, or 90 degree angles.
(5)After defining the final vertex, c, right-click or press `C` to complete and fill the Polygon. Points a and c are joined and the object is filled.	To cancel the drawing, click on the 🖭 icon. Double-clicking on any object drawn on the screen automatically calls up that object's attribute settings. ▼ **Reference** ▲ *2.3.15 Changing Attributes*

✎ *Note:* · **About Filling a Polygon**

When a polygon's segments overlap, the filling alternates, so that areas next to each other do not display the same pattern. As a result, areas without any fill (white) may develop inside the polygon. If fill is desired in these areas as well, click on the 🖼 icon.

E.g.

2.2.8 ▶ **Scale**

To draw or create a Scale, input the number of divisions desired and then left-click the mouse's cursor to designate the scale's beginning and end points. Scales can be either horizontal or vertical, linear (straight line) or curved (semi-circle).

■ **Scale Attributes**

Enter the number of divisions desired

Select the Scale's type

Select the line type

Displays the currently selected object's image

(Only with straight line Scales) Changes the scale's orientation to vertical (default is horizontal)

Select the Color and blinking, if desired

■ **Drawing a Scale**

PROCEDURE	R EMARKS
(1)Select the [Draw] menu - [Scale] command, or click on the [icon] icon.	
(2) Set the attributes of the divisions to be marked. Select the Scale's colors, line type, and Scale type, and input the number of scale divisions. If "Linear" is selected as the type, select the orientation direction by clicking on the Vertical check box. 	<Number of Divisions> When the number of the divisions is specified as 8, a total of 9 division lives will be displayed.

Procedure	Remarks
The following explanation is divided into two parts; first, when creating a linear type scale, and second, when creating a curved type scale. **[Creating a Linear type scale- (Vertical, with 8 divisions)]** Specify the area of division lines by a rectangle. **(3)Use the mouse's cursor to create a rectangle in the drawing area, i.e. left-click to indicate the linear scale's start point, a.**	
(4)Complete the rectangle by left-clicking on the Scale's end point, b. The rectangle shape will disappear, and be replaced by division lines.	Holding down the Ctrl key while performing step (4) will draw a perfect square. When using the keyboard to perform drawing, press the ↵ key to designate the start and finish points. To cancel the drawing, click on the ↺ icon.
[Creating a Curved type scale- (8 divisions)] Specify the area of division lines, using double circles. **(3)Use the mouse's cursor to create a circle on the drawing area, i.e. left-click to indicate the curved scale's start point, a.**	

PROCEDURE	REMARKS
(4)Click on the radius point "b", which is of a scale's outer circle.	
(5)Draw another circle inside the circle drawn in step (4) to decide the width of the scale. Click on this inner circle's radius point "c".	
(6)Rotate the displayed segment and click on the scale start point "d" or on its elongation.	
(7)Then, rotate the segment again until you reach the desired end point e, and click to designate the end of the scale's divisions. Division lines appear inside the area surrounded with the double circles and the two segments. They will be drawn clockwise from the start point to the end point.	When using the keyboard to draw divisions, press the ⏎ key after moving the cursor to the division circle's center point, to the other point on its circumference (radius point), and then to the divisions' start and end points. To cancel the drawing, click on the ↺ icon. Double-clicking on any object drawn on the screen automatically calls up that object's attribute settings. ▼Reference◤ *2.3.15 Changing Attributes*

2.2.9 **Text**

Use your PC's keyboard to enter text, and then place in on the screen with your mouse's cursor. This software has two methods of placing text on the screen. The first method defines the placement point, and the second defines the area where the text will be centered.

■ Text Attributes

Enter the text used as direct text.

Selects the text's display direction

Specifies the character width and height

Display a sample of the current text's attributes

Selects the Character Type

Rotates the text in 90 degree increments

Selects the Fg and Bg colors, and blinking

◆ **Direct**

The text entered in the text entry field is placed directly as a fixed text string.
A maximum of 100 characters can be entered per line, and 100 lines per screen.

◆ **Index**

Select and add the Index Text.

▼ *Reference* ◣ *4.5.3 ■ Selecting the index character string* ◆ *Entering the index character string*

◆ **Font Size**

Clicking on the font size display area, displays the current character size (used after text is placed on the drawing area). Move the cursor to where the X and Y axis lines cross, and drag the cursor. As the axis lines move, the character size will change. Click on the text block again, or press the ⏎ key to register (enter) the change.

◆ **Style**

Characters can be either Normal, Bold, or Raised.

```
┌Style────────┐
│ ○ Normal    │
│ ○ Bold      │
│ ○ Raised    │
└─────────────┘
```

Note: **When text character background (Bg) is specified to Black + Blk (Blink), transparent mode is used, thereby displaying that area as transparent. If an object has been drawn underneath these characters, they (the characters) will appear transparent, showing the object behind. This function is useful when overlaying text on objects, i.e., over the face of Switches and Lamps.**

▼ **Reference** ▲ *2.2* ■ *Selecting Colors*

■ Changing to a New Text Line and Line Settings

When entering characters, simply press the ↵ key to move to a new line. When there are 2 or more lines of text, icons will appear to allow adjustments in line spacing, and justification.

Controls the Line Spacing. Spacing is performed in dot increments

Controls the selected text's justification

◆ **Justification**

Horizontal text's alignment can be changed to either Left, Center, or Right justified.

Left justified ——— **Right justified**

Centered

■ **Entering Text**

PROCEDURE	REMARKS
(1)Select the [Draw] menu - [Text] command, or click on the ⬚ icon.	
(2)Set the attributes of the characters to be input. Select Colors and Character Size, if desired. 	The attributes can also be entered and selected after entering text. When "Raised" is selected for Character Type, the border color (Bd) will become shadowed (i.e. 3-D).
(3)Click on the text field to input characters, via your PC's keyboard. Simply clicking on the text field allows you to input characters there. Hereafter, two text alignment cases will be explained, one not using and one using the Centering function: **\<When Centering function is NOT used\>** **(4)Move the cursor to the drawing area and click on any desired point.** After clicking on a point in the drawing area, a text box the size of the selected character will appear on the screen. The top left corner of the text box is the base point used for positioning. 	When using your PC's keyboard to enter text, press the ⬚ key to designate a position.

PROCEDURE	REMARKS
(5)Move the cursor to the desired position and left-click the mouse to place it on the screen.	To cancel the placement, click on the ⌧ icon.

\<When the Centering function IS used\>	Double-clicking on any object drawn on the screen automatically calls up that object's attribute settings.
(4)Move the cursor over the desired placement area and, while holding down the ⎡Shift⎤ key, click on any desired point. After clicking on a point in the drawing area, the text box will appear on the screen in dotted line.	▼ *Reference* ▲ *2.3.15 Changing Attributes*

(5)Select a centering area that is the same size or larger than the previously selected text area. The designated size's text box will appear in the center of the selected area.	To cancel the designated area, click the right mouse button.

2.2.10   Load Screens

Graphics created on screens in a project can be loaded and used repeatedly on others with LT Editor. Thus, a single screen's contents can be used repeatedly elsewhere. The Load Screen function is also a good way to cut down on your screen's actual size, since you only need to call up items to your screen, not save them on it.

■ Screens that can be loaded to other screens

The screen currently being edited cannot be loaded on to itself.

Current Screen	Loadable Screens
B (Base) screen	B (Base) screen
	I (Image) screen
U (Window) screen	B (Base) screen
	I (Image) screen

Note:
- **The screen currently being edited cannot be loaded on to itself.**
- **If a portion of an Image screen extends over a Base screen's Y axis border, that portion will not be displayed on the LT screen. When the Image screen is placed over the Base screen laterally, however, any part that extends over the Base screen X axis border will be squeezed onto the LT screen.(i.e. not cut)**

Example)

When using LT Editor   When using the LT panel display

Drawing Areas

■ **Nesting**

Screens can be nested up to 10 times (11 layers). However, if your PC's system memory is low, a loaded screen/object may not be displayed. Later, however, when the data is transferred to the LT, the display will appear normally.

E.g.) Nesting Objects Twice (3 layers)

Note: **The load screen nesting condition can be viewed via the load screen nesting display function.**

▼ Reference ▲ *2.7.9 Display at Screen Level Change Structure*

■ **Loading a Screen**

PROCEDURE	REMARKS
(1) Select the [Draw] menu - [Load Screen] command, or click on the ⊞ icon.	
(2) Select a desired screen from the list or enter that screen's number directly on the [Screen No.] field via the keyboard, and then click on the ⟨OK⟩ button. Then, the screen's outline and center point will appear in the drawing area, next to your cursor.	Only screens in the currently used Project file can be loaded. Screens in other project files can not be loaded. The current (selected) Screen cannot be loaded on to itself.

PROCEDURE	REMARKS
(3)Click on the point where the Screen's top left corner is to be placed. The image's center point is left top corner of its border, and for other objects, the screen center mark will be the placement point. 	A loaded screen cannot be edited while it is being used on a different (i.e. loaded) screen. You will need to open the original screen to perform any editing. To cancel the loading, click on the icon.

Note: **When calling up a filled object:**

When the current screen's graphics overlap loaded filled (painted) graphics, depending on the color used, unfilled areas may be created. To correct this, add a fill to the current screen's unfilled area.

▼Reference▲ *2.2.6 Fill*

Important
· **If a background color is selected for the screen used for screen call-up, the object placed on the screen will not be displayed on the LT.**

· **To call up the screen for which a background color has been selected, specify the center of the screen as the call-up position and then place the screen.**

2.2.11   **Load Mark**

Marks (dot images) created in a Mark screen can be loaded and used repeatedly on a Base screen.

■ **Loading a Mark Screen**

P ROCEDURE	R E M A R K S
(1)Select the [Draw] menu - [Load Mark] command, or click on the 🖼 icon.	
(2)Select a desired Mark screen from the list or enter that screen's number directly on the [Screen No.] field via the keyboard, and then click on the [OK] **button.** The Mark's outline will appear in the drawing area, next to your cursor. Designate its color and size before clicking on the [OK] button, if desired. 	Only Mark screens in the current project can be loaded. Mark screens in other projects are not available. When the screen display size is 50%, the loaded Mark may not be displayed correctly on the LT Editor software. To cancel the loading, click on the 🖼 icon.
(3)Click on the point where the Mark's top left corner is to be placed. If desired, use the Mark's handles to alter its size. 	To change the Mark's size, refer to ▽*Reference*△ *2.3.3 Scaling Up/Down* Double-clicking on any Mark loaded on the screen automatically calls up that Mark's attribute settings. ▽*Reference*△ *2.3.15 Changing Attributes*

2.3   Object Editing

Parts, objects, and text previously placed or drawn (hereafter called "Objects"), can be edited using various functions, such as Copy and Delete.
To edit an object, first, use the cursor to select the object, and then select the type of edit operation.

Usage Pattern						
Select an Object	→	**[Edit]** or Tool Bar	→	Select the type of editing to perform	→	Perform the editing

■ Types of Editing Functions

Icons contained in the Edit Tool Bar and their corresponding edit operation are as follows:

Icon	Edit Type	Icon	Edit Type
🔙	Undo	⬍	Mirror X-axis
↪	Redo	◀▶	Mirror Y-axis
✂	Cut	✖	Group
📋	Copy	⤢	Ungroup
📋	Paste	▣	Bring to Front
	Command Data Paste	▣	Send to Back
	Duplicate	▣	Change Attribute
✏	Delete		Change Coordinates
▣	Align		Convert Bitmap
↻	Rotate Left		Transferring Screen to Clipboard
↻	Rotate Right		Converting Screen to Bitmap File
		✏	Redraw Screen

Note: **The tools shown above can also be used from a menu by right-clicking the mouse.**

2.3.1 **Selecting Objects**

Two methods are available for selecting objects: 1) clicking on an object directly, or 2) dragging the mouse to enclose and select single or multiple objects.

Also, you can select individual objects that have other objects either on top of, or overlapping them.

When the tool bar's ▐ ▶ ▌ icon is clicked on (active), an object can be selected. To activate this icon, click on it directly, or select the pull down [Edit] menu's [Select] command. Also, while drawing objects, right-clicking anywhere on a desired object allows you to select it.

Either a ■ or a □ mark will be displayed on the sides of the selected object. These square marks are called "handles".

Handle Types

There are two types of handles, those that can be used to scale the object and those that can not.

　■ : Can be used to scale the object
　□ : Cannot be used to scale

When an object has been be selected, the Selection Tool box will automatically appear. When multiple objects are selected, all the selection Tool box's functions are available.

Selects all of the objects in a group

After selecting either `One` **or** `Type` **, clicking on either** `→` **or** `←` **selects the next object or type**

After selecting a group of objects, selects one of that group

After selecting a group of objects, selects one type of object (i.e. squares, circles, etc.)

Note: **Objects may be selected using the Screen Data List, instead of selecting them on the screen.**

▼*Reference*▲ *2.7.4 Screen Data List*

■ **How to Select a Single Object**
Here, the procedure for selecting an object is explained.

PROCEDURE	REMARKS
[Selecting an Object Directly] **(1)Move the cursor over the object, and left-click.** Handles display on the object to show that it is selected. **[Selecting an Object by Dragging]** **(2) Position the cursor near the object and hold the button down, then drag(this is called "Left-dragging") the mouse over the object. As you do so, a "box" formed by a dotted line will expand to enclose the object. When the entire object is enclosed within the "box", release the mouse button; handles display on the object to show that it has been selected. You must position the cursor relative to the object so that when you Left-drag over it, the entire object will be enclosed within the "box"; if it is not, then the object will not be selected. This method is most useful when selecting multiple objects, described below.** **[Selecting an Object from Overlapped Objects]** **(2)While holding down the** Ctrl **key, click on an Object to be selected.** That Object's handles will appear to reveal it has been selected.	When selecting grouped objects, click on any one of the objects in a group to select the group. A Part's Label can be selected independently from the Part. Click on a Part to display its handles and then on its Label to display the Label's handles. After selecting the Label, it can be moved or scaled independently from the Part. Numeric Display and text can also be selected using the above-mentioned steps. Left-dragging over only a part of the object will not select it. The entire object must be enclosed to select it. When you wish to select another object without de-selecting the previous one, hold down the Shift key while making the next selection. This can also be done continually to select multiple objects.

■ **How to Select Multiple Objects**

Use this operation to select multiple objects. All the objects in a designated area or on the entire screen can be selected. Also, if necessary, some of these objects can be de-selected.

PROCEDURE	REMARKS
[Selecting Multiple Objects by Dragging] (1)**Left-drag over objects as described in Selecting an Object by Dragging (see above). Be sure to enclose all of the objects to be selected completely; if part of an object is not enclosed within the "box", it will not be included in the multiple selection.** Handles will display on the objects that have been selected. **[Selecting All the Objects on a Screen]** (1)**Select the pull down [Edit] menu's [Select All Objects] command.** All object handles will appear, to show that they have been selected. 	Left-dragging over only a part of an object will not select it. The entire object must be specified to make selection possible. When two or more objects are selected, the [Change Attributes] command cannot be used. The editing commands available depend on what objects have been selected.

PROCEDURE	REMARKS

[Excluding Objects From A Multiple Selection]

(2) **When multiple objects are selected, to de-select an object while preserving the selection of the other objects, first move the cursor over the object; then, while holding down the** Shift **key, left-click on the object.**
When the object's handles disappear, that object is no longer selected. Repeat this process as many times as desired.

[Adding Objects To A Multiple Selection]

(2) **When multiple objects are selected, to add an object, either left-click on the object or Left-drag over it, while holding down the** Shift **key.**
The imaginary "box" that encloses the multiple selection (represented by its' own handles) will expand to include the added object , which now has handles Using this process, you can add as many objects to the multiple selection as you want.

P ROCEDURE	R EMARKS
[Selecting One Object in a Multiple Selection] **(2)First, make a multiple selection; then, click on the Selection Tool box's** `One` **icon.** All the objects in the multiple selection will become de-selected, except for one. **(3) Use the** `←` **and** `→` **icons to "scroll" through all the objects originally in the multiple selection; clicking on these arrow keys will change the selected item, one at a time.** Clicking on the `→` icon will select the next object, and clicking on the `←` icon will select the previons object , in the order that they were drawn. 	If you wish to re-select all the objects originally in the multiple selection, click on the Selection Tool box's `All` button. To select an Object from over-lapped Objects. ▼**Reference**▲ *How to Select a Single Object*

PROCEDURE	REMARKS

[Selecting Objects by Type from a Multiple Selection]

(2)First, make a multiple selection; then, click on the Selection Tool box's `Type` icon.

Selection handles will appear for only one type of object (here, only square objects are selected), while an outline remains around them all. This will effectively de-select any objects that are not the currently selected type.

Objects are classified as follows:
Parts: by each type,
Objects: by each type,
Loaded Screens and Marks: All as one type, respectively.

To re-select all the objects originally in the multiple selection, click on the Selection Tool box's `All` button.

(3) Use the `←` and `→` icons to select a different object type.
As you press either arrow key, the selected object type will change.

2.3.2	Moving Objects

In this section, the procedures for moving objects are described.

■ **How to Move an Object**

PROCEDURE	R EMARKS
(1)Click on the desired object. The object's handles will appear, showing that it has been selected.	▼*Reference*▲ *2.3.1 Selecting Objects* The keyboard's ↑ , → , ← , and ↓ keys can also be used when the object's handles are displayed.
(2)Place the cursor over the object, away from the handles, and after the cursor changes to ✥, drag it to the desired location.	If an object is too small to select and move (i.e. it is only scaled up or down), click on and drag the object while holding down the Alt key. Also, you can move the object by zooming out the screen or using the keyboard. ▼*Reference*▲ *1.5.2 Display Area (50%, 100%, 200%)* To cancel the movement, click on the ↩ icon.

✎*Note:* · **To move an object horizontally or vertically, do so while holding the Shift key down. In this case, the object will be moved in either the horizontal or vertical direction where the moving distance is greater.**

· **To move and scale up/down an object, designating its coordinates can be used.**

▼*Reference*▲ *2.3.16 Changing Coordinates*

2.3.3 ▶ **Scaling Up/Down**

Scaling means changing the size and proportion of an object. This function allows you to easily scale an object up (larger) or down (smaller). Be sure the object's handles are displayed as (■).

■ **Scaling An Object**

PROCEDURE	REMARKS
(1) Click on the object to select it. The object's handles will appear to show that it is selected. 	▽Reference△ *2.3.1 Selecting Objects* Re-sizing will depend on which handle is dragged:
(2) Place the cursor on an object's handle, and after the double arrow cursor appears, drag the handle to re-size the object. 	Ex. To scale a square up or down: Corner Handles = proportionally Top/Bottom handles = vertically Right/Left handles = horizontally Place the cursor on one of the handles of the object. When the cursor becomes ↔, use the keyboard's either ↑ , → ← or ↓ key to scale the object up or down in the unit of dot. To cancel the re-sizing, click on the ↩ icon.

✎ *Note:*
· **When re-sizing an object while holding down the** Ctrl **key, lines will snap to 45 degree intervals, Rectangular and Scale (Linear) objects will become square-shaped objects, and ovals will become circles. Also, if the** Shift **key is held down, all selected Lines, Rectangles, Ovals, Scales, Text and loaded Marks will scale up or down proportionately.**
When scaling a Part with a Label, holding down the Ctrl **key causes the Label to scale up or down together with the Part.**

· **When selecting an oblique line, 8 handles will be displayed. Click on the line again and 8 handles will change to 2 handles, one at either end. Clicking and then dragging on one end's handle "fixes" the opposite end in place, and "releases" the dragged end, and allowing the line to pivot freely.**

· **Multiple parts may be selected and then scaled up/down. However, the following parts are not scaled up/down, but their positions are moved: Half-pie Graphs, Pie Graphs, Meters, Trend Graphs, Alarms, Keypads, and Picture Displays.**

· **To move and scale up/down an object, designating its coordinates can be used.**

▽Reference△ *2.3.16 Changing Coordinates*

2.3.4	Cut

Here, the procedure for "cutting" an object (deleting it) and placing it on another screen, is explained. (When an object is "cut", it is stored in the Clipboard[*1].)

■ Cutting (Moving) an Object

| PROCEDURE	REMARKS
(1) **Select an object.**	▼Reference▲ *2.3.1 Selecting Objects*
(2) **Select the [Edit] menu - [Cut] command, or click on the [icon] icon.** Then, the selected object will be cut.	To cancel the Cutting, click on the [icon] icon.
(3) **Open the object's destination screen, and select the [Edit] menu - [Paste] command, or click on the [icon] icon.** Then, the outline of the object cut from the previous screen will appear.	
(4) **Position the cursor and click on the point where the object is to be placed.** The object that had been Cut from the previous screen will be "pasted" at the new location.	To cancel the pasting, click on the [icon] icon.

*1 An area where text, graphics, or both, that have been Cut or Copied, are temporarily stored. The contents of the Clipboard can be "pasted" (copied from the Clipboard) using the Paste function. However, once the Copy/Cut command is executed, the data stored in the Clipboard is replaced; therefore, only the data from the most recent Copy/Cut command can be Pasted.

2.3.5	Copy

Here, the procedure for "copying" an object (without deleting it) and placing it elsewhere, is explained. (When an object is "copied", it is stored in the Clipboard*[1].)

■ Copying an Object

PROCEDURE	REMARKS
(1) Select the desired object(s). 	▼Reference△ *2.3.1 Selecting Objects*
(2) Select the [Edit] menu - [Copy] command, or click on the [icon] icon. The selected object(s) will be Copied to the Clipboard.	To cancel the Copying, click on the [icon] icon.
(3) Select the [Edit] menu - [Paste] command, or click on the [icon] icon. Then, the outline of the object copied from the previous screen to the Clipboard will appear.	When "pasting" the Copied object on another screen, be sure to open that screen first. Selecting and dragging an object to anther screen while holding down the [Esc] key can also be used to copy the object.
(4) Position the cursor and click on the point where the object is to be placed. The object stored in the Clipboard will be Copied to the specified location. 	To cancel the pasting, click on the [icon] icon.

---

1 An area where text, graphics, or both, that have been Cut or Copied, are temporarily stored. The contents of the Clipboard can be "pasted" (copied from the Clipboard) using the Paste function. However, once the Copy/Cut command is executed, the data stored in the Clipboard is replaced; therefore, only the data from the most recent Copy/ Cut command can be Pasted.

2.3.6	**Paste**

Here, the procedure for "pasting" an object, that has been Copied (or Cut) to the Clipboard[*1], is explained.

■ **Pasting an Object**

PROCEDURE	REMARKS
(1)First, Copy (or Cut) an object.	▼Reference▲ *2.3.5 Copy*
(2)Select the [Edit] menu - [Paste] command, or click on the ⊡ icon. Then, the outline of the object copied from the previous screen to the Clipboard will appear.	
(3)Position the cursor and click on the point where the object is to be Pasted. The object stored in the Clipboard will be Pasted to the new location.	To cancel the paste, click on the ⊡ icon. When an object is copied from another screen, it will be automatically placed at the same coordinates as its original ones. To place the object at different coordinates, move it after this automatic placement.

---

1 An area where text, graphics, or both, that have been Cut or Copied, are temporarily stored. The contents of the Clipboard can be "pasted" (copied from the Clipboard) using the Paste function. However, once the Copy/Cut command is executed, the data stored in the Clipboard is replaced; therefore, only the data from the most recent Copy/Cut command can be Pasted.

2.3.7 **Pasting Instruction Data**

By copying and pasting to the Screen Editor a logic program instruction created with the Logic Program Editor, you can place a Part corresponding with the instruction.

In the same way, copying and pasting to a logic program a Part placed on the screen inserts an instruction corresponding with the Part.

■ **Conversion between Instructions and Parts**

Each instruction and part has counterparts that have been already determined.

◆ **Conversion from Instructions to Parts**

Below is the list of Parts to which each instruction is to be converted.

Instruction	Parts
NO (a Contact)	Bit/Toggle Switch
NC (b Contact)	Bit/Toggle Switch
PT (Start Up Contact)	Bit/Toggle Switch
NT (Start Down Contact)	Bit/Toggle Switch
OUT/M (Out Coil)	Lamp
NEG/NM (Reverse Coil)	Lamp
SET/SM (Set Coil)	Lamp
RST/RM (Reset Coil)	Lamp
CTU (Up Counter)	Numeric Display/Graph/Keypad Input Display
CTD (Down Counter)	Numeric Display/Graph/Keypad Input Display
CTUD (Updown Counter)	Numeric Display/Graph/Keypad Input Display
TON (On Delay Timer)	Keypad Input Display
TOF (Off Delay Timer)	Keypad Input Display
TP (Pulse Timer)	Keypad Input Display

◆ **Conversion from Parts to Instructions**

Below is the list of Instructions to which each Part is to be converted.

| Parts	Instruction
Bit/Toggle Switch	NO (a Contact), NC (b Contact), PT (Start Up Contact), NT (Start Down Contact)
Lamp	NO (a Contact), NC (b Contact), PT (Start Up Contact), NT (Start Down Contact), OUT/M (Out Coil), NEG/NM (Reverse Coil), SET/SM (Set Coil), RST/RM (Reset Coil)
Numeric Display/Graph/Keypad Input Display	CTU (Up Counter), CTD (Down Counter), CTUD (Updown Counter)
Keypad Input Display	TON (On Delay Timer), TOF (Off Delay Timer), TP (Pulse Timer)

■ **Pasting a Logic Program Instruction to the Screen**

Here, the procedure for "copying and pasting" a logic program instruction to the screen is explained. When pasting the instruction, the type of Part to be converted to needs to be selected from the list.

⚠ **Important**

• *Before copying an instruction, you have to allocate a variable to the instruction. Instructions without a variable allocated cannot be copied to the screen.*

• *Before pasting an instruction, be sure to save the logic program.*

| PROCEDURE	REMARKS
(1) Select the desired instruction on the Logic Program Editor. 	▼ **Reference** *1.2.3 Creating/ Editing/Saving a Logic Program*
(2) Select the Logic Program Editor [Edit] menu - [Copy] command, or click on the [icon] icon. The selected instruction will be copied to the Clipboard. 	To cancel the Copying, click on the [icon] icon.

PROCEDURE	REMARKS
(3) Select the Screen Editor [Edit] menu - [Paste Command Data(2)] command, or click on the 📋 icon.	To cancel the Pasting, click on the ↩ icon.
(4) Select the Part to convert, and determine by clicking OK .	A list of the Parts to which the copied instruction can be converted will appear. If there is only one Part that corresponds to the instruction, the step 4 is omitted.
(5) Change the size and attributes of the Part as necessary and place it on the screen.	▼Reference▲ *2.1 Parts*

■ **Pasting a Part placed to the screen to a Logic Program**

Here, the procedure for "copying and pasting" a part placed to the screen to a logic program is explained. When pasting the Part, the type of instruction to be converted to must be selected from the list.

> ⚠ **Important** *Before copying a Part, you have to allocate a variable (Logic symbol) to the Part. Parts without a variable allocated cannot be copied to a logic program.*

> 📝 **Note:** **A variable will be registered with the Symbol Editor as a Logic symbol when the logic program is saved.**

PROCEDURE	REMARKS
(1)Select the desired Part on the Screen Editor. 	▼Reference◣ *1.2.3 Creating/ Editing/Saving a Logic Program*
(2)Select the Screen Editor [Edit] menu - [Copy] command, or click on the 🗎 **icon.** The selected Part will be copied to the Clipboard.	To cancel the Copying, click on the 🔙 icon.
(3)Select the rung where you wish to insert an instruction on the Logic Program Editor, and then select [Edit] menu - [Paste] command, or click on the 🗎 **icon.** 	

PROCEDURE	REMARKS
(4)Select an instruction to convert, and determine by double-clicking on it. The instruction will be inserted.	A list of instructions to which the copied Part can be converted will appear. To cancel the Pasting, click on the [icon] icon.

■ Dragging and Dropping

Copying and pasting of an instruction or a Part can be performed by the drag and drop operation.

⚠ Important *Before dragging and dropping an instruction or a Part, you have to allocate a variable to the instruction or the Part. Instructions or Parts without a variable allocated cannot be dragged and dropped.*

◆ Dragging and dropping of a Logic Program Instruction to a Part

By dragging a logic program instruction created with the Logic Program Editor to the Screen Editor, you can place a Part that corresponds with the instruction.

⚠ Important *Before dragging and dropping an instruction, be sure to save the logic program.*

◆ Dragging and dropping of a Part to a Logic Program instruction

By dragging a Part placed on the screen to a Logic Program, you can place an instruction that corresponds with the Part. Drag the Part while holding down the Ctrl key.

2.3.8 **Duplicate**

This command allows you to easily make multiple copies of any object. The address of the copies can be set up so as to increment automatically from copy to copy, or simply reuse the address of the original object.

■ Duplicate Setting Dialog Box

When this command is used, the Duplicate dialog box for entering the copy specifications, will appear as shown below.

Enter the number of copies in the X and Y directions

Enter the line spacing, in dot units

When copying Parts that require addresses, clicking here will automatically assign new, incremented addresses for each copy

The device comment corresponding to an address assigned by the automatic address increment is reflected in the Description field.

◆ Number of Copy

Here, how many times an object will be copied in the X and Y directions is entered. When "1" is entered for either direction, copying will not be performed in that direction.
The number of copies is also limited by the copied object's location, size, the Duplicate dialog box's Spacing settings, and any other related settings.

◆ Spacing

Enter the spacing interval of dot (screen pixel) units to be used when the object is copied for both the Horizontal and Vertical directions.

Note: **When Duplicating an object, its positioning will be decided based on the top left handle of the copied (master) object. However, if a Bar Graph's handles are located in a graph display area, the object will be placed based on the graph display area, not the graph's border. Therefore, when setting the spacing, be sure to not overlap any of the graphs' borders.**

◆ Address Increment

To copy multiple Parts, specify the direction of the automatic address increment. According to the automatic address increment, consecutive Addresses will be assigned in the designated direction. When the original object's Address is a Bit Address, the automatic address increment is performed in the unit of bit, and when it is a Word Address, the automatic address increment is performed in the unit of word.
If the automatic address increment is not used, Parts will be copied using the same address as their original ones.

Note: **When the original object's Address is a symbol/Logic symbol, the automatic address increment is not performed.**

E.g.) When duplicating with the settings shown below:

◆ **Apply Device Comment**

When the [Apply Device Comment] check box is marked with a check, the device comment corresponding to an address assigned by the automatic address increment will be reflected in the Description Field. For Parts designating multiple Addresses, however, the device comment corresponding to an Address designated as the Reflected Description Address is reflected. The Reflected Description Addresses for different Parts are shown in the table below:

<Reflected Description Address Table>

Object name	Automatic input address
Bit Switch	Operation bit address
Word Switch	Word address
Function Switch	
Lamp	Bit address
Bar Graph	Word address
Pie Graph	Word address
Half-pie Graph	Word address
Meter Graph	Word address
Trend Graph	Channel 0 word address
Keypad	
Keypad Input Display	Word address
Alarm	Word address
File Name Display	
Data Logging Display	Block number designated address
Numeric Display	Word address
Message Display	Address
Date Display	
Time Display	
Graphic Display	Address
Window Parts	Word address
Data Sampling	Sampling Address

■ **Duplicating**

PROCEDURE	REMARKS
<When Duplicating a Switch 5 times in both the X and Y directions>	
(1)Select the desired object.	
(2)Select the pull down [Edit] menu's [Duplicate] command.	
(3)Enter the number of copies to make in the X and Y directions, spacing between copies. If desired, click on the Address Increment check box, to increment addresses automatically. Enter **5** Enter **5**	When duplicating an object, positioning will be decided based on the top left handle of the copied (master) object.
(4)Click on the [OK] **button to duplicate the object.**	To cancel the duplication, click on the [⟲] icon. To stop duplicating, press the [Esc] key.

2.3.9	Delete

Here, the procedure for deleting an object is explained.

■ **Deleting an Object**

PROCEDURE	REMARKS
(1) Select an object.	
(2) Select the pull down [Edit] menu's [Delete] command, or click on the ☐ icon.	Instead of selecting the [Delete] command, the computer keyboard's Delete key can also be used. To cancel the deletion, click on the ⟲ icon.

2.3.10 **Align**

Here, the procedure for aligning and centering object(s) are explained.

■ **Alignment Dialog Box**

Shows the current alignment settings

Resets the X axis settings

Aligns above the X axis

Aligns on the X axis

Aligns below the X axis

Resets the Y axis settings

Aligns to the left of the Y axis

Aligns on the Y axis

Aligns to the right of the Y axis

■ **Aligning Object Positions**

| PROCEDURE	REMARKS
(1)Select all the desired objects to be aligned.	▼**Reference**▲ *2.3.1 Selecting Objects*
(2)Select the [Edit] menu - [Align] command, or click on the ___ icon.	
(3)Select the type of alignment from the Alignment dialog box. In this example, select the ▢ icon (X-axis: Bottom) and do not select any vertical (Y-axis) position.	While an individual label can be aligned, groups of labels cannot. (Click on an object to select its handles and then click on its Label to select the Label's handles.) Text characters on both Numeric or other types of Displays can be aligned in the same manner. To align objects, combine the selections shown below: Horizontal position: Up, Center, Bottom Vertical position: Left, Center, Right
(4)Click on the [OK] button to align the objects.	To cancel the alignment, click on the ▢ icon.

2.3.11	**Rotate Left/ Rotate Right**

With this command, an object can be rotated in 90º increments. However, loaded Screens and Marks, and grouped objects cannot be rotated.

■ Rotating an Object Counterclockwise (Left)

| PROCEDURE	REMARKS
(1)Select an object.	▼**Reference**▲ *2.3.1 Selecting Objects*
	The center point of the object is where two lines, connecting the opposite handles (other than the corner handles), cross.
(2)Select the [Edit] menu - [Rotate Left] command, or click on the icon. The object will be rotated counterclockwise 90 degrees, relative to its center point; if necessary, repeat the command.	To cancel the rotation, click on the icon. (Clicking on the icon one time reverses one 90 degree rotation.) If an object is moved outside the drawing area by rotating, the object will not be displayed on the LT screen.

■ Rotating an Object Clockwise (Right)

| PROCEDURE	REMARKS
(1)Select a desired object.	▼**Reference**▲ *2.3.1 Selecting Objects*
	The center point of the object is where two lines, connecting the opposite handles (other than the corner handles), cross.
(2)Select the [Edit] menu - [Rotate Right] command, or click on the icon. The object will be rotated clockwise 90 degrees, relative to its center point. If necessary, repeat the command.	To cancel the rotation, click on the icon. (Clicking on the icon once reverses one 90 degree rotation.) If an object is moved outside the drawing area by rotating, the object will not be displayed on the LT screen.

2.3.12   **Mirror X/ Mirror Y**

An object can be moved symmetrically around its center line with respect to the X or Y axis. The display position of Parts, Text, Load Screens, and Load Marks can only be moved symmetrically.

■ Moving Symmetrically along the X-axis

| PROCEDURE	REMARKS
(1)Select an object. 	▽**Reference**△ *2.3.1 Selecting Objects* The center point of the object is where two lines , connecting the opposite handles (other than the corner handles), cross. If an object is moved outside of the drawing area by using the Mirror X function, the part of the object outside the drawing area will not be displayed on the LT screen. To cancel the change, click on the ⌨ icon.
(2)Select the [Edit] menu - [Mirror X-axis] command, or click on the ⬍ **icon.** The object will move symmetrically with respect to the X-axis. 	

■ Moving Symmetrically along the Y-axis

| PROCEDURE	REMARKS
(1)Select an object. 	▽**Reference**△ *2.3.1 Selecting Objects* The center point of the object is where two lines, connecting the opposite handles (other than the corner handles), cross. If an object is moved outside of the drawing area by using the Mirror Y function, the overflowing part of the object will not be displayed on the LT screen. To cancel the change, click on the ⌨ icon.
(2)Select the [Edit] menu - [Mirror Y-axis] command, or click on the ◀▶ **] icon.** The object will moves symmetrically around the Y axis. 	

2.3.13	Group/ Ungroup

This function can be used to "group" multiple objects, enabling you to manipulate the "group" as a single object, even after changing screens or using a different editing function.

■ Grouping Objects

PROCEDURE	REMARKS
(1) Select the objects to be Grouped.	▼**Reference**◢ *2.3.1 Selecting Objects*
(2) Select the [Edit] menu - [Group] command, or click on the 🀫 **icon.**	To cancel the Grouping, click on the 🔄 icon.

Note:
- **When a Load Screen is included in a group, its handles appear as □ , so that the objects cannot be scaled up/down. Thus, you must first ungroup the objects in order to scale any individual object.**
- **When a Part is included in a group, double click on the group to bring up the Confirm Device Address dialog box, where address changes can be made.**

▼**Reference**◢ *2.3.15 Changing Attributes*

■ **Ungrouping Objects**

This function changes a Group of objects to a selection of multiple objects.

PROCEDURE	**R** EMARKS
(1)Select a group of objects. 	▼Reference◣ *2.3.1 Selecting Objects*
(2)Select the [Edit] menu - [Ungroup] command, or click on the 🔀 **icon.** 	To cancel the ungrouping, click on the 🔁 icon.

| 2.3.14 | **Bring to Front/ Send to Back** |

When graphics and Parts overlap each other, you can change the order of the layers with these two commands.

■ Changing the Order of Overlapping Objects

PROCEDURE	REMARKS
In this example, you will move the oval, partially hidden by the rectangle, to the front.	▼Reference▲ *2.3.1 Selecting Objects*
[Bringing an Object Forward]	
(1)Use the cursor to select the filled oval.	
(2)Select the [Edit] menu - [Bring to Front] command, or click on the ___ icon.	To cancel the movement, click on the [icon] icon.
[Sending an Object Behind]	
(1)Use the cursor to select the black rectangle.	
(2)Select the [Edit] menu - [Send to Back] command, or click on the ___ icon.	To cancel the movement, click on the [icon] icon.

2.3.15 **Changing Attributes**

Here, you can change any of an object's attributes, i.e. its color, address, etc. Also, with objects of the same type, you can change the same attribute of all the objects of that type at the same time.

■ **Changing Attributes**

PROCEDURE	REMARKS
(1) First, select an object to change its attributes. In this case, an unfilled rectangle drawn with a solid line. **(2) Select the [Edit] menu - [Change Attribute] command, or click on the ⬚ icon.** **(3) Select a new attribute from the dialog box.** Here, a dotted line is selected. **(4) Click on the [OK] button to register your change.** 	▼*Reference*▲ *2.3.1 Selecting Objects* While the attributes of Grouped objects generally, cannot be changed, the same type objects can be changed at the same time. When Grouped Parts have been selected, only their addresses can be changed. ▼*Reference*▲ *2.3.15 ■ Changing Attributes; Confirming Addresses* Instead of clicking on the ⬚ icon, simply double-click on the object when selecting it, to display the Attribute Settings dialog box (skip step {2}). To cancel the attribute changes, click on the [Cancel] button in the dialog box. You can reverse the attributes changes (only for the most recent change) by clicking on the ⬚ icon.

✎ *Note:* **You can select more than one object of the same type and change the attributes of each, at the same time. With all the desired objects selected, click on the Tool box's [Type] button; then, proceed with step (2).**

▼*Reference*▲ *2.3.1 ■ Selecting Objects; How to Select Multiple Objects; Selecting Objects by Type from a Multiple Selection*

■ **Confirming Addresses**

If a Part that requires an address has been grouped, the Confirm Device Address dialog box shown below will appear whenever its attributes are changed; the Part addresses are changed here.

Allows you to view either the Bit or Word Addresses of all the Parts in the currently selected group of objects

Part Addresses are displayed here

Check this box to automatically change all the addresses of the Parts in this group that have the same Device Address

◆ **Address**

Each Part's address is displayed. To change an address, click on the inside of each cell. As shown above, any Switches selected that have state changes will have both their Operation Bit and their Monitor Bit addresses displayed.

◆ **Address Range Conversion**

When an address is changed and this check box is checked, any other Part with the same device address will be automatically changed.

Note: **The address conversion is not performed in the case of symbol/Logic symbol.**

In the example above, if the first bit address is changed from X00000 to X00010, the following bit addresses will be changed as below.

Clicking on any cell other than the changed one will show the changed address

2.3.16　　**Changing Coordinates**

Object positions and sizes can be changed by specifying their coordinates.

Check this check box to change the size.

Enter the object's left top coordinates.

Enter the object's right bottom coordinates.

■ Using Coordinates to Change an Object's Position

PROCEDURE	R EMARKS
(1) Select a desired object.	▼**Reference**◄ *2.3.1 Selecting Objects*
(2) Select the [Edit] menu - [Change Coordinates] command.	
(3) Enter the object's left top and right bottom coordi-	To change the size, check the Change size check box in step (3). To cancel the coordinates change, click on the 〔 Cancel 〕 button. To undo the coordinates change, click on the 〔🔄〕 icon.
(4) Click on the 〔 OK 〕 button to execute the command.	

| 2.3.17 | Editing the Node of a Multi-segment Line |

Creating, Editing, or deleting a node can be performed on a multi-segment line and a filled polygon.

The [Node Edit] dialog displays.

Deletes the selected peak.

Adds a node. The added node is the same as the selected node. If the screen capacity is exceeded by the added value, the [Insert in Front] and [Insert in Back] buttons are highlighted and cannot be specified.

If the node edit is selected, the selected point in the displayed dialog is marked with a cross.

■ Editing a Node on a Continuous Line

PROCEDURE	REMARKS
(1) Select the desired continuous line. (2) Select [Node Edit(K)] from [Edit(E)]. (3) Select the coordinate value that you want to edit. (4) Click on the [Edit] button. (5) Enter the X/Y coordinate values in the coordinate change dialogs.	▼Reference▲ *2.3.1 Selecting an Object*
(6) Click on the [OK] button to run the coordinate change.	To cancel the coordinate change, Click on the [Cancel] button.

2.3.18 ▸ **Convert (Import) Image**

This section describes how to convert image data (bitmap: BMP file and JPEG: JPEG file), created from other drawing software or imported from a scanner, for use on a LT Image (I) screen.

▽**Reference**△ For Image Conversion data, refer to ***3.2 Creating an Image: the Image Screen***.

■ **Converting and Placing an Image**

PROCEDURE	REMARKS
(1) Select the pull down [Edit] menu's [Convert Image] command.	Once an image has been converted, it can be placed on a screen using the Load Screen function.
(2)Set all conversion settings and click on the `Convert` **button.**	▽**Reference**△ ***2.2.10 Load Screen***
	▽**Reference**△ For each setting item, ***3.5 Creating Image Data - Image.***
	Before conversion, the image displayed in the Import Image dialog box is still compressed and may appear different from the actual display (after conversion).
(3)Click on the `Save` **button.** The bit map is then saved as an Image screen.	To cancel the conversion, simply click on the `Cancel` button.

P ROCEDURE	R EMARKS
(4)Click on the [Place] **button.** The Image screen's border will appear on the current screen. 	
(5)Click on the point where the Image screen is to be placed. The Image screen will appear on your screen. 	To cancel the placement, click on the [↩] icon.

Note: • **If a portion of an Image screen extends over a Base screen's Y axis border, that portion will not be displayed on the LT screen. When the Image screen is placed over the Base screen laterally, however, any part that extends over the Base screen X axis border will be squeezed onto the LT screen.(i.e. not cut)**

Example)   When using LT Editor   When using the LT
           for Windows   panel display

Drawing
Areas

■ **Pasting images with other file formats**

The paste function can be used for images copied onto the Clipboard [*1].
Executing the [Paste] command from screen editor while a copied image is in the clipboard will display the "Paste Image" dialog box on the screen. The "Source" tab will not be displayed on the screen.When images cannot be pasted with this procedure, convert the images into bitmap files or JPEG files with other image processing software before copying and pasting it to the screen editor.

---

1 The clipboard is a storage location where copied or cut data is temporarily stored. The data stored on the clipboard can be copied or moved by pasting it.

▶ **2.3.19**   **Transferring a Screen to the Clipboard**

The current screen is transferred as an image to the clipboard[*1]. The transferred screen can be utilized by pasting it to other drawing software. The screen types that can be transferred to the clipboard are the Base (B) screen, Mark (M) screen and Window (U) screen.

■ **Transferring a Screen to the Clipboard**

PROCEDURE	REMARKS
(1) Select the [Screen to clipboard] command from the [Edit] menu. The current screen will be transferred to the clipboard. **(2) Paste the screen to other drawing software.**	

1 An area where text, graphics, or both, that have been Cut or Copied, are temporarily stored. The contents of the Clipboard can be "pasted" (copied from the Clipboard) using the Paste function. However, once the Copy/Cut command is executed, the data stored in the Clipboard is replaced; therefore, only the data from the most recent Copy/Cut command can be Pasted.

2.3.20   **Converting a Screen to a Bitmap File**

The current screen is converted into a bitmap file, and then saved. The screen types that can be converted are the Base (B) screen, Mark (M) screen, and Window (U) screen.

```
┌──────────────────────────────────────────────────────────────────────────┐
│  Usage Pattern                                                             │
│                                                                            │
│  [Edit]  →   [Screen to      →   [Setting         →   Specify how to       │
│              bitmap file]        bitmap file]         save the bitmap      │
│                                                       file.                │
│                                                                            │
│  →   [Edit]  →   [Screen to      →   [Screen to                            │
│                  bitmap file]        bitmap file]                          │
└──────────────────────────────────────────────────────────────────────────┘
```

■ Designating a Bitmap's File Name

Before converting the screen to a bitmap file, specify how to save the bitmap file.

Specify a file name and output destination to save the file.

Automatically creates a file name to save the file.

Specify an output destination of the file when a file name is being created automatically.

Specify how a file name is to be created automatically.

```
┌─────────────────────────────────────────────┐
│ Setting bitmap file name                 [×] │
│                                              │
│  ○ Prompt for filename when saving           │
│  ◉ Automatically create file name             │
│   ┌─ File Name type ─────────────────┐        │
│   │ ◉ Type + Number .BMP             │        │
│   │ ○ Type + Number + Comment .BMP   │        │
│   └──────────────────────────────────┘        │
│   Output Folder                               │
│   │C:\PROGRAM FILES\PRO-FACE\LT\D│ [Browz]     │
│    [ OK ]    [ Cancel ]    [ Help ]           │
└─────────────────────────────────────────────┘
```

◆ Prompt for filename when saving

When the [Screen to bitmap file] command is executed, the Save As dialog box will appear, where you can specify the location and name of the file to be saved.

◆ Automatically create file name

When the [Screen to bitmap file] command is executed, a file name will be created automatically, and the file saved in a previously specified location.

Example: If the No. 1 screen of the Base (B) screen named "Menu" is converted into a bitmap file:

Screen type + number.BMP   —> B1.BMP
Screen type + number + screen title.BMP   —> B1 Menu.BMP

■ **Converting a Screen into a Bitmap File**

PROCEDURE	REMARKS

(1) Select the [Setting bitmap file] option for the [Screen to bitmap file] command from the [Edit] menu.

(2) Select a method for saving the bitmap file, and establish it by clicking on the ⟨ OK ⟩ button.

(3) Select the [Screen to bitmap file] option for the [Screen to bitmap file] command from the [Edit] menu.
When a file name is created automatically, the bitmap file is saved now.

(4) If [Prompt for filename when saving] was selected in step (2), specify a file name and output destination, and then click on the ⟨ Save ⟩ button.

2.3.21	**Redraw Screen**

This command updates the current drawing area display to reflect the latest drawing data. When the Auto Redraw feature is not used, filling and editing objects can cause after-images to remain on the screen. Use this function to remove these images and show the screen as it will appear on the actual LT display.

■ **Redrawing a Screen**

PROCEDURE	R EMARKS
Sometimes, when removing an object's filled color, only the fill point area's color will be removed, resulting in a small, non-colored square. **Point where fill began** — Fill point is deleted **(1)Select the [Edit] menu - [Redraw] command, or click on the icon.** The screen will automatically be refreshed and all the fill color will be removed.	

2.3.22   **Undo**

With this function, an operation can be "undone" and the screen display returned to the previous condition. Every time the 🔄 icon is clicked on, depending on memory, previous operations will be undone, in succession.

⚠️ *Important*   ***The Redraw Screen function cannot be undone.***

■ **Canceling an Action**

PROCEDURE	REMARKS
In this example, a circle has been accidentally deleted. (1) **Select the [Edit] menu - [Undo] command, or click on the** 🔄 **icon.** The circle will reappear and the screen is displayed as it was prior to the deletion.	To cancel the Undo operation, click on the ___ icon. ▼*Reference*▲ *2.3.23 Redo*

2.3.23   **Redo**

With this function, an operation previously undone with the Undo command can be "redone", if performed immediately after the Undo command is used.

■ **Redoing the Previous Undo Command**

PROCEDURE	REMARKS
In this example, the undone circle deletion will be re-done (i.e. deleted again). (1) **Select the [Edit] menu - [Undo] command, or click on the** 🔄 **icon.** The circle will reappear. (2) **Select the [Edit] menu - [Redo] command, or click on the ___ icon.** The circle will disappear.	To cancel the Redo operation, click on the 🔄 icon. ▼*Reference*▲ *2.3.22 Undo*

2.4 ▶ Library Items

The objects you created can be registered. These registered objects are called "Libraries". You can call up and use the registered Libraries, whenever necessary. Like a pre-made Part Shape, the objects registered in these libraries can be viewed and selected using the Browser function. Multiple objects can be combined and registered, and Marks created on Mark screens can also be registered.

▼*Reference*▲ *3.1 Creating a Mark - the Mark Screen*

These items are stored in a Library file (CPW file), separate from Project (LTE) files . When library data is a Mark, it will be saved in a Mark Library (MRK) file. Moving from one Library file to the other allows objects to be called up that were previously used in a variety of screens and Project files.

To call up an item from a Library, or save an item to a Library, either select one of the tool bar's icons [🗔][🗔] or use the pull down menu's [Library] commands.

Note: **With both Base and Mark screens open, when the Base screen where the Library Browser is remained open is changed to the Mark screen, the Mark Library Browser cannot be open on the Mark screen. When changing the screen, first close the Library Browser and change the screen, and then open the Library Browser on the newly opened screen.**

Objects called up via the [Load Screen] or [Load Mark] or [Window Parts (W)] command, as well as D-script cannot be registered.

■ Library Browser

When either [🗔] or [🗔] icon is clicked on, the Library Browser will appear.

Displays the currently selected item's registration number and title; clicking on the triangle brings up a list of the items in the current library

Menu Bar

Tool Bar

Reverse video indicates that this item is currently selected

Displays the item's registration number and title

Scrolls through the different items, either left, right, up, or down

Status Bar

■ Editing Library Items

Three Library Item editing functions are available.

Cuts a Library item (which is then moved to the Clipboard); the Library item can then be moved to another screen using the [Paste] function.

Copies the selected Library item to the Clipboard.

Pastes the Library item Cut or Copied, and temporarily stored in the Clipboard, to another screen. The Library item can also be Pasted to another Library file.

You can remove a Library item using the Delete function. To do so, select the [Delete] command from the Library dialog box's pull down [Edit] menu.

▼**Reference**◣ *2.4.3 Editing Library Items*

■ Changing the Library's Display

The Library's image display size and type can be changed. Also, you can change from one Library file to another.

◆ Library Size

When either the [magnifier], [magnifier], or [magnifier] icon is clicked on, or the pull down [View] menu's either [Normal], [Adjust to Fit], or [Full Screen] command is selected, and the Library display size can be changed. When Normal is selected, each Library size will be displayed relatively, allowing you to check the relationship between Libraries for their size. When the Adjust to Fit function is selected, the Library item will be enlarged until it fits inside the Library window's borders. When Full Screen is selected, the Library item will be displayed in its actual (LT) screen size.

◆ Library Type

When the pull down [View] menu's [All Objects], [Part Objects], or [Graphic Objects] is selected, the Library type(s) shown on the Browser can be selected.

[All Objects]	Displays all the Library items in the selected Library file.
[Part Objects]	Displays only those items that are Parts in the selected Library file.
[Graphic Objects]	Displays only those items which are not Parts in the selected Library file.

■ **Switching Library Files**

◆ **Creating a New Library File**

When the [□] icon is clicked on, or the pull down [File] menu's [New] command is selected, the Dialog box shown below will appear. When a Description is input and the [OK   ] button is clicked on, a new Library file will appear.

```
┌─────────────────────────────────┐
│ New                          ⊠  │
│ ┌─────────────┐                 │
│ Description :                    │
│ ┌─────────────────┐  ┌────────┐ │
│ │                 │  │   OK   │ │
│ └─────────────────┘  └────────┘ │
│                      ┌────────┐ │
│                      │ Cancel │ │
│                      └────────┘ │
│                      ┌────────┐ │
│                      │  Help  │ │
│                      └────────┘ │
└─────────────────────────────────┘
```

◆ **Selecting (Calling Up) another Library File**

When the [🖼] icon is clicked on, or the pull down [File] menu's [Select File] command is selected, the Library file list will appear. By selecting (dragging) the desired Library file from this list, other Library files can be called up.

Note: **Library files for GP-PRO/PBIII for Windows (Digital Electronics Corporation) (CPW file) cannot be used.**

Shows the currently displayed file's folder

Lists all the files in the currently selected folder

```
┌────────────────────────────────────────────┐
│ Select                               ? ⊠   │
│ Look in: [ cpw ]      [▼][▣][▨][▩][▦][▤]    │
│ Op5-obja.cpw                                │
│ Op5-objb.cpw                                │
│ Op5-objc.cpw                                │
│ Op5-objd.cpw                                │
│ Op5-obje.cpw                                │
│                                             │
│                                             │
│                                             │
│                                             │
│ File name:   [                  ]  [ Open ] │
│ Files of type: [Windows Library Files (*.cpw)▼] [Cancel]│
│ Description :  [                 ]           │
└────────────────────────────────────────────┘
```

Displays the currently selected file's Description data (if any)

Currently selected file's format (type)

Currently selected file's name (If desired, can be entered)

■ **Modifying Library File Names (Titles)**

Library filenames can also be changed. Simply select a library from the file list, then select [Property] from the [Edit] menu, and the Property screen will appear. Type in the filename (title) that you wish to use and click on OK.

Property	☒
Description :	OK
3state SW word	Cancel

■ **Displaying the Browser at the Top of the Normal Screen**

If the [Always on Top] option is selected from the [Window] menu, whenever the Library Browser is called up, it will be placed at the top of the current window. If this option is not selected, selecting another screen will place that screen over the Library screen, hiding it from view.

2.4.1	Registering Library Items

Here, the procedure for registering a Library is explained.

PROCEDURE	REMARKS
(1)Select objects to be registered as Library items.	▼ **Reference** ▲ *2.3.1 ■ Selecting Objects; Registering Library Items*

(2)Select the [Library] menu - [Register Library] command, or click on the ▣ icon.

<A. When registering a new Library item to the currently open Library file:>

(3)Enter the Library's registration number and description.
In the Cell Number area, the smallest of the currently open Library file's unused numbers will be automatically displayed. To change it, simply enter the desired number.

(4)Click on the ｜ OK ｜ button to register the number.
The registered Library will then be displayed in the Browser.

Remarks column:

If the Library Browser is already showing, click on either ▣ or ▣ icon in the screen editor drawing area, and the ▣ icon in the Library Browser, which will perform the function of step (2).

The following procedures will differ depending on the Library file registered.
• When registering a new Library item to the currently open Library file:
• When no Library file is displayed:
• When registering a Library item to a new Library file:
• When registering a Library item to a Library file other than the currently open one:

Up to 200 Library items can be registered in one file.

PROCEDURE	**R** E M A R K S
\<B. When no Library file is displayed:\> (3) The "New" dialog box will appear. When registering a Library item to a new Library file. *\<C. When registering a Library to a new Library file\>'s step (5)* When registering a Library item to an existing Library file: Click on the [Cancel] button. *\<D. When registering a Library item to a Library file other than the currently open one\>'s step (4)* **\<C. When registering a Library item to a new Library file:\>** (3) Click on the [Cancel] button. (4) Via the Library Browser, select the [File] menu - [New] command, or click on the [ ] icon. (5) Enter a comment and click on the [OK] button. (6) Via the Screen Editor, select the [Library] menu - [Register Library] command, or click on the [ ] icon. (7) Enter a Cell Number and Description.	Enter the file name when the Library file is saved. ▼**Reference**▲ *2.4.4 Saving Libraries and Quitting ■ Saving a Library File Under Another Name* A comment of up to 60 characters can be entered. Enter a description up to 60 characters. Enter the file name when the Library file is saved. ▼**Reference**▲ *2.4.4 Saving Libraries and Quitting ■ Saving a Library File Under Another Name*

PROCEDURE	REMARKS
(8) Click on the [OK] **button.** The newly registered Library item will appear in the Browser. **<D. When registering a Library item to a Library file other than the currently open one.>** **(3) Click on the** [Cancel] **button.** **(4) Via the Library Browser, select the [File] menu - [Select File] command, or click on the** [icon] **icon.** **(5) Select the desired Library file from the list, or input the Library file name in the file name area.** **(6) Click on the** [Open] **button to display the selected Library file.** 	A maximum of 200 Library items can be registered in each Library file. After creating a new Library item, if you attempt to create or select another Library file without first saving the item via the [Save As...] function, a prompt will appear, asking whether the newly created Library item should be saved or not. ▼ *Reference* ▲ For the procedures for saving a Library item, refer to **2.4.4 Saving Libraries and Quitting**. ▼ *Reference* ▲ *2.4 Libraries* ■ *Switching Library Files* When selecting a Library file in another directory, use the [Look in:] window. In step (5), simply move the cursor to the desired Library file name and double-click on it to open it. By doing so, the [Open] (Step 6) button does not need to be used.

P ROCEDURE	R EMARKS
(7) Via the Screen Editor, select the [Library] menu - [Register Library] command, or click on the [⬛] icon on the Draw Tool Bar.	
(8) Input a Cell Number and Description. In the Cell Number area, the smallest of the currently open Library file's unused numbers will be automatically displayed. To change it, enter the desired number. *Save Library* Cell Number : [100] OK Cancel Description : [switch]	
(9) Click on the [OK] button to register the item. The registered Library item will appear in the Browser. [ment] [100: switch ▼] 47: Volume SW se 48: Volume SW cir 50: Numeric Input 100: switch	Up to 200 libraries can be registered in one file.

■ **Using the Cut, Copy, and Paste Functions**

Library items can be Cut, Copied and Pasted from the screen drawing area to Browser. First, select the desired Library item in the drawing area, and then either Cut or Copy it; then, Paste it to the current Library Browser.

2.4.2	Placing Library Items

Here, items registered in a Library file are placed on a drawing area.

PROCEDURE	REMARKS

(1)Via the Screen Editor, select the [Library] menu - [Call Up Library] command, or click on the [ ] icon on the Draw Tool Bar.

(2)Select a Library Item to be read out from the Browser.

Library items Cut, Copied, or Pasted between the screen and the Browser. Simply select the desired Library item and perform the command.

When calling up an item from a file different than the currently displayed file, click on the [ ] icon to bring up a file list.

▽ *Reference* △   *2.4 Libraries*
■ *Switching Library files*

(3)Drag the Library item to the desired position in the drawing area.
The Library item can be placed on any open screens, and will be displayed in the drawing area. If desired use the sizing handles to alter the item's size.

The Library item's top left corner is the placement point.

To cancel the placement, click on the screen editor's [ ] icon.

▽ *Reference* △   To change a Library item's size, refer to *2.3.3 Scaling Up/Down*.

Items called up are automatically grouped. They can be freely edited after ungrouping them by clicking on the   icon.

▽ *Reference* △   *2.3.13 Group/ Ungroup*

Grouped library items containing Parts cannot be scaled up or down.

When a Library that contains Parts is called up, the Confirm Device Address screen will appear. After entering each Part's address, click on the [OK] button. To cancel these settings, click on the [Cancel] button.

▽**Reference**△ *2.3.15 Changing Attributes* ■ *Address Confirmation*

When the Library placed on the screen is double-clicked on, the Confirm Device Address dialog box shown below will appear, allowing you to change the Part's previously entered addresses.

■ **Using the Cut, Copy, and Paste Functions**

Library items can be Cut, Copied, and Pasted from the screen drawing area to the Browser. First, select the desired Library item in the drawing area and Cut or Copy it; then, Paste it to the Library Browser.

2.4.3 ▶ **Editing Library Items**

Library Items can be Edited, Deleted, Copied, Cut, or Pasted.

■ Editing a Library Item

Here, a registered Library item is edited.

PROCEDURE	REMARKS
(1)Select and double-click the Library item to be edited from the Browser. 	In order to call up a Library item from a Library file which is different from the currently displayed file, click on the 📁 icon. ▼**Reference**▲ *2.4 Libraries* ■ *Switching Library Files* When double-clicking on a Library item's title, the title editing screen will appear. (Property Screen)
(2)Edit that Library item. 	
(3)Via the Screen Editor, select the [Screen] menu - [Save] command, or click on the 💾 icon on the Main Tool Bar. 	 *Important* ***Once an item is edited, it cannot be Undone.***

■ **Deleting a Library Item**

Here, a registered Library item is deleted.

PROCEDURE	REMARKS
(1) Select the Library item to be deleted from the Browser.	In order to call up a Library item from a Library file which is different from the currently displayed file, click on the ⌧ icon. ▽ **Reference** △ *2.4 Libraries* ■ *Switching Library Files*
(2) Select the [Delete] command from the Library Browser's [Edit] menu. A dialog box appears to confirm your command.	
(3) Click on the ⟨ OK ⟩ button, and the Library item will be deleted.	*Important* **Once an item is deleted, it cannot be Undone.**

■ **Cutting a Library Item (from a Library File) and Pasting**
Here, a registered Library item is Cut and Pasted.

PROCEDURE	REMARKS
(1) Select a Library item to be cut (out) from the Browser. 	In order to call up a Library item from a Library file different than the currently displayed Library file, click on the ▨ icon. ▼*Reference*▲ *2.4 Libraries* ■ *Switching Library Files*
(2)Via the Library Browser, select the [Edit] menu - [Cut] command, or click on the ▨ icon. The selected Library will be cut. 	
(3)Open a desired Library file and, via the Library Browser, select the [Edit] menu - [Paste] command, or click on the ▨ icon. The following steps are the same as those used for a Library Item registration. **(4)Input the Item's Cell Number and Description.** In the Register Number area, the smallest number in the currently open Library file's empty numbers will be automatically displayed. To change it, input the desired number. 	To register the Library item to a new Library file, click on the ▨ icon. To register the Library item to a Library file different from the currently displayed one, click on the ▨ icon. ▼*Reference*▲ *2.4 Libraries* ■ *Switching Library Files*

PROCEDURE	REMARKS
(5)Click on the [OK] button to register the Library Item. The registered Library will be displayed on the Browser. 	

■ Copying a Library Item

Here, a previously registered Library item will be copied.

PROCEDURE	REMARKS
(1)Open the desired Library Item's Library file and select the Library item from the Browser. 	In order to call up a Library item from a Library file different than the currently displayed Library file, click on the [ ] icon. ▼Reference▲ *2.4 Libraries* ■ *Switching Library Files*
(2)Via the Library Browser, select the [Edit] menu - [Copy] command, or click on the [ ] icon. The Library item will be copied to the Clipboard.	
(3)Open the destination Library file and select the [Edit] menu - [Paste] command, or click on the Library Browser's [ ] icon.	To register the Library item to a new Library file, click on the [ ] icon. To register the Library item to a Library file different than the current one, click on the [ ] icon to call up a list of Library files. ▼Reference▲ *2.4 Libraries* ■ *Switching Library Files*

PROCEDURE	REMARKS
Hereafter, steps are the same as Library Item Registration. **(4) Input the Item's Cell Number and Description.** In the Register Number area, the smallest of the currently open Library file's unused numbers will be automatically displayed. To change it, enter the desired number. **(5) Click on the** [OK] **button to register the Item.** The registered Item will appear in the Browser.	

2.4.4   Saving Libraries and Quitting

When a Library file's contents are changed, the changed data will automatically overwrite the old data and be saved. However, if the Library file has been newly created, when you attempt to create or select another Library file, a prompt will appear asking if whether the new file is to be saved or not. When │ Yes │ is clicked on, the [Save As...] Dialog box will appear.

■ Saving a Library File Under Another Name

Here, the Library File will be saved under a different name.

PROCEDURE	REMARKS
(1)Select the [Save As...] command from the Library Browser's [File] menu.	
(2)The currently selected Library file name and its comment data, if any, will appear. Input a new file name and change the desired settings. 	The file name can be input within 255 characters, including a path and extension.
(3)Click on the │ Save │ button to save the Library. When a project with the same name already exists, a prompt asking whether the new name should overwrite the old name will appear; to do so, click on the │ Yes │ button. When you do not want to overwrite, click on the │ No │ button. 	

■ **Quitting the Library Browser**

PROCEDURE	REMARKS
(1) Select the pull down menu [File]'s [Exit] command. If a newly created Library file has not been saved yet, a prompt asking whether the new Library file should be saved, will appear. When the [Yes] button is clicked, the "Save As.." dialog box will appear, and when the [No] button is clicked, the Library file will not be saved and the Library Browser will quit. Then, a Library file creation or selection screen will appear.	Clicking on the Library Browser's top right mark [X] can also be used to quit. ▼**Reference**▲ *Saving a Library File Under Another Name*

Library Browser [X]

? Do you want to save changes ?

[Yes]   [No]   [Cancel]

2.5 D-Script/Global D-Script

The LT Editor provides a special feature that enables you to create a program to execute functions, in addition to Parts. This feature is given by D-Scripts/Global D-Scripts. The display load on the Device/PLC can be reduced significantly by creating and registering a program with D-Scripts/Global D-Scripts. D-Scripts are used on each screen and serve as programs that are only effective on that screen. Global D-Scripts serve as programs that are effective on all the screens.

Using D-Script, you can program (describe) separately the trigger used and the action it performs. Then, when the trigger conditions are satisfied, the script is performed. The procedures for writing a program with Global D-Scripts are the same as those for writing a program with D-Scripts.

Trigger: Bit Rising
Bit address: Switch
Action: [W:WORD10]=100

Parts of Logic Program Editor's logic program can be replaced by D-Script commands.

Trigger: Bit Rising
Bit address: M0050
Action: [W:D00100]=100

Parts of external device's logic program can be replaced by D-Script commands.

■ Overview

- To use D-Script for all of a project's screens, regardless of the current screen, select Global D-Script. To use the D-Script only for the currently displayed screen, select D-Script while creating that screen.

- D-Script allows you to perform Bin/BCD display format changes, text data changes, or other functions, all previously performed by the Device/PLC, via the LT.

- Since D-Script is a language program, debugging can be performed easily.

- D-Script can be programmed as a trigger to sense the leading or falling edge of a bit, to activate a timer, or to detect true or false of a given condition.

- There are three elements in a D-Script, Operators, Statements, and Operands, which can be used to program conditions in the Device/PLC.

- There are four types of commands: Drawing, Mathematical calculations, Boolean operations, and Bit operations.

- Syntax check is available during program creation.

- Syntax auxiliary function provides a pop-up keyboard for address settings to enhance programming efficiency.

- Programming commands can be entered via icons.

⚠ **Warning**
NEVER use the D-Script/Global D-Script function for the control of machines or actions which have the possibility of resulting in either operator injury or damage to equipment.

⚠ *Important*
- *D-script and Global D-script cannot be registered as Libraries.*
- *To select [Global D-Script], open any Base screen in advance.*

2.5.1   **D-Script Settings**

D-Script can be added, edited and deleted on the D-Script list. D-Script is programmed with the D-Script Editor. For details of the D-Script's commands, please refer to 2.5.2.D-Script Commands

Usage Pattern				
[Special] →	**[D-Script] or [Global D-Script]** →	Add, Modify, or Delete →	the ⎡Close⎤ or ⎡Esc⎤ key	

An example of the D-Script dialog box (the initial screen) is shown below.

Lists the D-Script ID numbers and descriptions

Adds a D-Script

Deletes a registered D-Script

Allows you to edit the contents of a D-Script

Copies the contents of a D-Script

Pastes the copied contents of a D-Script

■ **Registering D-Script Editor**

Here, additional D-Scripts can be registered. When the [Add] button is clicked on, the D-Script Editor will appear.

Enter the D-Script's ID No. (from 00000 to 99999)

Enter a description here

Displays the D-Script's command tool box

The pro-grammed "actions" (commands) of the D-Script

Message area (window)

Trigger area

Displays defined function names

◆ **ID**

Each D-Script program is uniquely identified by an ID number. Enter an ID number in the range of 00000 to 99999.

◆ **Description**

Up to 20 Single-byte or 10 Double-byte characters can be entered here as a description about the D-Script you are to create.

◆ **Show Toolbox**

When checked, the tool box appears that contains the Operators, Statements, and Operands used to create the D-Script program.

◆ **Data Type**

Designates the D-Script data format as either Bin or BCD.

◆ **Data Length**

Designates the D-Script data bit length as either 16 bits or 32 bits.

◆ **Code +/-**

Please refer to the following table when entering negative numeric data.

Data Format	Constant Entry	
	Min. Value	Max. Value
Bin16	0	65535
Bin32	0	4294967295
Bin16+/-	-32768	32767
Bin32+/-	-2147483648	2147483647
BCD16	0	9999
BCD32	0	99999999

! Important

When a D-Script's command follows another D-Script's command, enter a space between these commands.

For example, if the "not" command follows the "and" command, spacing is needed between the commands.

> ***"andnot" : Incorrect (The operation will not be performed and an error message will display on the software screen.)***

> ***"and not" : Correct***

■ Trigger

These selections designate the type of trigger used to activate your program. The possible options are "Timer", "Bit Rising", "Bit Falling", "Expression becomes Non-Zero", and "Expression becomes Zero."

◆ Timer Settings

When the designated time elapses, the statements described in the Action area of your program are performed. The timer duration can be set from 1 to 32767 seconds. The timer restarts its counting when the designated time elapses.

◆ Bit Rising

When the LT detects the designated bit change from 0 to 1, the statements described in the Action area are performed.

◆ Bit Falling

When the LT detects the falling edge of the designated bit, the statements described in the Action area are performed.

◆ Bit Dual Operation Trigger

When the LT detects the rising or the falling edge of the designated bit, the statements described in the Action area are performed.

◆ **f → t (Expression becomes Non-Zero)**

When the LT detects true of a given condition in a triggering program, the statements described in the Action area are performed only one time at the detection.

◆ **t→ f (Expression becomes Zero)**

When the LT detects false of a given condition in a triggering program, the statements described in the Action area are performed only one time at the detection.

- *The bit designated for the "Bit Rising / Falling" option must be held ON or OFF for longer than the Part scanning time (stored in LS2036).*

- *Printing or drawing operation may cause a timer delay.*

- *The Timer feature, when a screen change is performed, will reset to "0" (with D-Script). When using Global D-Script, the timer continues the current counting.*

- *The timer may produce "designated time" or "Part scanning time" errors.*

▼ Reference ◣ *Device/PLC Connection Manual, 1.1.4/4.1.3 Special Relay*

- *Writing on the external device must be performed at an interval longer than a cycle time. If writing on the external device is frequently performed using a part scan counter of the special relay inside the LT as a trigger, communication errors may occur.*

- *The expressions specified in "f → t (Expression becomes Non-Zero)" or "t → f (Expression becomes Zero) must be held for longer than the Tag scanning time (stored in LS2036).*

⚠️ *Important*

- *When the bit used for the D-Script Trigger Condition is set for "touch" and that bit turns OFF during D-Script processing, the timing used when pressing the touch area repeatedly can prevent the detection of the bit's rise.*

- *The D-Script trigger will compare the previously read out value to the currently read out value to determine if the trigger is now "True". However, during a single scan, the value that is stored in the bit address used during the Trigger operation is kept the same, even if the value is changed during execution. The new value is read out only after the next scan begins.*

Ex. When Touch is used to turn trigger bit (LS010000) ON, and D-Script turns the value OFF:

> Trigger: Leading Edge of Bit ([b:LS010000])
> Execute: clear ([b:LS010000])

◆ **D-Script Processing Timing Chart**

As an example, if the D-Script touch timing is not used, and only detection is performed, the processing will be as follows.

Using an if() statement to detect a trigger

The if statement is used to detect when the bit is set using a touch. Prior to performing the processing, the value is read out and compared.

Trigger: **Bit rising ([b:LS203800])**
Execute: **if([b:LS010000]==1).**
{
        clear(b:LS010000])
        :

When this type of D-Script is created, even if touch input is done repeatedly, the tag scan is performed as shown in the following timing chart. Here, each tag scan value is read out, the condition is compared and, regardless of the previous value, if it agrees with the condition, the processing is performed.

◆ **D-Script Processing Timing Chart**

■ **Functions**

A D-Script program can be created using Functions. A program created as a Function can be used on the same screen or on other screens. The Functions can be used commonly for D-Script and Global D-Script.

Functions:

Call	New
Edit	Delete
Copy	Paste

◆ **Call**

Select a Function name to be loaded and then click on this button. After clicking on the Load button, the called-up Function name will be displayed in the formula area.

◆ **Edit**

Select a Function name to be edited and then click on this button. Use the D-Script Function dialog box to perform editing.

◆ **Delete**

Click on this button to delete a created Function. First, select a Function name to be deleted and then click on the Delete button.

◆ **Copy**

Any selected function can be copied.

◆ **Paste**

Use this command to paste a copied function.Click on this button and the following dialog box will appear. Then, enter the name for the function to be pasted.

Duplicate D-Script Function Name

Please enter a new function name:

function1

| OK | Cancel |

■ **Definition of Functions**

When the [New] icon is clicked on in the D-Scrip Editor, the D-Script function setting screen will appear.

Displays the D-Script command tool box when this check box is checked

Enter a function name

Enter the D-Script's action (program) to perform

Message area (window)

Displays defined function names

◆ **Function Name**

Enter the name of your Function here. Once a Function is created, that Function name is displayed in the Function area. Up to 20 characters can be used for a Function name. (Alphabet characters, numbers, and "_ ")

⚠ *Important*

The following function names are reserved. DO NOT use these names.

"rise", "fall", "rise_expr", "timer", "set", "clear", "toggle", "if", "else", "endif", "b_call", "Bcall", "dsp_rectangle", "dsp_line", "dsp_dot", "dsp_circle", "dsp_arc", "Call", "and", "or", "not" "memcpy", "memset", "loop", "break", "IO_READ", "IO_WRITE", "_memcpy_EX", "_memset_EX", "IO_READ_EX", "IO_WRITE_EX", "IO_READ_WAIT", "databuf0", "databuf1", "databuf2", "databuf3", "_strset", "_dlcopy", "_hexasc2bin", "_decasc2bin", "_bin2hexasc", "_strlen", "_strcat", "_strmid", "_wait", "return"

■ **Deleting D-Script Settings**

Here, existing D-Script settings can be deleted. After selecting the D-Script settings to be deleted from the listing, and clicking on the [Delete] button, the Confirm Script Delete dialog box will appear. When the [Yes] button is clicked on, the D-Script settings will be deleted. When the [No] button is clicked on, the deletion command will be canceled.

■ **Editing D-Script Settings**

Here, registered D-Script settings are changed. After selecting the D-Script settings to be changed from the D-Script list and clicking on the ⌈ Modify ⌉ button, an additional registration screen will appear. Click on the ⌈ OK ⌉ button to change the D-Script settings. To cancel the Change command, click on the ⌈ Cancel ⌉ button.

· *It is not possible to use the Project Manager [Utility]'s [Convert Address] area to modify addresses used in a D-Script. Any D-Script program that requires address conversion will need to be edited manually.*

· *If the [Save As...] function has been used to change a project file's Device/PLC, the D-Script program will not be able to automatically change those addresses.*

· *Be sure to not use D-Script to perform any life-threatening, or possibly damaging actions!*

■ **D-Script Settings: Copy and Paste**

PROCEDURE	REMARKS
(1) Select the pull down [Special] menu's [D-Script] command. (2) Click on the ⌈ Copy ⌉ button. 	
(3) When the ⌈ Paste ⌉ button is clicked on, the D-Script copied in step (2) will be added. The D-Script's ID number will automatically be assigned to the smallest number currently available. 	This D-Script can also be copied to another screen.

2.5.2   **D-Script Commands**

You can enter D-Script commands, Statements and constants using D-Script tool box.

■ **D-Script Tool Box**

The D-Script tool box contains icons for D-Script commands and Statements and constant input icons.

When the tool box check box is checked, the following tool box will appear.

■ **D-Script Toolbox**

◆ **Statements**

if() if-endif
> When a condition enclosed with brackets "( )" becomes true, the process following the "if ( )" statement is executed. The Assign "=" character cannot be used in a conditional expression.

if()else if-else-endif
> When a condition enclosed with brackets "()"becomes true, the process following the if "()"statement is executed. When the condition is false, the statement after "else" is executed. The Assign "=" cannot be used in a conditional expression.

Note: ▼ *Reference* ◣   For details about the execution path, refer to **3.1.8 Conditional Branches**.

loop() loop-endloop

Loop (repetitive) processing is repeated according to the number stored in the temporary Addresses designated in the brackets "( )".

Important

- *The loop() format is as follows:*

  E.g. loop (number of loops)<=Designates the temporary Address where the loop repetition number is designated.

  {

  Mode equation

  break   <=   Stated when escaping from the loop halfway (can be omitted)

  } endloop <=   Stated at the end of the loop

- *Only a temporary Word Address can be entered (in the paren theses).*

  (e.g.: loop ([t:000]))

- *"loop()" cannot be used for a trigger equation.*

- *The temporary Word Address value used to designate the "infinite loop" will decrease every time loop operation is performed. When the value changes to 0, the loop's operation is finished. If the temporary Word Address value designated for the "infinite loop" is modified, the loop will become end less. Also, the temporary Word Address used is designated as Global. Therefore, simultaneously using this temporary Word Address for another item means the loop's operation may be performed forever.*

- *Until loop operation finishes, screen displays of tags, etc. will not be updated/refreshed.*

- *loop() can also be nested. When it is nested, the inner-most loop() will be skipped via the "break" command.*

  loop ([t:0000])//loop 1

  {

          loop ([t:0001])//loop 2

          {

          ─────────── break// Escape from loop 2

          } endloop

  ─────────── break// Escape from loop 1

  } endloop

- *If loop operation is finished without using the escape com mand, the temporary Word Address value becomes 0.*

- *The range available for the temporary Word Address value will differ depending on the data format (Bin, BCD), bit length, and code +/- used. If code +/- has been designated and the temporary Word Address becomes a negative value, the condition is judged at the beginning of the loop and the loop processing stops.*

- *DO NOT use a PLC device in the loop formula. Instead, use an address from the LT's internal LS area's user area device, or a temporary Word Address. For example, the following de scription preforms data write to the PLC many times in a short period (100 times in the following example). This can cause a system error since communication processing (the time required to write to the PLC) cannot be performed at this speed. (The addresses entered below are just a few ex amples. The actual address entry varies depending on your PLC type.)*

E.g.

```
[t:0000] = 100                                    //Loop100 times
loop ([t:0000])
{
              [w:D0200] = [w:LS0100]              //Write data to D0200
              [w:LS0100] = [w:LS0100] + 1         //Increment  LS0100
} endloop
```

Change as follows:

```
[t:0000] = 100                                    //Loop100 times
loop ([t:0000])
{
      [w:LS200] = [w:LS0100]                       //Writes data to D0200
      [w:LS0100] = [w:LS0100] + 1                  //Increment  LS0100
} endloop
[w:D0200] = [w:LS0200]                             //Writes LS0200 data to D0200
```

- *Using "loop" or "break" a variable name for a D-Script vari able will cause an error.*

break

Halts loop operation while the loop() equation is being executed.

The "break" command can be used only in the { } section of loop().

◆ **Math (Operators)**

+ (Addition)
Adds the data in two word addresses, or the data in a word address and a constant. Any overflowing digits resulting from the operation are rounded.

- (Subtraction)
Performs subtraction on the data in two word addresses, or the data in a word address and a constant. Any overflowing digits resulting from the operation are rounded.

% (Remainder)
Detects a remainder of a division performed on the data in two word addresses, or the data in a word address and a constant. The operation result may depend on the sign of the left and right sides.

* (Multiplication)
Multiplies the data in two word addresses, or the data in a word address and a constant. Any overflowing digits resulting from the operation are rounded.

/ (Division)
Performs division on the data in two word addresses, or the data in a word address and a constant. Decimal places and overflowing digits resulting from the operation are rounded.

= (Assign)
Assigns the right side value in the left side. The left side can state a device address only, while the right side can describe both a device address and a constant. Any overflowing digits resulting from the operation are rounded.

<< (Shift Left)
Shifts the data on the left side to the left by the number on the right side. This feature supports logical shifts only.

>> (Shift Right)
Shifts the data on the left side to the right by the number on the right side. This feature supports logical shifts only.

Example: Shift Left operation (Shifts to the left by one bit.)

Before the shift

| 1 | 0 | 1 | 0 | 1 | 0 | 1 | 0 | 1 | 0 | 1 | 0 | 1 | 0 | 1 | 0 |

After the shift

| 0 | 1 | 0 | 1 | 0 | 1 | 0 | 1 | 0 | 1 | 0 | 1 | 0 | 1 | 0 | 0 |

↓   ↑

"1" is rounded off.   0

Bit-wise AND (&)

Performs logical AND of data between word devices, or between word device data and constant. Used to extract a specific bit or to mask a specific string of bits.

Bit-wise OR (|)

Performs logical OR of data between word devices, or between word device data and constant. Used to turn ON a specific bit.

Bit-wise XOR (^)

Performs exclusive OR of data between word devices, or between word device data and constant.

1's complement (~)

Inverts the bits.

Note: **For details about overflowing digits, and errors and rounded decimal places resulting from a remainder operation:**

▼*Reference*◣ *3.1.5 Notes on Operation Results*

Priority and Associativity

The following table shows the trigger priorities. If two or more operators have the same priority, follow the direction shown by the associativity.

Priority	Operators	Associativity
High	( )	→
	not, ~	←
	*, /, %	→
	+, -	→
	<<, >>	→
	<, <=, >, >=	→
	==, <>	→
	&, ^, |	→
	and, or	→
Low	=	←

◆ **Comparisons**

and (AND: Conjunction)

ANDs the right and left sides. Value 0 (zero) is regarded as OFF, and other values, as ON. "N1 and N2" is true if both N1 and N2 are ON, and false if otherwise.

or (OR: Disjunction)

ORs the right and left sides. Value 0 (zero) is regarded as OFF, and other values, as ON. "N1 or N2" is true if either N1 or N2 is ON, and false if otherwise.

not (NOT: Negation)

NOTs the right side. Value 0 (zero) is regarded as 1, and other values, as 0. "not N1" is 0 if N1 is 1, and 1 if N1 is 0.

< (Smaller than)

Compares the data in two word addresses, or the data in a word address and a constant. The result is true if N1 is smaller than N2 (N1 < N2).

<= (Equal to or smaller than)

Compares the data in two word addresses, or the data in a word address and a constant. The result is true if N1 is equal to or smaller than N2 (N1 <= N2).

<> (≠) (Not equal)

Compares the data in two word addresses, or the data in a word address and a constant. The result is true if N1 is not equal to N2 (N1 <> (≠) N2).

> (Greater than)

Compares the data in two word addresses, or the data in a word address and a constant. The result is true if N1 is greater than N2 (N1 > N2).

>= (Equal to or greater than)

Compares the data in two word addresses, or the data in a word address and a constant. The result is true if N1 is equal to or greater than N2 (N1>=N2).

== (Equal)

Compares the data in two word addresses, or the data in a word address and a constant. The result is true if N1 is equal to N2 (N1=N2).

Command		Example
Conjunction	and	if [(Arithmetic expression) and (Arithmetic expression)]
Disjunction	or	if [(Arithmetic expression) or (Arithmetic expression)]
Negation	not	if [not (Arithmetic expression)]
Smaller than	<	\<Term1>\<\<Term2>
Equal to or smaller than	<=	\<Term1>\<=\<Term2>
Not equal	< >	\<Term1>\<>\<Term2>
Greater than	>	\<Term1> >\<Term2>
Equal to or greater than	>=	\<Term1>>=\<Term2>
Equal	==	\<Term1>==\<Term2>

Note: **For details about logical operations:**

▼ Reference ◢ *3.1.6 Logical Operation Examples*

◆ **Constant/Address**

Temp. Address
    Here, a LT internal Address is specified that can be used with the program. There are 90 words (from 0000 to 0089) available for Temporary Work Address. The Temporary Work Address's initial value is not fixed.

Bit Address
    Enter a bit address.

Word Address
    Enter a word address.

Constant
    Select a constant.

Note: • **To identify data via the input data's format:**

    E.g.
    Decimal: A numeric value without leading zeros →100
    Hexadecimal: A numeric value preceding by 0x →0x100
    Octal: A numeric value preceding by a zero →0100

• **Calculation examples in hexadecimal and BCD formats**
        Hexadecimal format only
                0x270F & 0xFF00   The result is 0x2700
        BCD and hexadecimal formats
                9999 & 0xFF00   The result is 0x9900

◆ **Draw**

Circle

Draws a circle at the designated point. When the Pattern check box is checked, a filled circle will be drawn.

Select and enter the line type (or fill pattern when selecting a pattern), color attributes, center coordinates, and radius value.

Scrn (Load Screen)

This function is used to call up a previously registered Library Item. The designated screen (Base screen) will be called up at the designated X,Y coordinates.

Landscape type display

Portrait type display

Square/Rectangle

Draws a square at the designated position. When the Pattern check box is checked, a filled square will be drawn. When selecting a beveled square, a beveling dot can be entered. Select and enter the line type (or fill pattern when selecting a pattern), color attributes, and start and end coordinates.

Polyline

Draws a line at the designated position. Designate the line's type, color attributes, and start and end coordinates.

Dot

Draws a dot at the designated point. Designate a dot type, its X,Y coordinates, and its display color. 2, 3, and 5 dot groups cannot be selected.

◆ **Memory Control**

<Offset Address>

Offset Addresses

Offset Addresses can be designated. Only temporary Word Addresses can be designated for offset value storage Addresses.

The offset Address format is as follows:
(Word Address # Offset Value Storage Address)

Format:

[Word Address] # [Offset Value Storage Address]

<Constant Data Entry Ranges>

Data Format	Constant Entry	
	Min. Value	Max. Value
Bin16	0	65535
Bin32	0	4294967295
Bin16+/-	-32768	32767
Bin32+/-	-2147483648	2147483647
BCD16	0	9999
BCD32	0	99999999

E.g.   Read [w:WORD20] = [w:WORD10] # [t:0000]
          (Offset Word Address Read)

          Write [w:WORD10] # [t:0000] = 100
          (Offset Word Address Write)

This Address becomes the Word Address + Temporary Word Address value. For the above example, when the value "2" is used for [t:000], the Address becomes [w:0102].

< Offset Address >

- **The device designated as storing the offset value is not always read from the Device/PLC. It is read only when D-script processing is performed. If a communication error occurs during device read, the offset value will become 0, and the LT's internal special relay (LS2032 bit 12) is turned ON. When the data read is completed normally, this bit is turned OFF.**

- **Word Addresses used in the offset address format are not counted as D-Script Addresses.**

- **When a variable (Logic symbol) is used as an address, an integer array must be designated. For an integer array, an appropriate size required for consecutive addresses needs to be allocated.**

<Memory Copy>

```
D-Script ToolBox
┌─Functions─────────────┐
│ Memory Ops.        [▼] │
├───────────────────────┤
│ Memory Copy        [ ] │
│ Memory Set            │
│ Offset Address        │
│                       │
│                       │
│               ┌─────┐ │
│               │Entry│ │
│               └─────┘ │
├───────────────────────┤
│ ┌Statements┐ ┌Operators┐│
└───────────────────────┘
```

Memory Copy "memcpy"
   Copies device memory all at once. Data for the number of Addresses will be copied to the copy destination Word Addresses beginning from the copy original Word Address. The number of Addresses effective is 1 to 640.
Format:
   memcpy ([Copy destination Word Address], [Copy original Word Address], the number of Addresses)
Example statement:
   When copying data of WORD10 to WORD19 to WORD20 to WORD29
    memcpy ([w:WORD20], [w:WORD10], 10)

< Memory Copy (memcpy) >

• *Original copy data will be read from the PLC only once, when required. If a communication error occurs during data read, the GP's internal special relay LS2032's Bit 12 will be turned ON. When data read is completed normally, Bit 12 will be turned OFF.*

• *Although it will depend on the number of Addresses to be copied, data will be read from the original copy data, then divided into pieces and copied to the copy destination. Therefore, even if a communication error occurs during data read, data may be partially written.*

(Result of data write in the copy destination: ○: Data write completed, x: No data is written.)

<Block Memory Copy>

Copy original data

Communication error

Result of data write in the copy destination

X

<Divided Memory Copy>

Copy original data

Result of data write in the copy destination

No communication error　○
No communication error　○
Communication error　X
Communication error　X

• *As the number of Addresses increases, the more time is required for writing data to the PLC. Depending on the number of Addresses, it may take from 20 seconds to several minutes.*

• *Unless data write is completed for the designated number of Addresses, screen displays such as tags will not be updated or refreshed.*

• *If data to be written exceeds the designated device range, a communication error occurs. In this case, you must turn the GP's power OFF and then ON again to reset the GP from the error.*

• *When the data are written to the LS Area with the Memory Copy (memcpy) function, the data can be written only in the User area. Data cannot be written into the System Data area (LS0000 to LS0019), Special area (LS2032 to S2047), or Reserved area (LS2048 to LS2095). However, data can be read out from these areas.*

• *When the 32 bit device data is copied to a 16 bit device using D-Script, and the bit length is designated as 16 bits, only the data for lower 16 bits will be copied.*

E.g.: memcpy ([w:100], [w:WORD10], 3)

```
        31              0          15          0
WORD10 |     | (1) |        | (1) | 100
    11 |     | (2) |   -->  | (2) | 101
    12 |     | (3) |        | (3) | 102
```

Also, when 16 bit device data is copied to a 32 bit device, the data for the lower 16 bits will be copied and "0" will be designated for the upper 16 bits.

E.g.: memcpy ([w:WORD10], [w:100)

```
     31        0          0     15         0
100 |  (1)  |          |  0  | (1) | WORD10
101 |  (2)  |    -->   |  0  | (2) |     11
102 |  (3)  |          |  0  | (3) |     12
```

- *When 32 bit device data is copied to a 16 bit device, or when 16 bit device data is copied to a 32 bit device, if the D-Script bit length designated in D-Script is 32, the copying will be as fol lows:*

E.g.: memcpy (100, WORD10, 2)

```
       31              0          15          0
WORD10 |     (1)      |        |---(1)---| 100
    11 |     (2)      |   -->  |         | 101
                               |---(2)---| 102
                               |         | 103
```

E.g.: memcpy (WORD10, 100, 4)

```
     0        15          31              0
100 |--(1)--|          |     (1)      | WORD10
101 |       |    -->   |     (2)      |     11
102 |--(2)--|
103 |       |
```

- *If the original and destination data ranges overlap, all overlap ping data will be rewritten as follows:*

E.g.: When copying "D101 to D104" to "D100 to D103"

(Data is copied to a smaller number Address)

```
        Copy From        Copy To
D100 |          |       |   (1)    |
D101 |   (1)    |  -->  |   (2)    |
D102 |   (2)    |  -->  |   (3)    |
D103 |   (3)    |  -->  |   (4)    |
D104 |   (4)    |  -->  |          |
```

E.g.: When copying "D100 to D103" to "D101 to D104"

(Data is copied to a larger number Address)

E.g.: When copying "WORD11 to WORD14" to "WORD10 to WORD13"

(Data is copied to a smaller number Address)

E.g.: When copying "WORD11 to WORD13" to "WORD11 to WORD14"

(Data is copied to a larger number Address)

- *Although this example's function designates 2 Addresses, these Addresses will not be counted as D-Script Addresses.*
- *When using device addresses for the Assign operation, the write values will not be assigned immediately, due to the LT to PLC transmission time. (The addresses entered below are just a few examples. The actual address entry varies depending on your PLC type.)*

E.g.: memcpy ([w:D200], [w:D100], 10) //Copies "D100 to D109"
                                                                    to "D200 to D209"
        [w:D300] = [D200]   //Assigns D200 data to D300.

In this case, D100's value to be written to D200 as the operation result has not yet been assigned to D300.

<Memory Set>

Memory Set (memset)

This feature initializes all devices at once. Setting data for the number of Addresses is taken from the Set Word Address. The allowable range of Addresses is from 1 to 640.

Format:

memset ([Set Word Address], set data, number of Addresses)

Example statement:

When "0" is set to addresses WORD10 to WORD19 - memset ([w:WORD10], 0, 10)

< Memory Set (memset) >

• *As the number of Addresses increases, the more the time is required for writing data to the external device. Depending on the number of Addresses, it may take from 20 seconds to several minutes.*

• *If data to be written exceeds the designated device range, a communication error occurs. In this case, you must turn the LT's power OFF and then ON again to reset the LT from the error.*

• *Although it will depend on the number of Addresses to be copied, data will be read from the original copy data, then divided into pieces and copied to the copy destination. Therefore, even if a communication error occurs during data read, data may be partially written.*

• *Unless data write is completed for the designated number of Addresses, screen displays such as tags will not be updated or refreshed.*

• *Although this function designates Address(es), they are not counted as D-Script Address(es).*

• *When writing data to the LS Area with the Memory Set (memset) function, the data can be written only into the User area. Data cannot be written into the System Data area (LS0000 to LS0019), Special area (LS2032 to S2047), or Reserved area (LS2048 to LS2095).*

- **When using device addresses for the Assign operation, the write values will not be assigned immediately, due to the LT to PLC transmission time. (The addresses entered below are just a few examples. The actual address entry varies depending on your PLC type.)**

    E.g.: memset ([w:D0100], 0, 10)   //Initializes "D100 to D109" as 0

    [w:D200] = [w:D100]   //Assigns D100 data to D200.

In this case, value 0 written to D100 as the operation result has not been assigned to D200 yet.

- **When a variable (Logic symbol) is used as an address, an integer array must be designated. For an integer array, an appropriate size required for consecutive addresses needs to be allocated.**

◆ **Bit Control**

   <Clear Bit>

Clear Bit: clear ()
Changes the specified bit address from 1 to 0.

Example statement:
clear ([b: LS010000])

In the above example, the 00th bit of LS0100 is changed from 1 to 0.

   <Toggle Bit>

Bit toggle (invert): toggle ()
Changes the specified bit address from 1 to 0 or from 0 to 1.

Example statement:
toggle ([b: LS010000])

In the above example, the 00th bit of LS0100 is changed from 1 to 0 or from 0 to 1.

\<Set Bit\>

D-Script ToolBox

Functions

Bit Ops.

Clear Bit
Set Bit
Toggle Bit

Entry

Statements
if() | if() else
loop | break

Operators
+ | − | %

Bit set: set ()
Changes the specified bit address from 0 to 1.

Example statement:
set ([b: LS010000])

In the above example, the 00th bit of LS0100 is changed from 0 to 1.

2.5.3   D-Script / Global D-Script Limitations

◆ **Limitations on BCD format operations**

If a value which cannot be converted into BCD format is found during operation, the program stops running. These values include A to F in hexadecimal format. Do not use such values. If the program stops due to non-BCD values, bit 7 in common relay information (LS2032) in the LT turns ON. This bit does not turn OFF until the LT is turned OFF or goes offline.

> E.g. **[w:WORD20] = ([w:WORD30]) << 2) + 80**
> If WORD30 is 3, shifting two bits to the left results in 0x000C, which cannot be converted into BCD format interrupts program execution.
>
> **[w:WORD20] = [w:WORD30] << 2**
> If WORD30 is 3, shifting two bits to the left results in 0x000C. Unlike the above example, 0x000C is the result of the operation to be stored in the memory, and does not cause the program to stop.

◆ **Limitations of zero operations**

Do not divide by zero in division (/) and remainder (*) operations. If you do, the program stops and bit 8 in common relay information (LS2032) turns ON. This bit does not turn OFF until the LT is turned OFF or goes offline.

◆ **Notes on delay during assign operation**

Using a device address in an assign operation may cause write delay because the LT has to read the address data from the external device. Consider the following:

> E.g. **[w:D200] = [w:D300] + 1 ... (1)**
>   **[w:D201] = [w:D200] + 1 ... (2)**

Statement (1) assigns (D300+1) into D200. However, in statement (2), the result of statement (1) has not been assigned in D200 because of time-consuming communication with the host (Device/PLC). In such case, program so that the result of statement (1) is stored in the LS area before it is executed, as shown below.

> **[w:LS100] = [w:D300] + 1**
> **[w:D200] = [w:LS100]**
> **[w:D201] = [w:LS100] + 1**

- As a guide for D-Script programming, three addresses occupy the same amount of memory as one Parts. The maximum number of addresses available for a script is 255. However, try to use the fewest possible addresses, since the more devices that are used, the slower the response.
- The Convert Address command in the Utility menu of the Project Manager cannot convert addresses used in D-Script. Open the D-Script Editor to change these addresses.

▼**Reference**▲ *4.2.4 Converting Addresses and Device Codes*

- If you have changed the external device, the addresses used by D-Script will not be converted. Be sure to use the D-Script Editor to change these addresses.

▼Reference▲ *4.2.8 Changing Your Project's Device/PLC*

• The size of a D-Script affects the Parts scanning time. Note that using a large number of addresses may significantly degrade the performance of the program.

• Up to 9 levels of Functions can be called by a program. Do NOT create more than that.
• Up to 254 Functions can be created.
• D-Script operations activated by a trigger after the screen changes are as

Trigger Conditions		Direct Access Method				Memory Link Method			
	Current Value or Condition	Bit "0"	Bit "1"	FALSE	TRUE	Bit "0"	Bit "1"	FALSE	TRUE
Bit rise		X	◯	-	-	X	X	-	-
Bit fall		◯	X	-	-	X	X	-	-
Bit Dual Operation		◯	◯	-	-	X	X	-	-
Timer settings		X	X	X	X	X	X	X	X
Detecting true		-	-	X	◯	-	-	X	◯
Detecting false		-	-	◯	X	-	-	◯	X

◯: Operation is performed right after the screen is changed, or the power is turned ON.

X: Operation is not performed right after the screen is changed, or the power is turned ON.

* When the timer is operating, the timer starts counting right after the screen changes.
* When using Global D-Script, the operations mentioned above are performed only when the LT's power is turned ON. When the LT screen changes, however, the operation mentioned above will not be performed and the monitor operates using the trigger conditions that have been set.
* When a Global D-Script includes a timer, the timer starts counting right after the LT's power cord is connected.

📝*Note:* **Do not use the touch panel key to set the trigger bit or to operate the start bit in a program because the timing of the touch input may not be correct, resulting in the bit being improperly entered.**

• When a value is assigned to an address for switching screens while a D-Script command is being executed, the screen switching operation is processed after all D-Scripts have been processed.

Example:

ID: 00000

Data Format: Bin,   Data Length: 16 bits,   Code +/-: No Code

Trigger: Leading bit ([b:M0000])

Processing   [w: WORD10]=0 // (1)
[w: LS0008]   =30 //(2) Switches to Base screen No. 30
[w: WORD11]=1 //(3)
[w: WORD12]=2 //(4)

When the above D-Script is executed, processing of the screen switching is performed after (3) and (4) have been processed.

■ Limitations Specific to Global D-Script

- When the LT's power is turned ON, the actions shown in the table on the previous page are performed. At the screen change, this table is not applied, and the trigger conditions are continuously monitored.
- Global D-Script operation is suspended during screen changes or other LT operations.
- After the LT's power is turned ON, Global D-Script actions are not performed until all data reads are completed for the initial screen. However, after the initial screen changes, Global-D-Script actions may be performed before the data reads are completed.
- The maximum number of addresses in Global D-Script is 255. When this number exceeds 256, the D-Script does not function. Since these addresses always read data regardless of the screens, be sure to use only the minimum number of device settings in your D-Script. Otherwise, operation performance can be degraded.
- The maximum number of Global D-Scripts available is 32. The currently used function also counts as one Global D-Script. When the number of the Global D-Scripts reaches 32, any new Global D-Scripts are ignored.

2.5.4   Notes on Operation Results

■ Overflowing Digits

Overflowing digits resulting from operations are rounded.

E.g.   When performing an operation on unsigned 16-bit data:

- 65535 + 1 = 0 (Produces overflowing digits)
- (65534 * 2) / 2 = 32766 (Produces overflowing digits)
- (65534 / 2) * 2 = 65534 (Does not produce overflowing digits)

■ Difference of Residual Processing

The result of a residual processing depends on whether the left and right sides are signed or unsigned. When a remainder is produced by a division operation, an error may be created due to round up operation.

E.g.   • -9 % 5 = -4
         • 9 % -5 = 4

■ Rounded Decimal Places

Decimal places resulting from a division are rounded.

E.g.   • 10 / 3 * 3 = 9

         • 10 * 3 / 3 = 10

■ Notes on Operating BCD data

A BCD-data operation which produces overflowing digits does not give the correct result.

2.5.5   **Logical Operation Examples**

■ **Bit Operation Examples**

◆   **((100 > 99) and (200 <> 100))**

Result : ON

◆   **((100 > 99) and (200 <> 200))**

Result : OFF

◆**((100 > 99) or (200 <> 200))**

Result : ON

◆   **((100 < 99) or (200 <> 200))**

Result : OFF

◆   **not (100 > 99)**

Result : OFF

◆   **not (100 < 99)**

Result : ON

◆   **[w:WORD20] < 10**

Result : True if WORD20 is smaller than 10.(ON)

◆   **not [w:WORD20]**

Result : True if WORD20 is 0.(ON)

◆   **([w:WORD20] == 2) or ([w:WORD20] == 5)**

Result : True if WORD20 is 2 or 5.(ON)

◆   **([w:WORD20] < 5) and ([w:WORD30] < 8)**

Result : True if WORD20 is smaller than 5, and WORD30 is smaller than 8.(ON)

          False = (OFF)

2.5.6　Bit Operation Examples

■ **This section gives examples of bit operations.**

◆　**[w:WORD20] << 4**

Result: The data in WORD20 is shifted 4 bits to the left.

◆　**[w:WORD20] >> 4**

Result: The data in WORD20 is shifted 4 bits to the right.

◆ **12 (0000Ch) is stored in D301, using the BIN format.**

[w:WORD20] = [w:WORD30] >> [w:WORD31]

Result : The data in WORD30 is shifted 12 bits to the right and assigned to WORD20.

◆ **Bit AND**

0 & 0	Result : 0
0 & 1	Result : 0
1 & 1	Result : 1
0x1234 & 0xF0F0	Result : 0x1030

◆ **Bit OR**

0 | 0	Result : 0
0 | 1	Result : 1
1 | 1	Result : 1
0x1234 | 0x9999	Result : 0x9BBD

◆ **Bit XOR**

0 ^ 0	Result : 0
0 ^ 1	Result : 1
1 ^ 1	Result : 0

◆ **Bit One's complement (NOT) (When the data format is Bin16 +.)**

~ 0	Result : 0xFFFF
~ 1	Result : 0xFFFE

2.5.7   **Conditional Branches**

■ **Control Branches Using "if-endif" and "if-else-endif"**

◆   **if-endif**

if (condition)
{Process 1}
endif

If the condition is true, process 1 is executed. If false, process 1 is ignored.

E.g.   if ([w:WORD20] < 5)
{
              [w:WORD10] = 1
}
endif

If the data in WORD20 is smaller than 5, 1 is assigned in WORD10.

◆   **if-else-endif**

if (condition)
{Process 1}
else
{Process 2}
endif

If the condition is true, process 1 is executed. If false, process 2 is executed.

E.g. if ([w:WORD20] < 5)
{
       [w:WORD10] = 1
}
else
{
       [w:WORD10] = 0
}
endif

If the data in WORD20 is smaller than 5, 1 is substituted in WORD10.
Otherwise, 0 is substituted in WORD10.

2.5.8	Application Example (1)

In this example, we create a program for a temperature management system, which checks an error bit in the host (Device/PLC) to detect the temperature 70° or above and 30° or below. If an error is found, the LT displays alarm messages accordingly. This system also counts the detected errors.

Error bit	:	M0001
Temperature information	:	D200
Error counter (70C° or above)	:	LS300
Error counter (30C° or below)	:	LS301
Alarm message screen number storage address	:	LS302

(1) From the [Special] menu, select the [D-script] option.

(2) When the D-Script List appears, click on the [Add] button.

The D-Script Editor will appear.

(3) Enter an ID number and Description.

In this example, enter "00000" in the ID field, and enter "Alarm Display" in the Description field.

ID [00000]

Description:
Alarm Display

(4) Select a trigger type.

In this example, select the "Bit Rising" (left side) option and designate a bit address "M0001."

```
Trigger
  ○ ▦                          Edge Bit Address
  ◉ ╱      ○ ╲      ○ ✕     ▦ [            ▼] ▦
  ○ ƒ→t    ○ t→ƒ
```

(5) Create a program in the Action area by clicking the buttons in the Operators, Statements, and Operands areas.

Action

```
if ([w:D0200]>=70)
{
[w:LS00302]=100
[w:LS00300]=[w:LS00300]+1
}
endif
```

Program Example

```
if([w:D200]>=70)
    {                           //If 70C° or above
        [w:LS302]=100           //70C°-or-above alarm message screen No.100 //assigned
        [w:LS300]=[w:LS300]+1   //Count up errors
    }
    endif
    if([w:D200]<=30)
    {                           //If 30C° or below
        [w:LS302]=101           //30C°-or-below alarm message screen
                                //No.101 assigned
        [w:LS301]=[w:LS301]+1   //Count up errors
    }
    endif
```

(6)Click on the OK button.

The ID number and description you have entered will appear in the D-Script List window.

2.5.9   Application Example (2)

In this example, we create three interlocked switches as shown below:

SETUP	OK	RUNNING

◆ **Screen**

SETUP   Bit switch   Address : M0001, Bit operation : Set
OK   Bit switch   Address : M0002, Bit operation : Set
RUNNING   Lamp   Address : M0003

◆ **Operation Example**

Pressing the SETUP and OK keys in that order turns the RUNNING lamp ON. The host (PLC) uses M0003 as the trigger bit.

◆ **Program Example**

```
Trigger
        [ b:M0002 ] == 1
Execution
        if ( [ b:M0001 ] & [ b:M0002 ] )
        // bit set
        {
          set ( [ b:M0003 ] )
        }
        else
        // bit clear
        {
          clear ( [ b:M0003 ] )
          clear ( [ b:M0002 ] )
        }
        endif
```

2.6 Data Sampling

Designated address data is sampled and stored (backed up) in the LT unit. When using this function for a graph (Part)'s channel, Trend graph data can also be stored (backed up).

Up to 20 sets of Data Sampling can be entered, including the number of channels; the setting attributes can also be confirmed in the [Data Sampling Settings] of the [View] menu.

▼Reference◢ *2.7.6 Data Sampling List*

■ Overview

- The specified Word Address data is sampled each specified time or with a desired time cycle and stored it into the LS Area via the trigger bit.

- Data can be sampled per word, and data for up to 640 words can be stored in series.

- Sampled data can now be backed up. The backed up data can be stored in the LS Area via the Trigger Bit.

- Decide a channel name for each piece of sampling data.

- The number of channels that can be set is up to 20 for the entire system including trend graph channels. When more than 20 channels are set, channels after 20th will be disregarded according to the following rules:
  - Data sampling will be given priority over trend graphs.
  - Data sampling channel numbering will begin from those set previously.

2.6.1 Data Sampling Settings

Usage Pattern					
[Special]	→	**[Data Sampling]**	→	Add, Edit, or Delete	→	the Close or Esc key

An example of the Data Sampling Setting dialog box is shown below.

Lists the registered Data Sampling Settings' Channel name and description

Registers additional Data Sampling Settings

Changes the Data Sampling Setting attributes

Deletes the registered Data Sampling Settings

■ **Registering Data Sampling Settings**

Additional Data Sampling Settings are registered.

When the [Add] button is clicked on, the Data Sampling Setting screen
will appear.

■ **General**

The General page provides information about the current channel settings
for the Trend Graph Display.

Tag Name

Must be no more than five Single-byte
or two Double-byte characters long and
composed of letters and/or symbols.

Description

Up to 20 Single-byte or 10 Double-byte
characters can be entered as a descrip-
tion.

■ **Data Format**

Sampling Address

Designates the Word Address to be
sampled.

Trigger Bit Address

When the bit address stored here turns
ON, the sampled data will be stored into
the LS Area.

Note: **The address to be entered varies
depending on your LT and
external device. Note that the
sample screen in this manual is
just an example.**

Top Write Address

Specifies the LS Area's data storage
start address. LS0000 to LS0019 can-
not be used since they are the system
area. The "Start address + Sampling
data count +1" must not exceed
LS2031.

No. of Sampl. Addr.

Designates the number of sampled data
(items) to be stored.

⚠ **Important** *When a variable (Logic Symbol) is used as a Top Write Address,
an integer array must be designated. For an integer array, an
appropriate size required for consecutive addresses needs to be
allocated.*

BackUp

Data Backup

The sampled data will be backed up in the LT's backup memory.

Synchronous Mode

With this mode selected, when the LT's power is turned ON, data will be sampled following that data stored before the LT's power was turned OFF. With this mode unselected, when the LT's power is turned ON, data sampling will start from the value "0". For normal operation, select this mode.


Data stored in the backup SRAM is erased when:
* *The memory is initialized.*
* *Screen data is transmitted.*
* *The LT system and protocol are set up.*
* *The LT self-diagnosis "Internal FEPROM (screen area)" is performed.*

◆ **Data Storage Example**

The following is an example of data stored from the storage start address. When the trigger bit is turned ON, the data is stored into the LS Area.

* The stored data count is stored in the storage start address.

* The stored data count number "n" is in the Bin format.

* When the stored data count is less than the sampling data count, the Word Addresses up to that number will be cleared to "0".

Storage start address		
	Stored data count = "n"	**Old**
+1	Data 1	
	Data 2	
	:	
	:	
	Data n	
	:	
+m	Data m	**New**

m = Sampling data count

■ **Sampling**

Sampling Type

The method to import data from the host (Device/PLC) is specified from the following: Periodic, Trigger Control, and Trigger Sampling.

Periodic (No Trigger)

The host (Device/PLC) data is imported at the setup intervals starting from when the LT is powered up.

Periodic During Trigger

The host (Device/PLC) data is imported at the setup intervals. The data import start, pause, and clear commands will be performed according to changes to the corresponding bit in the specified Word Address.

Sample Only On Trigger

The data is sampled at the desired timing setup. Data import and data clear will be performed according to changes to the corresponding bit in the setup Word Address.

Sampling Time

Specifies the sampling time, in 1 second units, for the import of host (Device/PLC) data.

Word Address (When Periodic During Trigger option is selected)

The 00 and 01 bits of the Word Address specified here will control the data import start, pause, and clear operations.

```
 15                    01  00
┌──────────────────────┬───┬───┐
│                      │   │   │
└──────────────────────┴───┴───┘
```
[1]: Data clear   **[0]: Pause**
(With [0] →[1],   **[1]: Start**
data is cleared.)

Word Address (When Sample Only On Trigger option is selected)

The 00 and 01 bits of the Word Address settings control the Data Read Start and Clear operations.

```
 15                 01  00
┌───────────────────┬───┬───┐
│                   │   │   │
└───────────────────┴───┴───┘
```
[1]: Data clear
(With [0] → [1],   **Change: Data Import**
data is cleared)   (With [0] →[1] or [1]
                          →[0], data is imported)

Please wait until the LT confirms the status of the control bits - i.e. whether they are "0" or "1" (For Direct Access communication, either the communication cycle time or 50ms, whichever is longer).

Careful!

Note: **A delay of up to 1 second may occur from the time of data import start to actual data sampling.**

■ Deleting Data Sampling Settings

Here, the registered Data Sampling Settings can be deleted. Select a Data Sampling to be deleted from the list. When the [Delete] button is clicked on, a dialog box will appear to confirm your command. If you click on the [Yes] button, the Data Sampling will be deleted; if you click on the [No] button, the deletion will be canceled.

```
┌────────────────────────────────────┐
│ Data Sampling Setting          ⊠ │
├────────────────────────────────────┤
│  (?)   Selected Screens will be deleted ! │
│                                    │
│      ┌────────┐   ┌────────┐       │
│      │  Yes   │   │   No   │       │
│      └────────┘   └────────┘       │
└────────────────────────────────────┘
```

■ Editing Data Sampling Settings

Here, the registered Data Sampling Setting attributes can be changed. Select a Data Sampling to be changed from the list. When the [Edit] button is clicked on, the Add (registration) dialog box will appear. If you click on the [OK] button, the Data Sampling setting attributes will be changed, and if you click on the [Cancel] button, editing will be canceled.

■ Setting Up Data Sampling

The Data Sampling setup procedure is shown below.
Data Sampling samples data stored in D0102 and stores it in the LS0020 LS area.

PROCEDURE	REMARKS
(1) Select [Data Sampling] from the [Special] pull down menu.	
(2) Click on the [Add] **button.**	Up to 20 Data Sampling sets, including Trend graph channels, can be entered.
(3) Perform the data sampling settings. After the settings are all completed, click on the [OK] **button.**	Enter a Channel name of up to 5 characters.
(4) Click on the [Close] **button to quit the registration.**	

Displays the registered items

2.7   Efficient Drawing Techniques

This section explains how the use of grids, changing display states, and the help function can all help to increase your drawing efficiency.

2.7.1   Grid/Snap

Grid Points are placed at regular intervals on your screen and divide the drawing area into a coordinate "grid" pattern; when the Snap to Grid function is enabled, objects that are drawn will automatically "snap" (be aligned) on this "grid" pattern. Use the Grid Point Spacing command to adjust the density of the Grid points, and to display the grid or not. Also, grid points can be displayed as grid lines, not as dots. Grid Points are not shown on the LT unit's display.

Select the pull down menu [Option]'s [Grid/Snap] command.

■ Grid/Snap Settings dialog box

Turns the display of the Grid Points ON or OFF

Designates the Grid Point display's being drawn on top of, or under, screen objects

Turns the Snap function ON or OFF

Registers a Grid pattern.

Registers the grid pattern that has been designated in Spacing to the position highlighted in the Grid Spacing List.

Enters the desired Grid Point spacing

Sets up the grid to the optimal 20 × 20 dot size

Enter the coordinate for the start point.

Set the start point in a center area that is to be the start point for calling up the screen. (The start point is set as the default value.)

Designates the grid display style, i.e. as dots or grid lines.

◆ **Display**

Sets the Grid Point display state (displayed or not displayed).

Grid pattern display can also be changed in the Grid Tool Bar's grid pattern selection list box.

◆ **Snap**

When the Snap check box is checked, the cursor will "snap" to the grid; objects can only be drawn on points (start & end) along the grid.

Note: **Turning the Snap function ON or OFF can also be performed via the Grid/ Snap Tool Bar's icons [OFF] and [ON].**

◆ **Spacing**

The Grid Point intervals are entered here. The unit is a dot. Input the interval value for the X and Y axes, respectively. The default value is 20 dots.

When clicking on [Touch Area], a 20 x 20 dot spacing will be automatically designated, which is most suitable for the touch panel.

Select a desired grid pattern in Spacing and click on the [OK] button. Then, the selected grid pattern will be reflected to the current screen and will also be displayed as the 6th selection of the Grid Tool Bar's grid pattern selection list.

◆ **Grid Spacing List**

Clicking on the [Change] button changes Grid Spacing List's highlighted set value to Spacing's set value and registers it.

The grid patterns registered here will be displayed on the Grid Tool Bar's grid pattern selection list box. A grid pattern selected from the grid pattern selection list box will be reflected to the current screen.

◆ **Grid Shift Start Point**

The Grid Shift Start Point is entered here. The default setting has the start point in the center of the screen. Pressing the [Standard] button returns the start point to the center of the screen.

◆ **Style**

Select grid pattern display style from "Dot" and "Line".

<When selecting Dot:>

<When selecting Line:>

**2.7.2   Screen Property Settings**

Here, the screen display's environment is set up, which effects both the method used to draw screens and displaying the Part addresses. The user's work environment can be modified whenever necessary, helping to reduce the time required for drawing.

Select the pull down menu [Option]'s [Screen Property] command.

■ **Setting Screen Property - [Display]**

The display state (displayed or not) of the items such as object Fill and setting information on Parts can be selected on the screen Editor. Check the box of the items to be displayed. When a box is not checked, that item will not be displayed.
The settings on this screen will be applied to all the screens. Properties cannot be set up for individual screens.

Note: **The display state of ID numbers and Addresses can also be changed via the [Option] tool bar icons.**

◆ **Fill**

When creating a screen, the drawing can be controlled so that any Fills used will either be displayed or not. If the "Fill" check box is not checked, all Fills are not shown. Using this feature will help you to speed up screen redrawing time, and thus speed up screen creation.

Important ***When the "Fill" check box is not checked, the actual screen shown on the LT unit may differ from the screen shown on your PC. To be sure the display is correct, check the "Fill" check box ON at least once, to verify the screen, before sending screen data to the LT.***

◆ **Fill Point**

When this feature is selected, specified Fill points will appear with an "X" mark, which is especially useful when selecting Fill points.
If the Fill Points are not displayed, Fill cannot be performed while editing.

Note: **The X (cursor position) mark's color can be designated in the system's [Color] area.**

◆ **Multiple Open with Next/Prev**

When selecting [Previous Screen]/[Next Screen] from the [Screen] menu, or opening a screen with the Open Screen switch ◀ ▶, specify whether the next screen is opened with the currently active screen open or after that active screen is closed. Up to 20 screens may be opened continuously.

◆ **Display in Load Screen Object**

You can specify whether Part addresses and ID numbers on a screen which has been called up using the [Load Screen] command are displayed or hidden.

◆ **Load Screen Double Click**

Specify an edit method for editing a screen that has been called up on another screen where the [Load Screen] command was executed, or for editing a screen on the Screen List.

If [Change Attribute] is specified, the Load Screen dialog box will be opened, enabling you to select a screen to be called up (screen number).

If [Edit Screen] is specified, the screen that has been called up will be opened, allowing you to edit the data.

◆ **Window Parts**

Designate whether the contents of the window part placed on the Base screen will be displayed or hidden.

◆**Parts ID**

Designates whether or not a Part's ID number is displayed on the Base screen.

◆**Device Address**

Designates whether or not Part Addresses are displayed on the Base screen. Part Addresses appear below the ID number.

◆**Information Data Size**

Selects the character size displayed from Standard (half size) and Minimized (1/4 size) for ID No. and Address.

◆ **Used Hairline Cursor**

Changes the arrow cursor to the hairline cursor.

■ **Setting Screen Property - [Color]**

Select the Grid, Fill Point, and Screen Background colors here. When the drawn image data's and system's colors are the same, the screens will be hard to see. Here, these colors can be changed to remedy that.

◆ **Grid Color**

Selects the grid point's color.

◆ **Fill Point Color**

Fill Points designate the point where a fill will begin; this setting determines the color of the fill point.

◆ **Screen Background**

Select the Base screen's background color; the color selected here is also displayed on the LT.

> ⚠ *Important*
>
> · *If any background color is specified for the screen to be loaded, no on-screen object will be displayed on the LT unit.*
>
> · *To load a screen whose background color was specified, specify the loading position at the center of the screen.*

2.7.3	Preview Screen

With this feature, you can confirm how an image will appear on the LT unit.
This image will differ depending on each LT display device type.
Select the [View] menu's [Preview] selection.

Note: **Select "B/W" (black and white) to view the monochrome LT screen image.**

Select the type of display used

2.7.4	Screen Data List

The currently displayed screen's object locations and setting attributes are
listed in the Screen Data List.

■ Screen Data List

An example of the Screen Data List is shown below.

Displays the object placed on the currently displayed screen

Designates the type of the object to be displayed in the Screen Data List

Edits the object selected from the Screen Data List

Deletes the object selected from the Screen Data List

Highlights an object selected on the screen.

Changes the order of drawing objects

■ Screen Data Display

The designated type of object(s) data is displayed. If a grouped object contains at least one object whose type has been designated, it is displayed as an grouped object.
The Screen Data List displays the following information:

Drawing .... Type and coordinates of a drawing object
Part .... ID Number and Address
Grouped object ...... Grouped object's coordinates and each grouped object's information

Note: **D-Scripts are displayed all the time. Each D-Script shows ID and description information.**

■ Selecting an Object

The object selected from the list will be displayed with handles (i.e. selected) in the Screen Editor. To select multiple objects from the list, Left-drag them, or hold the Shift or Ctrl key down and click on desired ones.

◆ Link Select

Normally, when any object is selected with the Screen Editor, it will not be displayed on the list. If the check box for [Link Select] is marked, an object selected with the Screen Editor will also be selected (highlighted) on the list.

■ Editing an Object

To edit an object, select it from the list and click on the Change Attr button; or simply double-click on the object.

If the object is D-Script, D-Script Editor will be actuated.

Clicking on the Delete button deletes the selected object.

◆ Change Order

Objects are displayed on the list in the order where they have been drawn. If the order of objects on the list is changed, the overlapping order of drawn objects and the executing order of Parts can also be changed.

◆ Copying

Any object on the list can be copied by pressing the Ctrl + C key, or pasted by pressing the Ctrl + V keys. Multiple objects can be copied at a time by selecting them.

2.7.5   **Part Reference List**

The settings for each Part placed on the currently edited screen are listed here, for each Part type. Part settings can also be changed on the Part Reference List.

Usage Pattern	When either modifying or deleting...
[View] → [Parts List] →	Select desired Part → After selection, either modify or delete the Part → [Close] or the [Esc] key

An example of the Part Reference List on a screen is shown below.

Reflection of device comment
The device comment corresponding to an entered device address overwrites the Description field.

Changes Part's settings

Shows a list of the Parts on the currently selected screen. Simply click on the desired Part

Deletes the selected Part

Copies a Part

Pastes a Part

Stores the Parts list information as a CSV file.

Use this scroll bar to view all the data on a long screen

Closes the current screen. (The [Esc] key can also be used)

Note: **The tab width for each item can be adjusted by placing the mouse pointer on the border between items and then dragging it.**

■ Editing Items on the Part Reference List

Part setting data can be changed directly on the Part Reference List.
Click on the left-most number of a Part to be changed, and it will be highlighted; then, click on the [Edit...] button, and the Part's Dialog box will appear and its settings can be changed.
Setting items, such as the Description and Address areas, can be changed via the Part Reference List. Also, items displayed in gray can be changed in the dialog box by double-clicking on the inside of their border.

	Part ID	Description	Data Address	Display M...	Data Format
1	BA_001	_ _ _ _ _	0000	+	Abs. Bin

Can be edited directly   **Can be edited by double-clicking**

Note: **For the labels and messages of more than one line, use "\\" as the carriage return.**

RESET BUTTON ⟺ Reset\\Button

■ Deleting Items from the Part Reference List

Parts can be deleted directly from the Part Reference List.
Click in the middle of a Part to be deleted, and it will be highlighted. Then, click on the [Delete] button, and a dialog box will appear. Clicking on the [Yes] button will delete the Part from the Part Reference List. To close the box without deleting the Part, click on the [No] button. When multiple Parts are selected, all the Parts will be deleted by clicking on the [Yes All] button, and by clicking on the [No All] button, the box will be closed.

Confirm Delete

? Are you sure you want to delete: BS_001?

[Yes] [Yes All] [No] [No All] [Cancel]

■ Copying a Part on the Parts List

Any Part can be copied on the Parts list.

Select the left-most number for the Part being copied by clicking on that number. The selected Part will be highlighted. After this selection, click on the [Copy] button and then the [Paste] button. The Part will be copied to the bottom line of the list.

■ Reflecting a Device Comment on the Parts List

The device comment corresponding to an entered device address can be entered on the Parts list by clicking on a specified button. This can be done in either of the following two ways:

1. Select the address setting field and click on the [Apply Device Comment] button.

   The device comment corresponding to the selected address will be reflected in the Description field.

2. Select a Part by its line and click on the [Apply Device Comment] button.

   If there are multiple address setting items for that Part, the description corresponding to the address specified in the [Address Table for Automatic Input of Device comment] will be reflected in the Description field.

▼*Reference*▲   *2.3.8* ◆ *Reflection of Device Comments*

■ **Exporting to a CSV File**

The Parts list information can be saved as a CSV file.

You can also select whether the currently selected page (tab)'s information will be exported or the entire page will be exported.

2.7.6   Data Sampling List

Data Sampling List shows data sampling settings created in the edited project file. You can confirm the status of each data sampling setting there. You can also change the data sampling settings on the list.

Usage Pattern	
	When editing or deleting...
[View] → **[Data Sampling List]** →	Select Desired Item and Edit or Delete It → Close / or the Esc key

The following is the Data Ssampling List (local) screen example.
The edit method of this list is the same as that of the Parts list.

▼ *Reference* ▲ *2.7.5 Parts List*

[All] tab

Using Device Comment Here, the device comment that corresponds to an device address is automatically written in the Description field.

Click on Close **to close the Data Sampling Setting List screen. Pressing the** Esc **key will also close the screen**

Opens the selected Data Sampling Setting for editing

Deletes the selected Data Sampling Setting

Copies Data Sampling Setting

Pastes Data Sampling Setting

Moves Data Sampling Setting one position higher on the list

Moves Data Sampling Settingone position lower on the list

[Setup Channel] tub

Saves the Data Sampling Setting List in a CSV file

Scrolls the display left, right, up and down when the Data Sampling Setting List is bigger than the screen size

Note: **The tab width for each item can be adjusted by positioning the mouse pointer on the border between items and then dragging it.**

■ Changing the Data Sampling Setting Order

The Data Samplings will function in the order that they have been set up (the order displayed on all the pages of the Data Sampling List) on the LT screen. To change this order, click on either the ⎹ Move Up ⎸ or ⎹ Move Down ⎸ key. When multiple Data Sampling are grouped, that group will be moved up or down.

■ Exporting a CSV File

The Data Sampling Setting list information can be saved as a CSV file.

▼*Reference*▲ *2.7.5 Parts List* ■ *Exporting a CSV File*

2.7.7 Cross Reference List

The Cross Reference List feature is useful when displaying the current address condition of Parts and other items. Here, the exact address used for each Part can be checked.

Cross reference will be displayed for local settings (each screen's Parts and D-scripts), and data sampling and global D-scripts registered for all the screens. For the global cross reference, setting display will not be sorted for each functions and screens, but the address designation conditions will be displayed for the entire Project File.

Note:
· **Since, to display the global cross reference, address information for all the screen will be acquired, it can take a long period of time.**

· **The global cross reference does not display the condition of addresses that have been designated via [LT System Settings].**

■ **Cross Reference (Local, Data Sampling, Global D-script)**

Usage Pattern					
[View] →	[Cross Reference List] →	[Local] or [Data Sampling] or [Global D-script]	→ Select either Word or Bit units	→ Confirm →	Close or the Esc key

An example of the Cross Reference List dialog box (in the case of Local) is as shown below.

Select whether to display by Bit Address or Word Address

Click to change the Display Start Address

Selects the Address Display condition

■ **Global Cross Reference**

The global cross reference has two display methods, i.e. list display same as the standard cross reference and address map display.

This feature enables you to go to the screen that uses the address you want to edit, to convert addresses in one operation, and to make a reference to an address.

· **Limitations exist regarding the display of the following addresses with the global cross reference that was designated when the LT System was set up. (To set up the LT system settings, select** GP Setup **from the Project Manager menu, and configure the settings in the [LT System Settings] dialog box.)**

· **The [Watch Dog] address designated on the [Extended Settings] tab will not be displayed when the "Time" is set to "0" seconds.**

· **As for the [System Start Address] designated on the [Mode Settings] tab, only the designated System Start Address will be displayed regardless of the total number of words used in the system area and the reading area size.**

```
┌─────────────────────────────────────────────────────────────────┐
│  Usage  Pattern                                                   │
│                                      [List]                       │
│                      [Global Cross          Start address search. │
│  [Utility]  →        Reference]       or  →                       │
│                                      [Map]                        │
│                                                          Close    │
│               Select either Word or                        or     │
│            →  Bit Address.         →  Confirm →   the  Esc  key    │
│                                                                   │
│                                                 Open Screen... to │
│                                              →  edit address      │
│                                                                   │
│                                              →  Convert Addresses... to │
│                                                 change addresses  │
└─────────────────────────────────────────────────────────────────┘
```

The following is the overview for the global cross reference screens.

◆ **List Display**

For local settings, which screen is used, and for global settings, function type will be displayed, respectively.

Selects whether setting conditions are displayed for Bit Addresses or for Word Addresses.

Changes the display start address to be displayed.

Selects the range of Addresses to be displayed.

Click to select the screen in which the address you want to edit is used, or go directly to the desired screen.

Click to convert the addresses in one operation. ▽*Reference*△ *4.2.4 Converting Addresses and Device Codes*

◆ **Address Map Display**

When selecting Word Address, the table cells from Word Address Bits 0 to 15 (for 32 bit device, from 0 to 32) will all be filled. When selecting Bit Address, only bit cells currently used will be filled.

Selects whether setting conditions are displayed for Bit Addresses or for Word Addresses.

Displays the Bit location.

Click to select the screen in which the address you want to edit is used, or go directly to the desired screen.

Click to convert the addresses in one operation. ▽*Reference*△ *4.2.4 Converting Addresses and Device Codes*

◆ **Changing Addresses**

You may move to the drawing screen of the specified address from the global cross reference, or change addresses.

On the global cross reference list, double-click on the column of the address you wish to change. Or, click on the ⬚ Open Screen... ⬚ button to open the [Start Address] dialog box, specify the address before the change, and click on the ⬚ OK ⬚ button.

Note: **When selecting an address designated on the Base screen, Trend Graph screen, Keypad screen, Video screen or Window screen, open the screen by double-clicking on the address or by clicking on the ⬚ Open Screen... ⬚ button after selecting the desired address.**

When the specified address is used only on one screen, the screen will be displayed directly. When the specified address is used on two or more screens, the [Open Screen] dialog box appears. Select the desired screen (two or more screens can be selected) and click on the ⬚ Open ⬚ button.

The Global Cross Reference dialog box closes when the drawing screen opens.

◆ **Address Block Conversion**

The addresses listed on the Global Cross Reference dialog box (all addresses in the Project and GP system addresses, excluding the addresses registered as symbols) can be converted into different addresses in one operation simply by clicking on the ⬚ Convert Addresses... ⬚ button.

▼**Reference**◣*4.2.3 Converting Addresses and Device Codes*

The Global Cross Reference display is automatically updated after the Address Block Conversion operation.

Note:

- **Among the tags and parts, the ones corresponding to both bit addresses and word addresses are cross-referenced with both of those addresses on the Cross Reference List even if they were placed by specifying their bit addresses.**

   Example: A tag (part) placed at bit address, X0000F is displayed as word address, X00000.

- **The addresses displayed in the sample screen are an example. Note that the address actually displayed on your screen varies depending on your LT and PLC type.**

■ **Changing Display Addresses**

For cross reference and global cross reference list display, when selecting [Used], addresses that have been used for the Parts and other items used in the currently open screen or Project will be displayed. When selecting "All Addresses", all the addresses beginning with the Start Address will be displayed. To change the Start Address, click on the [Address...] button, and the Dialog box shown below will appear. Set the Start Address and click on the [OK] button, and the display will show from that address on.

Enter the Start Address ——

For the global cross reference's address map display, the map display start address can be designated when toggling Bit and Word display.

When clicking on [Word Address] or [Bit Address], the following dialog box will appear. After selecting Bit or Word, designate the start address. Then, click on the [OK] button and the cross reference display will start from the designated start address.

Enter an Address ——

2.7.8   Load Screen List

The Load Screen List will be displayed on the currently edited screen. With this list, you can check the setting attributes of a screen to be loaded and also can change its loading location.

Usage Pattern	When editing or deleting...
[View] → [Load Screen List] → Select a screen to be loaded → Edit or Delete → Close or Esc

General Load Screen Summary List

Lists all the screens loaded on the currently open screen. Select the desired screen to show its setting attributes.

Click on to close the Load Screen List screen. Pressing the Esc key will also close the screen

Changes Load Screen List Settings

Deletes a Load Screen List

■ **Editing via the Load Screen List**

Screen settings can be changed using the Load Screen List.
Clicking on the left-most number of a screen to be changed will select (highlight) it. Then, clicking on the [Edit] button will bring up the [Load Screen] dialog box or the currently called-up screen, allowing you to edit the screen. The procedure for calling up and then editing a screen varies depending on the settings in the [Load Screen Double Click].

▼Reference▲ *2.7.2 ■ Screen Property Settings [Display Settings]*

Any coordinate setting can be changed directly via the Load Screen List.

■ **Deleting from the Load Screen List**

Screens can be deleted from the Load Screen List.

Clicking on the left-most number of a screen to be changed will select (highlight) it. To delete multiple Load Screen Lists simultaneously, simply drag the cursor to select the screen numbers. Then, click on the [Delete] button, and the dialog box will appear to confirm the command. If you click on [Yes] button, the screen will be deleted. To cancel the request, click on the [No] button. When selecting multiple screens, click on the [Yes All] to delete all of them, and click on [No All] to cancel any deletions.

Confirm Delete   ☒

   ❓   Are you sure you want to delete: 2?

  [Yes]   [Yes All]   [No]   [No All]   [Cancel]

2.7.9   Display of Screen Level Change Structure

The nesting of Load Screens that have been set up on the currently edited screen is displayed. In this way, a multiple nesting condition can be viewed.

▽ **Reference** △   *2.2.10 Nesting*

Select the [View] menu - [Load Screen Nesting Display] command.

Load Screen Nesting   ☒

B1   [OK]
 ├── B4
 ├─ B3
 │   └── B4
 ├─ B3
     └── B4

                                     [Help]

Each screen will be displayed via the following symbols:

Screen Type	Symbol
Base screen	B
Mark screen	M
Image screen	I
Window screen	U

2.8   # DXF Conversion

This feature allows you to convert DXF (Drawing Interchange File) file data into Base screen data, and to convert Base screen data into DXF file data. (A DXF file is on Auto Cad® drawing file)

⚠ Important

- *DXF filenames must be alphanumeric.*

- *DXF can be used for the Release 12 program. If a newer version's data is used, that data will not be converted.*

- *When each object's coordinates are converted, errors may occur, thereby slightly changing them.*

- *Once a DXF file data is converted into Base screen data, even if the Base screen is again converted back into the original DXF file, or vice-versa, the resulting data my be unusable.*

- *When converting data, be sure that the screen's width and height ratio will be the same for both the Base screen and the DXF file (Screen size settings: $LIMMAX, $LIMMIN). If this ratio is different, after data is converted, object locations or shapes will also be different from the original.*

2.8.1   **Conversion from DXF File to Base Screen (DXF → Screen)**

DXF file data is converted into Base screen data.

■ **Requirements and Restrictions when Converting Data (DXF → Screen)**

- Grouped objects (Blocks) can be nested up to 10 layers (levels deep).

- The DXF file data format is ASCII. Both "CR LF" and "LF" can be used as line feed characters and will be converted correctly.

- During conversion, when the resulting output file's size reaches 16Kbytes, the conversion will quit, and subsequent data will not be converted.

- Three dimensional data cannot be converted.

- If the X,Y coordinate screen boundaries ($LIMMIN, $LIMMAX) are not set up correctly in the DXF file, after the data created in the DXF file is converted into Base screen data, it may go beyond the Base screen's display area.

- After DXF file data is converted into Base screen data, the DXF file name is used as the Base screen's description.

- When a layer's attribute has been turned OFF, that layer's data will not be converted, and only ON layer data will be converted into Base screen data.

- Fill and Oval/Arc data cannot be converted.

■ Option (DXF → Screen)

Here, select and enter the color and size used when converting data. According to the specified DXF and Base screen size, data will be relatively magnified or minimized when converted.

Convert Color
Data is converted as colored

Screen Size
Designates the screen size used after conversion

DXF size
Selects a DXF file size

◆ Convert Color

When this box is checked, DXF file data is converted as colored. When this box is not checked, DXF file data is converted as monochrome.

▼ **Reference** ▲ ■ *Color Conversion (DXF → Screen)*

◆ Convert DXF Size

The DXF file data conversion range is selected.
When "Use $LIMMIN, $LIMMAX" is selected, data in the DXF file's maximum screen area (X,Y coordinate screen boundaries) will be converted.
When "Use $EXTMIN, $EXTMAX" is selected, only data in the DXF file's object area will be converted.

◆ Convert LT Size

The Project File screen size (LT screen size) used after conversion is specified.

■ Color Conversion (DXF → Screen)

When the [Option] dialog box's [Convert Color Data] check box is checked, the DXF file's color data will be converted as follows:

DXF File Color No.	Base Screen
1 (red), 1X (red-based)	Red
2 (yellow), 5X (yellow-based)	Yellow
3 (green), 9X (green-based)	Green
4 (light blue), 13X (light blue-based)	Light blue
5 (blue), 17X (blue-based)	Blue
6 (purple), 21X (purple-based)	Purple
7 (white)	White
Other colors	White

The background color will be converted into Black.

■ Line Type Conversion (DXF → Screen)

Each DXF file's line type will be converted as follows:

DXF File	Base Screen	
CONTINUOUS	———	Solid line
DASHED	– – –	Broken line
HIDDEN	– – –	Broken line
CENTER	— · —	A dot-dash-line
PHANTOM	— · · ·	Two dot-dash-line
Other	———	Solid line

The user defined line types will be converted into solid lines.

■ Object Conversion (DXF → Screen)

The DXF file's objects will be converted as follows.
Colors and line types will be converted as shown above. Tiling patterns will be converted into solid Fill.

DXF File	Base Screen
LINE	Straight line
POINT (dot)	Straight line (The start and end are the same point)
CIRCLE	Regular circle
ARC	Arc
TRACE (thick line)	Filled polygon
SOLID (filled object)	Filled polygon
TEXT (characters and signs)	Text
DIMENSION (dimension indicator)	Straight line
INSERT (inserting object)	Conversion breaks down complex objects into component parts (objects)
ATTRIB (attribute)	Conversion breaks down complex objects into component parts (objects)
POLYLINE(polyline/donut-shaped/ oval/polygon/rectangle)	Continuous straight line
VERTEX	Vertex coordinates of a continuous straight line

Objects other than the above will not be converted.

Each object's elements, other than colors and line types, will be converted as follows:

◆ **POINT (dot)**

- A dot's pattern will be converted into "0" (point), and its display size will be converted into "0,0".
- A dot will be converted to a straight line, with the start and end coordinates at the same point.

◆ **TEXT (characters and signs)**

- A rotation angle will be converted into an angle closer to 90°, 180°, 270°, or 360°. (in 90° units)
- The character size will be converted into a size closer to either 1, 2, 4, or 8 x magnification.
- Special characters that will be converted are %%d (°), %%c (φ), and %%p (±).
- When text contains more than 100 characters, it will be divided every 100 characters into records of data and then converted.
- When more than 100 character text is divided into records of data, groups of overflowing characters after the first 100 characters will be dislocated toward the right bottom for a few dots.
- Tilting angles, character fonts, and character spacing will not be converted.
- Text will be converted based on the ASCII code; therefore, the character style (Standard, Bigfont, etc.) or font file settings will be ignored.
- When text with half-sized and full-sized characters mixed in vertical lines is converted, the half-sized characters will be centered.

◆ **DIMENSION (Dimension Indicator)**

- During conversion, the breaking down of a grouped object (Block) is performed by referring to the Block's sections, which indicate the Block's component Part (objects). However, dots will not be converted.

◆ **INSERT (Inserting Object)**

- A grouped object defined in the Block section will be broken down into each drawing object and converted.
- Up to 10 layers of nested data will be converted. However, since all the data will be converted into a single layer on a single screen, the objects over the limit (file capacity) will not be converted.
- Although the rotating angles, and the number of lines and columns can be converted (lines and columns of the objects over the limit will not be converted), their ratio (scaling) will not be converted.
- The grouped object created in Layer "0" will be converted based on the inserted layer's colors and line types, however, a grouped object created in an other layer level will not be converted based on the inserted layer's colors and line types. In this case, if BYBLOCK is specified to the grouped object, the inserted layer's colors and line types will be used.
- Simulated object sectioning (hatching) data cannot be converted, since, when the Block section's hatching data pattern is converted into each drawing object, that data size can exceed the LT file capacity.
- If another file's grouped object has been inserted or another file is referred, that grouped object will not be converted.

◆ **ATTRIB (attribute)**

ATTRIB (attribute) data is part of INSERT data.

- Attribute data will be converted in the same manner as TEXT conversion.

◆ **POLYLINE (polyline/donut-shaped/oval/polygon/rectangle)**

•POLYLINE data will be converted connecting the following VERTEX's coordinates with a continuous straight line. Only data whose polyline flag is either "0 (default)", "1 (closed polyline)", "2 (adding the fit curve vertex)", or "4 (adding the spline curve vertex)" will be converted.

•When the number of vertices exceeds 100, data will be divided every 100 vertices and converted.

•When the converted data's coordinates are repeated at the same point, the following coordinates will be omitted.

•When a polyline has curved sections, they will not be converted. Therefore, donut-shaped lines and curved polylines will be converted into continuous straight lines, connecting each coordinate point.

◆ **VERTEX**

Top coordinates of a polyline.

• A polyline's width will not be converted.

■ Converting DXF File Data to Base Screen Data

PROCEDURE	REMARKS
(1) Select the pull down menu [Utility]'s [Convert DXF] command.	
(2) Click on the DXF -> PRW **button.**	
(3) Designate the source (DXF file) and the destination (Project File), and enter the Base screen number.	To designate a folder, click on the Select button.

PROCEDURE	REMARKS
(4) Click on the [Option] **button and enter the conversion conditions.**	

(5) After all the attributes have been entered, click on the [OK] **button to registered the entered data.**

▼**Reference**▲   *2.8.1 ■ Option (DXF → Screen)*

(6) Click on the [Convert] **button to start conversion.**

If the designated screen number already exists, a prompt will appear, asking whether the new number should overwrite the old number. When the [OK] button is clicked on, the new number will overwrite the old one, and when the [Cancel] button is clicked on, the new number will not overwrite the old one.

(7) After the conversion is completed, click on the [Cancel] **button. The [DXF<->LTE Converter] dialog box will reappear.**

To convert another DXF file, DO NOT cancel here; rather, start from step (3) again.

(8) Click on the [Exit] **button to quit.**

| 2.8.2 | Conversion from Base Screen to DXF File (Screen → DXF) |

Base screen data is converted into DXF file (Drawing Interchange File) data.

LT Editor Base screen ⇒ **Convert** ⇒ **DXF file**

Can be used for CAD software for a personal computer, such as AUTO-CAD

■ Requirements and Restrictions when Converting Data (Screen → DXF)

- Only Base screens can be converted.
- Image screens called up on the Base screen will not be converted.
- Tag data will not be converted, so for example, M-tag's Marks will not be displayed after conversion.
- When text is converted, the character size and position may differ from the original due to font type difference and errors created during conversion.
- Since Load Mark will be converted into a simple straight line (i.e. no width), if it has been magnified, it will be displayed differently from the original after it is converted.

Important *If you try to convert a filled polygon that has four peaks, one of which introverts, into a DXF file, this polygon will not be converted properly.*

■ Option (Screen → DXF)

Here, select and enter color and size data used when performing data conversion.

Screen Size
Designates the LT screen size after conversion

DXF size
Designates the DXF screen size when Base screen data is converted into DXF file data

Parts State
Selects and enters the Part State when converted

◆ Convert Screen Size

The screen size of a LT unit specified in the Project File.

◆ Convert DXF Size

The DXF file size used after data is converted using data conversion is selected. The default values are the same as the Screen Size values mentioned above.

◆ Parts State

Bit .... When Part display states (ON/OFF) are specified, that Part will be converted for each display state.

Word .. Picture Display and Message Display will be converted with the display state specified here.

■ Color Conversion (Screen → DXF)

Base screen's drawing data colors will be converted as follows:

Base Screen	DXF File Color No.
Black	250 (gray)
Blue	5 (blue)
Green	3 (green)
Light blue	4 (light blue)
Red	1 (red)
Purple	6 (purple)
Yellow	2 (yellow)
White	7 (white)

■ **Line Type Conversion (Screen → DXF)**

Base screen's line types will be converted as follows:

Base Screen	DXF File
———— 1-dot solid line	CONTINUOUS
▬ ▬ ▬ ▬ 1-dot broken line	DASHED
▬ · ▬ · · 1-dot one-dot-dash line	CENTER
▬ · · ▬ 1-dot two-dot-dash line	PHANTOM
———— 2-dot solid line	CONTINUOUS
▬ ▬ ▬ · 2-dot broken line	DASHED
▬ · ▬ 2-dot one-dot-dash line	CENTER
———— · · 2-dot two-dot-dash line	PHANTOM
———— 3-dot solid line	CONTINUOUS
———— 5-dot solid line	CONTINUOUS

The line thickness will be converted in the same thickness for all the lines, regardless of the line types.

■ **Object Conversion (Screen → DXF)**

Base screen's drawing data will be converted as follows.
Colors and line types will be converted as shown in the previous page's table. The background colors will not be converted. Tiling patterns will be converted into solid Fill.

Base Screen	DXF File
Straight line/Continuous straight line	LINE/POLYLINE
Square/Filled Square	POLYLINE/SOLID
Regular Circle/Filled Regular Circle	CIRCLE/CIRCLE + SOLID
Oval/Filled Oval	POLYLINE/POLYLINE + SOLID
Arc/Pie	ARC/ARC + POLYLINE
Division	Collection of lines
Filled Polygon	SOLID or POLYLINE
Load Screen	Broken down into each Part object and converted
Text	TEXT
Load Mark	POLYLINE
Part	Broken down into each part and converted

Data other than the above will not be converted.

◆ **Straight line/Continuous straight line**

• When the number of coordinates is "2", a straight line or continuous straight line will be converted into LINE. If this number is other than 2, it will be converted into POLYLINE.
• When a line has an arrow at one end, a solid filled triangle will be drawn at the end coordinates, and when a line has arrows at both ends, solid filled triangles will be drawn at both ends.

◆ **Square/Filled Square**

• Any line will be converted into POLYLINE.
• Any Fill will be converted into SOLID.

◆ **Regular Circle/Filled Regular Circle**
  • Filled regular circle's border will be converted into CIRCLE and its filling will be converted into SOLID.

◆ **Oval/Filled Oval**
  • Any lines will be converted into POLYLINE.
  • Filled oval's border will be converted into CIRCLE and its filling will be converted into SOLID.

◆ **Arc/Pie**
  • Pie's straight line section will be converted into POLYLINE.

◆ **Divisions**
  • When the divisions are marked on a straight axis, their coordinates will be calculated based on their start and end coordinates, direction, and the number of divisions, and will be converted into LINE.
  • When the divisions are marked on an arc axis, their coordinates will be calculated based on their start and end angles, external circle's radius, internal circle's radius, number of divisions, and will be converted into LINE.

◆ **Filled Polygon**
  • Fill will be converted into SOLID. However, if the number of vertices is more than 5, Fill will not be converted and only its trace will be converted into POLYLINE (CONTINUOUS).

◆ **Load Screen**
  • The screen will be retrieved from its attributes, and screen number and if it exists, and each drawing data will be converted.
  • The called up screen's data will be converted in the same layer as other drawing data.
  • Only Base screen will be converted.

◆ **TEXT**
  • Characters written horizontally will be converted into BIGFONT. Those written vertically will be converted into TATEGAKI (vertical type of BIGFONT).
  • 1/4-sized characters will be all converted into half-sized characters.
  • Half-sized (1/4-sized) characters written horizontally will be converted with a relative scale of 1/2 in the X direction, and other size characters will be converted with a relative scale of 1.
  • Both half and full-sized characters written vertically will be converted with a scale of 1 for their height and width. Therefore, the half-sized characters will become the same size as the full-sized characters.
  • Character types of "Bold" and "Raised" will not be converted.
  • Due to font difference and other elements, text will be different from the Base screen, after conversion.

◆ **Load Mark**
  • The Mark screen will be retrieved from the screen number, if that screen exists, the dot pattern will be converted into POLYLINE (CONTINUOUS).

◆ **Part**
  • Each Part's data will be converted into drawing data.

■ **Converting Base Screen Data to DXF File Data**

PROCEDURE	REMARKS
(1)Select the pull down menu [Utility]'s [DXF Conversion] command. (2)Click on the [PRW -> DXF] button. (3)Designate the source (Project File) and Base screen number and designate the destination (DXF file). (4)Click on the [Option] button and enter the conversion conditions.	To designate a folder, click on the [Select] button.

PROCEDURE	REMARKS

(5) After all the attributes have been entered, click on the [OK] button to registered the entered data.

▽**Reference**△   *2.8.2* ■ *Option (Screen → DXF)*

(6) Click on the [Convert] button to start conversion.

If the designated DXF file name already exists, a prompt will appear, asking whether the new name should overwrite the old name. When the [OK] button is clicked on, the new name will overwrite the old one, and when the [Cancel] button is clicked on, the new name will not overwrite the old one.

(7) After the conversion is completed, click on the [Cancel] button. The File Convert (DXF → Screen) dialog box will reappear.

To convert another Base screen, DO NOT stop here; rather, start again from step (3).

(8) Click on the [Exit] button to quit.

3 DRAWING APPLICATIONS - CREATING and USING SCREENS

LT Editor provides various screens for specific purposes (for example: for creating marks and images), in addition to the Base screens which are the fundamental screen used for all drawing modes. Other screens can then be loaded onto Base screens as libraries.

This chapter describes the procedure for creating these screens and their applications.

3.1 Creating a Mark: the Mark Screen

Create a mark (dot pattern) on a "Mark" screen. Using the [Draw] menu -
[Load Mark] command, you can load the created Mark onto a Base screen.

Usage Pattern						
[Screen]	→ or	**[New]**	→	Draw a Mark by turning on/ off each dot.	→	Save the Mark screen.
Click on 🗋 to open a Mark screen.						

General description of the Mark screen:

Editing Tool Bar

Drawing Tool Bar

Indicates the size of the mark loaded on the base screen (1 x 1)

Origin

Mark drawing area of 48 x 48 dots. This area is composed of 6 (verti-cal) x 6 (horizontal) blocks (Each block: 8 x 8 dots)

Displays the current cursor coordinates, based on the origin (0, 0)

Screen capacity

■ Drawing Tools

The Drawing Tool Bar icons and their corresponding drawing objects are as
follows:

Icon	Drawing Tool	Description
▫	**Dot**	Specify the ON/OFF status of each dot by clicking on each dot or dragging the mouse within a specified area.
/	**Line**	Specify the start and end points of a line and draw a line by clicking on desired points.
▢	**Square (Rectangle)**	Draw a square or rectangle by clicking and dragging to the desired size on a diagonal axis.
■	**Filled square (Filled rectangle)**	
○	**Circle/Oval**	Draw a circle or oval by clicking and dragging to the desired size on a diagonal axis.
●	**Filled circle (Filled oval)**	

Icon	Drawing Tool	Description
	Fill	Fill in an area with a desired color by clicking in the area (enclosed within lines and shapes).
	Text	Enter the text to be displayed in the mark drawing area.
	Call Up Mark Library	Select a Mark from the Mark Library
	Register Mark Library	Register a created Mark as a Mark Library.

■ Editing Tools

The Editing Tool Bar icons and their corresponding functions are as follows:

Icon	Editing Tool	Description
	Cut	Used to delete an entire Mark screen and store it in the clipboard. Using the [Paste] command, you can then paste the Mark screen onto another screen.
	Copy	Used to copy the data of the selected Mark screen in the clipboard.
	Paste	Used to paste the data temporarily stored in the clipboard onto a desired place.
	Duplicate	Used to duplicate a Mark screen's specified area.
	Delete	Used to delete a mark.
	Undo	Used to cancel the command executed immediately before, and return to the previous condition. (Undo)
	Redo	Used to redo the command canceled with the [Undo] command. (Redo)
	Mirror X	Used to move the dot pattern symmetrically relative to the vertical axis. The symmetry axis is the vertical line that divides the screen into two equal sections.
	Mirror Y	Used to move the dot pattern symmetrically relative to the horizontal axis. The symmetry axis is the horizontal line that divides the screen into two equal sections.
	Turn counterclockwise	Used to turn the Mark counterclockwise by 90°.
	Turn clockwise	Used to turn the Mark clockwise 90°.
	Reverse	Used to reverse the white/black area of a Mark.
	Transparent/ Background color	If no dots are turned ON in a block (8 x 8 dots), this block becomes transparent.

■ **Mark Drawing Area Structure**

The mark drawing area has the following structure. When you edit a Mark, you can use this for your reference.

3.1.1 Drawing a Mark

When drawing a mark you can use LT Editor's standard drawing functions. Here, the procedures for using each function are described.

■ **Drawing with Dots**

You can draw a Mark by turning ON/OFF each dot. When you click the left mouse button in the Mark drawing area, each dot turns ON (white). When you click the right mouse button in the Mark drawing area, each dot turns OFF (black).
A Mark is created with dots, and displayed in a block (8 x 8 dots). If at least one dot is turned ON in a block, the whole block is displayed when the Mark screen is loaded onto a Base screen. In this status, the ON dots are displayed in the current display color (Fg), and the OFF dots are displayed in the background color (Bg).

This dot is ON.

■ **Freehand Drawing**

PROCEDURE	REMARKS
(1) Select the [Draw] menu - [Dot] command, or click on the ▪ icon. (2) Draw a Mark by clicking on each dot or by dragging the mouse in the Mark drawing area.	

■ **Drawing a Line**

PROCEDURE	REMARKS
(1) Select the [Draw] menu - [Line] command, or click on the ⬚/ icon.	
(2) Click on a start point in the mMark drawing area and drag the mouse.	
(3) Click the end point in the Mark drawing area. A line is defined.	If you press and hold the ⬚Ctrl⬚ key in step (2), you can draw a line at an angle of 0°, 45°, and 90°.

■ **Drawing a Square (Rectangle) or Filled Square (Filled Rectangle)**

PROCEDURE	REMARKS
(1) Select the [Draw] menu - [Square/Rectangle] or [Filled Square/Rectangle] command, or click on the ☐ **or** ■ **icon.**	
(2) Click on a point (a) and drag the mouse on a diagonal axis in the Mark drawing area. 	
(3) Click on the end point (b). A square or rectangle is defined. 	If you press and hold the Ctrl key in step (2), you can draw a square.

■ **Drawing Circle (Oval) or Filled Circle (Filled Oval)**

PROCEDURE	REMARKS
(1) Select the [Draw] menu - [Circle/Oval] or [Filled Circle/Filled Oval] command, or click on the ⬚ or ⬚ icon.	
(2) Click on a point (a) and drag the mouse on a diagonal axis in the Mark drawing area.	
(3) Click on the end point (b). A circle or oval is defined.	If you press and hold the Ctrl key in step (2), you can draw a circle.

■ **Filling a Mark**

PROCEDURE	REMARKS
(1)Select the [Draw] menu - [Fill] command, or click on the 🖌 icon. **(2)Click inside the area to be filled.** The specified area will be filled.	If you click on a line, the filling mode cannot be executed. Be sure to click inside a completely enclosed area, if you do not, the entire Mark screen may be filled.

■ Entering Text

The "Text" mode allows you to enter text on a Mark screen.

PROCEDURE	REMARKS

(1) Select the [Draw] menu - [Text] command, or click on the [icon] icon.

(2) Enter character(s) and select either 8 x 16 dot font or Windows font.

(3) To use the Windows font, click on the Select Font and click on the OK button.

(4) Click on the OK button.

An outline corresponding to the entered character(s) will appear.

P ROCEDURE	R EMARKS
(5)Move the box to the desired position where the char-acter pattern will be displayed. The character pattern is displayed in the position where you click. A Mark can be created using this pattern.	If you move the character pattern to a position where another character pattern has already been created, the new pattern will overwrite the existing pattern, and the existing pattern will be deleted.

3.1.2   Editing a Mark

To edit a Mark, you can use the following editing functions. This section describes the operating procedure for each function.

■ Cutting a Mark

The "Cut" command deletes the data of the selected screen and stores it in the clipboard[*1]. (The deleted screen can be moved to another screen, but cannot be moved to the original screen.) The "Cut" command can be executed for the entire screen.

PROCEDURE	REMARKS
(1) Select the original Mark screen to be cut. This description assumes that several screens have already been opened. 	
(2) Select the [Edit] menu - [Cut] command, or click on the [✄] icon to store the Mark data in the Clipboard. Data of the original data screen will be cut. 	To delete the Mark screen, perform steps (1) and (2) only.

---

*1 When the [Copy] or [Cut] command is executed, the copied or cut data are temporarily stored in the clipboard.
When you execute the [Paste] command, the data stored in the clipboard will be pasted to the selected position.

PROCEDURE	REMARKS
(3) Select the mark screen (destination) to which the selected Mark screen will be pasted. **(4) Select the [Edit] menu - [Paste] command, or click on the ▣ icon.** Data of the Mark screen will be pasted. 	

■ Copying a Screen

The selected screen data are copied in the clipboard. Unlike the [Cut] command, the original screen data will not be deleted.

To copy a Mark into the original screen, use the [Duplicate] command.

PROCEDURE	REMARKS
(1) Select the original Mark screen to be copied. This description assumes that several screens have already been opened. **(2) Select the [Edit] menu - [Copy] command, or click on the 📋 icon to store the mark in the Clipboard.** **(3) Select the Mark screen (destination) to which the selected Mark screen will be copied.** **(4) Select the [Edit] menu - [Paste] command, or click on the 📋 icon.** Data will be copied from the original Mark screen and pasted onto the destination Mark screen. 	

■ **Copying a Specified Range : Duplication**

A specified range in the Mark drawing area can be duplicated by dots.

PROCEDURE	REMARKS
(1)Select the [Edit] menu - [Duplicate] command, or click on the 🗗 icon.	
(2) **Specify the copy range in the same manner as drawing a square/rectangle.** A box appears, indicating the specified copy range.	
(3) **Move the box to a desired position where the data in the specified range will be copied.** Data in the specified range will be copied to the position where you click.	⚠ *Important* ***If you copy a mark into the position where another Mark has already been created, the new data will overwrite the existing data, and the existing data will be deleted.*** You can continue the copy mode until you click the right mouse button.
(4) **To quit the copy mode, click the right mouse button.**	

■ Deleting a Mark

Delete the Mark, or a partion of it.

PROCEDURE	REMARKS
(1) Select the [Edit] menu - [Delete] command, or click on the ▨ **icon.**	

The procedures for deleting part of a Mark or deleting a whole mark are separately described:

[Deleting Part of a Mark]

(2) Select [Partial Clear] and click on the `OK` **button.**

```
Clear Mark Screen        ☒
  ◉ Partial Clear
  ○ Clear All
  [   OK   ]    [ Cancel ]
```

(3) Specify the range to be deleted in the same manner as drawing a square/rectangle.

| PROCEDURE	REMARKS
(4) Click in the range to be deleted. The specified range will be deleted. **[Deleting the Entire Mark]** **(2) Select [Clear All].** **(3) Click on the [OK] button to delete the entire Mark.** The entire Mark will be deleted.	

■ Mirror X, Mirror Y

The "Mirror X" and "Mirror Y" functions move a Mark symmetrically relative to the vertical and horizontal axis, respectively.

To execute the "Mirror X" and "Mirror Y" functions, click on the ◈◈ icon, respectively.

Example) Mirror X

Example) Mirror Y


■ Turn Counterclockwise [O], Turn Clockwise [N]

The "Turn Counterclockwise", "Turn Clockwise" functions turn the mark counterclockwise and clockwise 90°, respectively.

To execute the "Turn Counterclockwise" and "Turn Clockwise" functions, click on their respctive the ◔◔ icons respectively.

Example) Turn Counterclockwise

Example) Turn Clockwise

■ Reverse

This function reverses the white and black areas. In the reverse display mode, all ON dots are turned OFF, and all OFF-dots are turned ON.

To execute this function, click on the ⊞ icon.

Example)

■ Transparent/Background Color

If no dots are turned ON in a block, this block becomes transparent. When this function is set to "Background color", a block without any ON dots is displayed in the background color (Bg).

| P ROCEDURE	R EMARKS
(1) Select the [Edit] menu - [Background Color] command, or click on the ▦ icon. **(2) Click in the block to be displayed in the background color.** The border line of the specified block is changed. Every time you click in the block, the color setting is switched. **(3) Click the right mouse button to register the above setting.**	

■ Display When Called Up to a B (Base) Screen

When this function is set to "Transparent":

These blocks contain no ON-dots.

If at least one dot is ON in a block, this block is displayed in the background color. The block with no ON dots becomes transparent, and you can see the objects on the base screen.

**When this function is set to "Background color":**

The block with no ON dots is displayed in the background color.

■ **Canceling a Command: Undo**

This function is used to cancel a command and return to the previous condition immediately before the command was made.

[Undo] is only effective for the command immediately before it.

PROCEDURE	REMARKS
After deleting a circle unintentionally: **(1)Select the** 🔄 **icon.** The deleted circle is restored, and the screen returns to the previous condition. 	

■ **Redo Command**

This function is used to redo the command canceled with the [Undo] command.

The [Redo] command is effective only for the command immediately before it.

PROCEDURE	REMARKS
After deleting a circle, you have selected the 🔄 icon to return to the previous condition, but you realize that actually, the circle must be deleted: **(1)Select the** 🔄 **icon.** The screen returns to the condition where the circle has been deleted and harmony is restored. 	

3.1.3 Registering and Placing a Mark Library Item

You can register a mark created in the mark drawing area and the registered Mark can be loaded whenever required. The Mark Library Item (mark list) can be saved as a Mark library file (MRK file). The LT Editor enables you to manage MRK files independent of project (LTE) files . This function allows you to use the sameMmark for several projects, since you can select a desired Mark while checking the image displayed in the browser. Registration, placement, and other editing operations of Mark Library are performed in the same manners as those of the standard Libraries.

▼Reference◢ *2.4 Libraries*

Note: **LT Editor has pre-made MRK files in correspondence with the ISO7000 Series Marks and symbols.**

▼Reference◢ *Parts List Manual*

Drawing symbol number	MRK file name	Title
0001-0200	IS07-1	0001-0200
0201-0400	IS07-2	0201-0400
0401-0600	IS07-3	0401-0600
0601-0800	IS07-4	0601-0800
0801-1000	IS07-5	0801-1000
1001-1140	IS07-6	1001-1140

3.2 Creating an Image: the Image Screen

When you convert image data (bitmap = BMP file and JPEG: JPG file) read with an image scanner into an Image screen for the LT series, the image data can be displayed on the LT series panel. Even though your original image file can be up to 256 colors, since the LT can only display in 64 colors, the file's colors will be converted to the LT's 64 colors.
You can load an Image screen onto a Base screen, Trend Graph screen, or Keyboard screen by selecting the [Draw] menu - [Load Screen] command.

▼*Reference*◢ *2.2.10 Load Screens*

To convert image data into Image screen data for the LT series, use the [Utility] menu - [Convert Image] command.

Note:
- **The Image Screen cannot be opened with the Screen Editor.**
- **You can also perform the conversion in the screen editor by selecting the [Draw] menu - [Convert/Image] command.**

    ▼*Reference*◢ *2.3.18 Convert (Import) Image*

- **Image screens cannot be edited. To edit the image data, you must use the original file, and then convert this file into Image screen data.**
  The Image screens can be checked on the screen list.

    ▼*Reference*◢ *4.1.1 Listing/Copying/Deleting Screens*

- **This command can convert image data of up to 800 x 600 dots. Note that any portion that does not fit into the LT screen will be cut off before conversion.**

3.2.1 Image Conversion

Convert image data (bitmap: BMP file and JPEG: JPG file) created with other editor software or read with an image scanner into an Image (I) screen for the LT series.

Number of colors		1 bit	4 bits		8 bits		16-bit color	24-bit color	32-bit color
		2 colors (black & white)	16 colors	16-level gray scale	256 color	256-level gray scale			
Windows BMP/DIB		O	O	O	O	O	O	O	O
Windows BMP/DIB(RLE4)	*.BMP	-	O	O	-	-	-	-	-
Windows BMP/DIB (RLE8)		-	-	-	O	O	-	-	-
JPEG	*.JPG	-	-	-	-	O	-	O	-

With a color Image screen, when the data volume becomes large the LT series' display speed is increased. With a monochrome Image screen, the LT series' display speed is slightly lowered, but the data volume can be reduced. Select a color or monochrome Image screen according to your purpose.
If the data volume is too large to be displayed on one screen, the converted data will be divided into several screens (up to nine screens) of 50 Kbytes each.

! *Important*

· **Compressed BMP files cannot be converted.**
· **Make sure that the original image data's longitudinal dimension ("X" for the horizontal type, and "Y" for the vertical type in the figure below) is a multiple of "4" for color data, or a multiple of "8" for monochrome data. Otherwise the fractional data will be deleted from the right edge of the screen after conversion.**

Y (Vertical)

LT

X (Horizontal)

Y (Vertical)

LT

X (Horizontal)

· **If the longitudinal dimension of the original image data is less than "4" for color data, or less than "8" for monochrome data, the image data cannot be converted.**

■ Converting/Placing an Image: [Source]

Specify the image file to be converted. The information on the specified bitmap file will be displayed.

Enter the name of the image file to be converted, or select the image file from the file list by clicking on the [Browse] button

Displays information on data colors (e.g. 16 colors, 256 colors)

Displays the size of the image file

Displays the dimensions (horizontal x vertical) of the image data

Used to select the image file to be converted

Displays the image of the image file to be converted. However, this image is different from the image that will be displayed on the LT series

Used to register the above settings to execute the Image conversion. If you save the converted Image data, the Image screen of the screen number specified in [Screen Setting] will be created

Convert Images to Image Screens

Source | Effects | Destination

Image File

Browse...

Source Image

Colors

Size (bytes)

Dimensions

No image

Close   Convert   Help

■ Converting/Placing an Image: [Effects]

Specify the brightness, resolution, blinking, compression, and mirror functions for the converted image data.

Used to set the brightness and display quality automatically

Used to manually set the individual options of the brightness and display quality

When 256-colors are selected, "Blink" cannot be selected

◆ Use Default Effects

When you specify Use Default Effects, the original data will be automatically converted into the image data with the optimum brightness and display quality.

◆ Brightness

Used to convert bitmap data according to the brightness level. The reference value can be changed between levels "0" and "15". A larger value indicates a brighter image, and a smaller value indicates a darker image.

◆ Dithering

Used to set the converted data's display quality.

◆ Blink

Used to make the converted data blink.

◆ Compress

Used to compress the original image data during conversion.

◆ Mirror

Used to replace the original image data symmetrically relative to the X-axis or Y-axis during conversion.

■ **Converting/Placing an Image: [Destination]**

Select the number of colors of the converted image file

Enter the screen number of the Image screen

Select a destion to save the image screen

Enter the title of the Image screen

Displays the size of the converted screen

◆ **Screen Color**
Select the type of the converted image file: Monochrome or 8-colors. The screen size and the number of screen divisions vary depending on the selected type.

◆ **First Screen**
Enter the screen number of the Image screen. If no screen number is specified, an Image screen of the currently displayed screen number will be created.

◆ **Screen Title**
Enter the title of the Image screen. Even if the converted data are divided into several screens, only one title can be specified for one original file.

◆ **Size**
Displays the size of the converted screen.

■ **Converting an Image**

Convert an image file into Image screen data.

PROCEDURE	REMARKS
(1)Select the [Utility] menu - [Convert Image] command of the Project Manager. **(2)Click on the** ⬚Browse... **button, and select a image file to be converted.** The color type, data volume, screen size and image data of the image file will be displayed. **(3)Specify the conversion parameters.** If the data volume is too large to be displayed in one screen, the image data will be divided into several Image screens.	 If the original data are monochrome, these conversion parameters cannot be specified.

PROCEDURE	REMARKS

(4) Enter the screen number and title of a new Image, and designate Screen Type.

If you do not set a title, the title of the original BMP file will be specified.

The number of colors specified for [Screen Color] must be equal to the number of display colors supported by your LT series.

· If the number of colors is different, the display speed will be lowered.

· Any colors that are not supported with your LT series cannot be displayed.

(5) Click on the [Convert] button to perform data conversion.

The image data conversion starts. Then, the converted image will be displayed.

If the same screen number already exists, the system asks if you want to replace the existing screen with the one you are attempting to save. If so, select [Yes]; otherwise, select [No].

(6) If the displayed image is correct, click on the [Save] button.

An Image screen is created.

To cancel conversion, click on the [Discard] button.

When an image is converted by selecting the [Convert Image] command from the [Draw] menu on the Screen Editor, pressing the [Place] button allows the converted image screen to be placed.

(7) Click on the [OK] button to quit the conversion mode.

▼ Reference ◢ *2.4.18 Convert (Import) Image*

Select the [Load Screen] command from the [Draw] menu to place the converted image.

▼ Reference ◢ *2.2.10 Load Screens*

3.2.2	Compressing/Decompressing an Image Screen

If the size of the Image screen is large, you can compress it to reduce the data size. The data is compressed to one-fifth the size of the source data. The compressed Image screen data can then be displayed directly to the LT series. With the compressed Image screen, however, the LT series' display speed will be slower.

PROCEDURE	REMARKS

(1) Select the [Utility] menu - [Compress Image] command of the Project Manager.

(2) Select the screen to be compressed or decompressed from the list.

The compression and decompression procedures are separately described as follows:

To compress an Image screen (bit map data) of another project, select the project.

▼*Reference*▲   *1.2.2 ■ Selecting an Existing Project*

To select several screens, click on the screen numbers while pressing the Shift key.

To select a specified screen, click on the screen number while pressing the Ctrl key.

[Compression]

(3) Click on the [Compress] **button to execute data compression.**
The process is finished when the word "Compressed" appears.

[Decompression]

(3) Click on the [Decompress] **button to perform data decompression.**
The process is finished when the word "Normal" appears.

## 3.3 Window Display: Window (U) Screen and Base (B) Screen

3.3.1 Overview of Window Display

Call up the windows registered on the Window Screen (U) or Base Screen (B) and display them on the Base Screen (B).

Additional windows can be displayed on the LT screen when necessary.

Example: Make the settings for displaying a bar graph by turning ON the window display switch.

<LT Screen>

<LT Editor Screen Editor>

1)Registering a window on the U Screen

Window Registration can be performed on the Window Screen (U) .

Specify the Window Parts to call up the windows registered on the Window Screen (U) onto the Base Screen (B).

▼*Reference*▲ *2.1.20 Window Parts, 3.3.2 Window Registration on the U Screen*

◆ **Global Window Display**

Displays a single window on all Base Screens (B) as a global window. To call up the window, make the "Global Window" settings on the OFFLINE settings of the LT unit or on the [System Setup] of the Program Manager in LT Editor.

▼*Reference*▲ *Each LT series User Manual, Global Window Setup*

⚠ **Important**   ***Trend graphs (T Screen and parts), Keypad Input Display and Logging Display* will not function from the registered window.**

3.3.2 Window Registration on the U Screen

Call up a window that has been registered on the Window Screen (U) onto the Base Screen (B)

The window can be easily called up with the window part placed on the Base Screen pasted to the Base Screen.

■ Window Screen

```
┌─────────────────────────────────────────────────────────────┐
│ Usage Pattern                                                  │
│                                                                │
│  [Screen]   →   [New Screen]   →   OK  →   Create a window.    │
│                                                                │
│  [Part]     →   [Window Part]  →   Specify the window.  → Place.│
│             or                                                 │
│             ⌗                                                  │
└─────────────────────────────────────────────────────────────┘
```

This section describes the procedure for calling up a window display of a bar graph onto B2, following the example in the section Overview of Window Display in 3.3.1.

PROCEDURE	REMARKS
(1) Select [New] from the [Screen] menu, or click ⌑ to select [Window Screen]. The Window Screen (U) opens and a window area with a square frame is displayed. 	
(2) Draw the bar graph to be called up to the B2 screen. 	Click the border of the window area and eight ■ will appear on the screen. With the mouse, drag ■ to change the size of the window area.

P ROCEDURE	R EMARKS
(3) Adjust the window area so that it surrounds the bar graph. **(4) Save the Window Screen (U).** **Select the [Save As] command from the [Screen] menu, or click [icon].** **Enter the "Screen Number" and "Title." Click the [OK] button.** **(5) Open the Base Screen (such as B2) to be used for the window display.** **(6) Select [Window Parts] from the [Parts] menu, or click [icon].**	The x coordinates for the window display can only be set up in 8 dot intervals, i.e. the cursor will snap from one 8 dot unit to another. You can set up the Y coordinates anywhere you wish.

PROCEDURE	REMARKS

(7) Select the window to be displayed from the "Window Number" field.
Specify the Window Control Address as well.

✎ *Note:* **The address to be entered varies depending on your LT and PLC type. Note that the sample screen in this manual is just one example.**

(8)Click the [Place] button after setting all attributes.
The border of the window area is displayed on the drawing area.

(9) Click on the position where the window is to be placed.

[Window Control Address]

Changing the order of window layers
[0]: Touching the window will change the order of the layer.
[1]: Touching the window will NOT change the order of the layer.

Show
[0]: Hide the window
[1]: Show the window

A maximum of one global window and two local windows can be displayed simultaneously on a single Base screen.

If the specified position overlaps the objects on the Base Screen, the objects are hidden while the window is displayed.

Memo

4 SCREEN AND PROJECT MANAGEMENT

As you use the LT Editor, file management work such as copying and deleting created screens and projects will increase, thereby improving your work efficiency. This chapter covers "Information Management of your data."

4.1   Screen Editing

This section describes the commands used to edit a screen, such as listing screens, and copying/deleting a specified screen.

### 4.1.1   Listing/Copying/Deleting Screens

You can list the number, size and title of all existing screens for each screen type. You can also print out this screen list.

▼**Reference**▲   *9.1 Print Settings*

| Usage Pattern |
|---|
| **[Screen]** → **[Open Screen]**   → Select a Screen Type. →   Screen list appears. Copy or delete a desired screen. |
| or |
| Click on [icon]. |

■ Listing Screens

This feature lists screens for the current project.

| PROCEDURE	REMARKS
(1) Via the Screen Editor, select the [Screen] menu - [Open Screen] command, or click on the [icon] icon.	
(2) Select the type of screens to be listed. The screens will be automatically listed.	By checking the [Preview] check box, the selected screen image can be viewed in the dialog box. By changing the [Open Screen] dialog box's size, the screen list display area can be enlarged so that more screens can be displayed. ▼**Reference**▲ To print the screen list, *refer to 9.1.1* ■ *Printing - [Project Information] Tab*.

■ **Copying Screens**

This feature copies a screen from the current project file.

PROCEDURE	REMARKS
(1) Via the Screen Editor, select the [Screen] menu - [Open Screen] command, or click on the [icon] icon. **(2) Select a screen to be copied from the list, and click on the [Copy] button.**	
(3) Specify the Start Screen Number of the copy destination and copy count. Then, click on the [OK] button. The screen will be copied for the designated number, consecutively from the Start Screen No.	To select several screens simultaneously, drag the mouse down the list, or click on the target screens while pressing your PC's [Shift] key or [Ctrl] key. When selecting multiple screens simultaneously, copy will be performed only one time. *Important* ***Once the [Copy] command is performed, it cannot be undone.***

■ **Deleting Screens**

    This feature deletes a screen from the current project file.

| PROCEDURE	REMARKS
(1) Via the Screen Editor, select the [Screen] menu - [Open Screen] command, or click on the 📂 icon. **(2) Select a screen to be deleted from the list, and click on the** `Delete.` **button.** **(3) Click on the** `OK` **button to delete the screen.** 	To select several screens simultaneously, drag the mouse down the list, or click on the target screens while pressing your PC's `Shift` key or `Ctrl` key . *Important* ***Once the [Delete] command is performed, it cannot be undone.***

■ **Changing Screen Numbers and Titles**

This feature allows you to change screen numbers and titles in the current project file.

PROCEDURE	REMARKS

[Changing only One Screen]
(1) Via the Screen Editor, select the [Screen] menu -
  [Open Screen] command, or click on the [icon] icon.
 	
(2) Select a screen to be changed from the list, and click
  on the [Change] button.
 	
(3) Change the screen number and title, and then click
  on the [OK] button to delete the screen.
	⚠ *Important*
	If any existing screen number is specified, it will be overwritten.
	
	The currently open screen cannot be changed.

PROCEDURE	REMARKS
[Changing Multiple Screens at a Time] **(1) Via the Screen Editor, select the [Screen] menu -** **[Open Screen] command, or click on the 📺 icon.**	
(2) Select multiple screens to be changed from the list, **and click on the [Change] button.** 	To select multiple screens at a time, drag the mouse through the desired screens on the list, or click on those screens while holding the [Shift] or [Ctrl] key down. The currently open screen cannot be changed.
(3) Specify the start screen number at the destination, **and then click on the [OK] button.** "13" is specified here. The specified number comes to the top, and the subsequent numbers are changed automatically with increments of off-set values. 	The difference between the start screen number at the destination and that at the source is taken as an offset value. Since the start screen number, 1 is to be changed to 13 here, the offset value is 12. This offset value is added to the subsequent screen number 2 and 5, which is then changed to 14 and 17.

4.1.2　Copying Screens from Other Projects

Screens created in any project file other than the currently open one, and other settings can be copied to the currently open screen.

Note: • **To copy a logic program from other project files, import a logic program file (*.wll) with the Logic Program Editor.**

▽*Reference*◁ *Logic Programming Operation Manual*
• **The contents of Alarm Editor and Text Editor tables can be shared between Projects by importing/exporting ALA (alarm data only) or CSV files.**
▽*Reference*◁ **4.5.2 ■ Importing/Exporting CSV files, 5.1.4 Alarm Import/ Export**

■ Specifying Items to Be Copied

After selecting a project file as the copying source, specify the items you want to copy, such as the screen area to be copied and other settings, and a copying method.

Specify the screen area to be copied from the project file at the copying source.

Specify the settings other than the screen to be copied from the project file at the copying source.

Specify the start screen number in the project file at the copying destination. The specified data will be copied to this and subsequent screens.

◆ **Source**

The project file selected as the copying source is displayed. Specify the screen area to be copied and a screen type. If you are not copying a screen, but other settings only, select [Internal Settings].

◆ **Destination**

The current project file is displayed. When copying a screen from another project file, specify the start screen number in the project file at the copying destination to start copying the screen.

◆ **Internal Settings**

Select the items to be copied among the global settings for each project file, which are not dependent on any screen. Also specify whether the settings existing in the current project file are deleted by overwriting them or merged (added) with additional settings without deleting them. If "Overwrite" is specified, the settings at the copying destination will be deleted and all the settings at the copying source will be copied. If "Merge" is specified, the settings at the copying source will be copied while those at the copying destination are left as far as possible.

When such a merge is made using [Window Registry], [D-Script Functions], or [Filing Data], you will be prompted to confirm whether any identical existing number or function name is to be overwritten. When the combination is made using [Data Sampling] or [Global D-Script] all the settings will be merged.

■ **Copying Screens from Other Projects**

PROCEDURE	REMARKS
First, open the copy designation project. **(1) Select the Project Manager's [Utility] menu - [Screen Copy] command.** **(2) Select the project file to be copied (original project file) from the screen list, or enter the target project name, then click on the ⬚ Open ⬚ button.** 	To select a screen located in a different folder, you must change to that folder. ▽**Reference**△ *1.2.2* ■ *Selecting an Existing Project* The currently opened project cannot be selected. When you double-click on the project name selected in step (2), you can skip the ⬚ Open ⬚ command.

PROCEDURE	REMARKS
(3) Enter the screen type and screen number of the original screen. Those screens corresponding to the specified initial screen number through the final screen number will be copied. **(4) Enter the screen type and screen number of the destination screen.** The screens will be copied to the Destination project, starting from the specified initial screen number onwards.	If you select [All], all screens from the current project will be copied.

P ROCEDURE	R EMARKS

(5) Select the internal settings to be copied, and specify a copying method (overwrite or merge).

(6) After confirming your selection and designation, click on the ⬚ Copy ⬚ button.

If there is any screen of an identical number or function name, you will be prompted to conform whether or not to overwrite it. Selecting ⬚ Yes ⬚ will overwrite such a screen or function name, and selecting ⬚ No ⬚ will proceed to the next question. If ⬚ Yes All ⬚ is selected, all the screens or settings will be overwritten. If ⬚ No All ⬚ is selected, only the screens or settings that do not exist at the copying destination will be copied.

PROCEDURE	**R** E M A R K S

(7) Click on the [OK] **button to exit the screen copy mode.**

The number of screens copied will be displayed in the dialog box.

```
┌─Screen Copy──────────────[X]─┐
│                              │
│  Base Screens Copied: 0      │
│  Mark Screens Copied: 0      │
│  Image Screens Copied: 0     │
│  Window Screens Copied: 0    │
│  System Information Copied:1  │
│  Data Sampling Information Copied:0│
│  D-Script Functions Copied:0 │
│  Global D-Script Copied:0    │
│  Data Logging Settings Copied.0│
│  Data Text Table Settings Copied.0│
│  Filing Information Copied.0  │
│                              │
│         ┌─────────┐          │
│         │   OK    │          │
│         └─────────┘          │
└──────────────────────────────┘
```

(8) Click on the [Close] **button.**

```
┌─Screen Copy──────────────────────[X]─┐
│ ┌─Source────────────┐ ┌─Destination─┐│
│ │B Manufacturing System.│ Select │ │A Manufacturing System.││
│ │                    │              ││
│ │ ○ All              │  Start From 1││
│ │ ◉ Screens  From 1  │              ││
│ │            To   1  │              ││
│ │                    │  ┌────────┐  ││
│ │ Screen Type:       │  │  Copy  │  ││
│ │ ┌──────────────┐▼  │  ├────────┤  ││
│ │ │ All          │   │  │  Close │  ││
│ │ │ Base Screen  │   │  ├────────┤  ││
│ │ ○ Mark Screen  │   │  │  Help  │  ││
│ │   Image Screen │   │  └────────┘  ││
│ │   Window Screen│   │              ││
│ ├Intern──────────┴───┤              ││
│ │☑ System Information │ ☑ Filing Data││
│ │                     │ ◉Overwrite ○Merge│
│ │☑ Data Sampling      │              ││
│ │ ◉Overwrite ○Merge   │ ☑ Data Loging Settings│
│ │☑ D-Script Functions │ ☑ Text Table data│
│ │ ◉Overwrite ○Merge   │              ││
│ │☑ Global D-Script    │              ││
│ │ ◉Overwrite ○Merge   │              ││
│ └─────────────────────┘              │
└──────────────────────────────────────┘
```

Remarks column:

⚠ *Important*

After replacing the screens, you must re-enter all Parts device addresses.

To subsequently copy any other screen in the same project file, repeat the procedures starting with step (3).

4.2   Project Editing

4.2.1   Deleting Project Files

This feature allows you to delete a project file.

P ROCEDURE	R EMARKS
(1) Via the Project Manager, select the [Project] menu - [Delete] command.	
(2) Select the project to be deleted from the screen list, or enter the desired project's file name. Then, click on the ⌈ Delete(D) ⌉ **button.** 	To select a project located in a different folder, change the directory to that folder. ▼*Reference*▲ *1.2.2* ■ *Selecting an Existing Project* When you double-click on the project name selected in step (2), you can skip the ⌈ Delete(D) ⌉ command.
(3) Click on the ⌈ Yes ⌉ **button to delete the project.**	 *Important* ***Once the [Delete] command is performed, it cannot be undone.***

4.2.2	Backing up Project Files

When a Project file is saved, a backup file (*.bak) of the most recently saved Project file data is created. The backup file is created in the same folder in which the selected Project Manager is stored.

To open and edit Backup files as Project files, change the filename extension to "lte".

PROCEDURE	R EMARKS
(1) In the Project Manager (such as A PLANT SYSTEM. lte), select the [Project] menu's [Backup Settings] command.	
(2) Put a check mark in the "Backup Project File" checkbox and click on the [OK] **button.**	The option is enabled in the initial settings.
(3) Save a Project file. The backup file [A PLANT SYSTEM. bak] is created in the same folder in which the selected Project Manager (Example: A PLANT SYSTEM.lte) is stored.	To open and edit Backup files via the Project Manger, change the filename extension from "bak" to "lte".

4.2.3   **Rebuilding A Project (Rebuild)**

The "Rebuild" tool is used to both check the contents of the LTE files, CPW files and MRK files created with LT Editor, as well as to rebuild these files if they are damaged.

In the following cases, use the "Rebuild" command to restore file data.

1. Your personal computer is either reset or shut down while you are saving data.
2. The system crashed while you were saving data.
3. Your floppy disk or hard disk is damaged.
4. Your personal computer's disk drive is defective.
5. A system error (an error not specified in the error message list, such as a partition or checksum error) occurs while a screen is being opened or transferred.
6. The desired project file does not display as a LTE file during project selection, or an existing screen's number is not displayed when you try to open that screen.
7. You cannot select a project file when you try to perform the [Select Project] command. (i.e. the LT Editor program cannot recognize the project file as a LTE file)
8. When you try to open a file, an error message appears, indicating that the file is damaged.

```
┌─────────────────────────────────┐
│ File Open Error            ☒    │
├─────────────────────────────────┤
│                                 │
│   ⚠    System file is corrupt   │
│                                 │
│        ┌─────────────┐          │
│        │     OK      │          │
│        └─────────────┘          │
└─────────────────────────────────┘
```

9. Parts placed on the LT Editor program screen cannot be displayed on the LT unit, or, a different screen than desired is displayed on the LT unit. (i.e. the relationship between the screen data and Parts data is not correct)

If this error message is displayed, LT Editor program cannot read the target file until this file is rebuilt.
If a file's data cannot be completely restored with the "Rebuild" tool, the system treats this data as abnormal data and deletes it. In this case, you must edit this LTE file using LT Editor program after the "Rebuild" command is performed.

Note: **File Rebuilding requires approximately three times the hard disk space occupied by the Project file.**

■ **Rebuilding**

General description of the "Rebuild" screen is as follows:

Menu Bar

Tool Bar

Displays the selected file's name

Displays the status of the rebuild operation

Displays the progress of the rebuild operation

PROCEDURE	REMARKS
(1) To rebuild a file, click on the Windows main menu's [Start] button. Point to the [Program] - [Pro-face] - [LT Editor] menu, and select the [Rebuild] command.	

(2) Select the [File] menu - [Open] command, or click on the [icon] icon.

(3) Select the file to be rebuilt, or enter the file name. Then, click on the [Open] button.

P ROCEDURE	R EMARKS
(4) After confirming that the file name is correct, select the [Actions] menu - [Start] command, or click on the ▤ icon. The selected file will then be rebuilt. 	 To cancel file rebuilding, click on the ✋ icon.

(5) Select the [File] menu - [Exit] command, or click on the ▤ icon and finish the rebuild operation.

*Note:* **When Parts or Tags set up on the LT Editor screens are not displayed on the LT screen, or displayed in shapes different from the designated shapes (the screen data and part data are not related properly), rebuilt the data, and then transfer the data again. Click on ▥, and select [Transfer] - [Prepare] to display the Transfer Settings dialog box. Then, select "Send All Screens" option from the Transfer Method field.**

> ### 4.2.4   Converting Addresses and Device Codes

This feature allows you to change a Part's addresses. This address conversion can be performed on either word or bit addresses. This command is useful for changing both addresses or an address' device code.

Note: **When assigning a variable (Logic symbol) to the address, do not perform the Address Block conversion; otherwise, the operation will fail.**

P R O C E D U R E	R E M A R K S
(1) Via the Project Manager, select the [Utility] menu - [Convert Addresses] command.	
(2) Select the type of the address conversion to perform: Word Address or Bit Address.	In word address conversion mode, Part addresses specified by a bit address can also be changed, within a specified range.

When using any of the following External Devices, specify the Device/PLC number, as well: FACTORY ACE, 1:n communication (Yokogawa Electric Corp.) SDC Series (Yamatake Electric Corp.) THERMAC NEO series (OMRON)

 |
| **(3) Enter the address conversion range and the updated initial address.** Before this step is performed, be sure that the first and last device codes used are the same. You cannot specify an address conversion range for a different device. | When converting addresses, be sure that the address settings meet the following condition: **"Final address before conversion" - "Initial address before conversion" ≤ "Final address after conversion" - "Initial address after conversion"**

If the left side is larger than the right side in the above formula, the Parts corresponding to the surplus addresses will be assigned to the final address of the same device. |

P ROCEDURE	R E M A R K S

(4) Select the type of screen to be replaced.

(5) Enter the screen number to be changed. (Enter the line numbers used in the Alarm Editor)

All the addresses between the initial screen number and the final screen number (or the addresses between the initial line number and the final line number), will now be changed.

Important

Do not convert addresses on 2,000 screens or more at a time. Otherwise, the memory capacity might run short after this conversion. If this memory shortage occurs, restart the LT Editor.

(6) After confirming that all the settings are correct, click on the Convert **button.**

PROCEDURE	REMARKS
(7)Click on the [Start] **button.** The progress of the address conversion will be displayed. **(8)To stop the address conversion prior to normal completion, click on the** [Close] **button.**	

4.2.5   **Convert Load Screens**

This feature allows you to convert the currently loaded screens to different ones via the [Load Screen] command, all at once.

■ Load Screen and Search Screen Settings

Here, specify the screens to be converted. Enter the numbers of the Search Screens on which Load Screens have been called up and called up Load Screens.

Specify the range of Load Screens before conversion.

Specify the Top Screen number of the Load screens after conversion.

Specify the range of the Search Screens on which Load Screens have been called up.

Specify the Load Screen Type.

P ROCEDURE	R EMARKS

Example; Load Screens B100 to B105 currently loaded on Base screens B1 to B30 are converted to B200 to B205.

(1) Via the Project Manager, select the [Utility] menu - [Convert Load Screens] command.

(2) Specify the type and numbers of the Load Screens to be converted and the Top Screen number of the Load Screens after conversion.

Base screen

Start No. (100)
End No. (105)

Top Screen No. (200)

(3) Specify the range of the Search Screens and their type.
The Load Screen numbers specified in step (2) will be converted and called up on Search Screens specified by the Start and End numbers, here.

Start No. (1)
End No. (30)

(4) After confirming all the settings are correct, click on the Convert **button.**

(5) Click on the Start **button to start conversion.**
The conversion status will continuously be displayed.

(6) Click on the Close **button to close the dialog.**

4.2.6   **Symbol Editor**

The Symbol Editor enables you to assign an address to a symbol and then register that symbol and to assign a device comment to an address and then register it.

The "Symbol" is the registered name used to indicate the address of any Part. Thus, when you change the address corresponding to a symbol, you will automatically change a Part's address(es) without having to re-setting the Part. The "device comment" indicates a comment assigned (attached) to each address. When setting a Part's address(es), simply clicking on [📥] ([Apply Device Comment]) reflects the registered device comment to the Part's comment field.

▽*Reference*◁ *2.1 Parts ■ Part Attributes - Entering a Comment*

In all the address entry fields, such as of Parts, addresses registered via the Symbol Editor will be displayed in a pull-down list together with the symbols or device comments. Addresses can also be specified here by selecting them from this list.

▽*Reference*◁ *2.1 Parts ■ Part Attributes - Entering Addresses*

The symbol and device comment data can be shared between multiple Projects by import and export.

Note: **The registered symbol and device comment information can be printed as a symbol list.**

▽*Reference*◁ *9.1.1 Printing*

Usage Pattern				
[Screen/ Setup] →	**[Symbol Editor]** →	Select "Word symbol" or "Bit symbol". →	Enter a symbol name. →	Save the symbol data.

Select a desired symbol or comment.

Pop-up Keypad

Enter the address(es) corresponding to the symbol's or description's name

Enter a symbol name of up to twenty characters

■ Symbol Editor Types

There are five types of symbols: the Word symbol corresponding to a word address, the Bit symbol corresponding to a bit address, the Logic Integer symbol, the Logic Discrete symbol and the Logic Real symbol which are used in a logic program.

Word Symbol   Logic Integer Symbol   Logic Real Symbol

Bit Symbol   Logic Discrete Symbol

◆ Logic symbol

Logic symbol means variables used in a logic program. A new logic symbol cannot be registered with the Symbol Editor. When a logic program is saved, global variables registered on the variable list will automatically be registered with the Symbol Editor.

Only global variables are registered as logic symbols.

Variables are registered as one of the following three logic symbols depending on the variable type: **Logic Integer symbol, Logic Discrete symbol, Logic Real symbol**.

As for an array variable, each element is registered as a symbol. An array of size 5 is registered as five logic symbols. [Element Number] representing elements in an array will be <Element Number> as a Logic symbol, and an array of size 5, ALLM, will be represented as below.

Array variable	Logic symbol
ALLM[0]	ALLM<0>
ALLM[1]	ALLM<1>
ALLM[2]	ALLM<2>
ALLM[3]	ALLM<3>

Note: **For details of variables, please refer to the "Logic Programming Operation Manual" or "online help".**

■ Device Comment Types

There are two types of bit device comments: the word device comment corresponding to a word address and the bit device comment corresponding to a bit address.

Word Device Comment

Bit Device Comment

■ **Edit Commands**

To edit symbols, you can use the following commands:

· [icon] ..... Used to delete a symbol's line of data and store it on the clip-
board. The Paste command allows you to then move that symbol
to another line.

· [icon] ..... Used to copy a selected line of data to the clipboard.

· [icon] ..... Used to insert the line of data temporarily stored on the clip-
board into the desired row, after the Cut/Copy command has
been performed.

· [icon] ..... Used to cancel the command previously performed and return to
the previous condition. However, an edited symbol character
cannot be restored.

■ **Using the Cut/Copy/Paste Commands**

Cut/Copy/Paste commands can be used to move data between different
Symbol Editor files. To do this, simply open another LBE file and select a
desired line. Then, use the [Cut] or [Copy] command, and then the Symbol
Editor's [Paste] command.

[Important icon]

· *Do not register the same symbol name for both a word sym-*
bol and a bit symbol.

· *If alphanumeric numerals are used at the end of a symbol*
name, executing the [Copy] and [Paste] command will auto-
matically change the symbol's name.

· *When Chinese characters and numbers are used in a symbol*
name:

All the Arabic numbers to the right of the Chinese
character(s) will be deleted. Sequence numbers starting from
"2" will be assigned after the Chinese characters.

· *When Roman characters and Arabic numbers are used in a symbol*
name:

Example) ABC123

All the Arabic numerals to the right of Roman character(s) will
be deleted and replaced by a sequence number.

· *When only Arabic numbers are used in a symbol name:*

Only the first number is retained, and all other digits are
truncated and replaced with a sequence number.

■ **Registering Symbols and Device Comments**

PROCEDURE	REMARKS
(1)Via the Project Manager, select the [Screen/Setup] menu - [Symbol Editor] command. **(2)Select symbol or device comment type.** In this example, please select "Word Symbols". **(3) Enter symbol names and addresses.** **(4) After all the necessary items are registered, select the [File] menu - [Save] command, or click on the icon.**	To enter a symbol name, you can use up to twenty alphanumeric characters, or up to ten Chinese characters. The entered characters are not case-sensitive. You can perform the [Delete] or [Copy] and [Paste] commands after selecting multiple messages. ⚠️ *Important* ***The symbols [],\, ?, and the*** Tab ***key cannot be used in the Symbol Editor.***

■ **Importing Symbols and Device Comments**

The previously saved Symbol Editor data can be imported to and shared with the currently open Symbol Editor. Files with the extension of "*.LBE" or "*.CSV" can be imported.

CSV files that have been created via a text editor, Microsoft Excel, or other applications can be used as symbol or device comment data via the Symbol Editor after imported.

Note: **Logic symbols cannot be imported with the Symbol Editor.**

Symbol data and device comment's CSV file formats are as follows:

<Symbol Data CSV Format>

> **"GP_SYMBOL"**
> "Symbol Name", "Word Address"
>   <Give one line feed between a word address and a bit address>
> "Symbol Name", "Bit Address"

Example

"GP_SYMBOL"
"Line A (1 to 5): Word","D00100"
"Line A (6 to 10): Word","D00101"

"Line A (1 to 5): Bit","X00100"
"Line A (6 to 10): Bit","X00101"

One line feed

<Device Comment Data CSV Format>

> **"GP_COMMENT"**
> "Word Address", "Device Comment Name"
>   <Give one line feed between a word address and a bit address>
> "Bit Address", "Device Comment Name"

Example

"GP_COMMENT"
"D00100","Machine A stops"
"D00101","Machine A is now operating"

"X00100"," Pump B"
"X00101"," Pump B"

One line feed

! *Important*

· *"GP_SYMBOL" and "GP_COMMENT" are identifiers indicating they are Symbol and Device Comment Data, respectively.*

· *Give a line feed only between a word symbol and a bit symbol. If an unnecessary line feed is given in any other place, data cannot be imported.*

P ROCEDURE	R EMARKS

Import symbol data.

(1) Select the [File] menu - [Import Symbol] command, or click on the 🖳 icon.

(2) Select a file (*.LBE or *.CSV) to be imported or enter the file name, and click on the ⟦ Open ⟧ button.

To import a device comment, select the [Import Device Comment] command.

⚠️
Important

To import a device comment, select the [Import Device Comment] command.

If the same symbol name already exists, the system asks if you wish to replace the symbol name.
[Import as]
Enter the symbol name to be replaced.
If no symbol name is entered, the original symbol name plus sequence numbers will be imported.
[Replace]
The same symbol name will be overwritten.

[Do not import]
The same symbol name will not be imported.

If the same symbol name exists as a Logic symbol name, [Import as] command imports the symbol name with a number added. The symbol name cannot be overwritten.

**(3) Select an import method and execute it.**
To import the specified symbol according to the current settings, click on the ⟦ OK ⟧ button. To import the current Project file's all the symbols according to the current settings, click on the ⟦ Do For All ⟧ button. To cancel the import, click on the ⟦ Stop ⟧ button.

✎
Note: • **Amount of the Symbol data created or imported via the Symbol Editor is not limited. However, the number of device comment characters is up to 20.**

  • **Items with an inappropriate device name are not imported.**

■ Exporting Symbols and Device Comments

Data registered via the Symbol Editor is exported and saved as an LBE or CSV file. By importing this data, the Symbol Editor data can be shared among Projects.

Note: **Logic symbols cannot be imported with the Symbol Editor.**

PROCEDURE	REMARKS
Export symbol data. **(1)Via the Symbol Editor, select the [File] menu - [Export Symbol] command, or click on the [🖳] icon.** **(2)Specify the name and type (*.LBE or *.CSV) of the file to save the exported data with, and click on the [Save] button.** If the same file name already exists, the system asks if the existing file must be overwritten. If it must be overwritten, select [Yes]. If you do not wish to over write it, select [No]. **Export as** Save in: 🗄 Database 🖹 Line1 word.LBE File name: Line3 word Save Save as type: LBE Files (*.LBE) Cancel ⬇ **Export symbol** (?) File already exists. Okay to replace? [Yes] [No]	To export a device comment, select the [Export Device Comment] command.

■ Calling up Device Comments

All the comments that have already been registered with Parts can be called up on the Symbol Editor as device comments. For addresses corresponding to each Part's comment, refer to the Input Description Address Table.

▼*Reference*◣ *2.3.8 Duplication*

PROCEDURE	REMARKS
(1)Select the [File] menu - [Get Device Comment From Project]. **(2) Select a device comment calling up method and click on the** `OK` **button.** [Overwrite] ... The device comment is called up after the already assigned address is deleted. [Merge] ... The device comment is called up in addition to the already assigned address. *Get Comment File From Project* ⊠ ┌Save Options┐ ◉ O̲verwrite ○ M̲erge ☐ Include A̲larm Files `OK` `Cancel`	⚠ *Important* *Multiple addresses may be given to a Part depending on its type. In this case, device comments will be called up for all the as-signed addresses.* To call up an alarm message from the Alarm Editor, mark the [Include Alarm Files] check box.

4.2.7 **Changing a Project's LT Type**

You can change the LT type of your current project.

Note: **After changing the LT type, you can save the current project using the [Project] menu - [Save As] command.**

▼ Reference ▲ *1.2.2 ■ Saving a Project Under a Different Name*

PROCEDURE	**R**EMARKS
(1) Via the Project Manager, select the [Project] menu - [Change Display Type] command. 	
(2) To change the LT type, click on the desired LT type. **(3) Click on the** `OK` **button.** 	 *Important* ***The drawing area, commands and memory used by this change will vary depending on the selected LT type. Be sure to check these items before changing the LT type to be sure that your change(s) will be compatible with your existing project's data.***

Important ***When a vertical type LT unit is replaced with a horizontal type or vice- versa, the displayed screen is rotated 90º . Therefore, you must also edit the screen using the [Rotate] command. After editing, be sure to check that the displayed data is as desired.***

Example)

Horizontal type   **Vertical type**

4.2.8	Changing Your Project's Device/PLC Type and Addresses

The PLC type selected in the current project and the available addresses can be changed. This function is enabled only when using LT Type C.

Note: **To change the Device/PLC type, save the Device/PLC type you have changed via the [Project] menu-[Save As] command.**

▽**Reference**△ *1.1.2* ■ *Saving a Project File under a Different File Name*

■ Changing the Device/PLC type

The PLC type can be changed in the following dialog box.

Add a check mark to display a screen that allows you to configure the conversion pattern of available devices.

Select the desired PLC type from the drop-down list.

■ Setting the Device Conversion Pattern

The conversion operation of available devices is executed when the PLC type is changed.

The "Conversion Pattern" should be registered in order to convert the available device.

Note: **For efficient setup operations, arrange the following items beforehand.**
  • **Tables of available devices/PLCs both before and after the device/PLC types have been changed.**

▽**Reference**△ *Device/PLC Connection Manual, Device Memory Map of the PLC, etc.*
  • **Printed result of global cross reference**

Click this button to execute the conversion according to the data shown in the Address Table.

Address Table Displays detailed information on the conversion patterns (address type, range of available addresses before the PLC type is changed, and start address of the available address after the change).

Click this button to cancel all conversion information in the Address Table.

Click this button to register an additional conversion pattern.

Click this button to modify the settings of the conversion pattern.

Click this button to load the conversion patterns from the CSV file data and display the data in the Address Table.

Click this button to save the conversion patterns in a CSV file.

Click this button to delete a conversion pattern.

PROCEDURE	REMARKS
(1) Via the Project Manager, click on the 🏭 **icon, or select the [Project] menu - [Change Device/PLC Type] command.**	Do not open screens other than the Project Manager. Doing so will disable the selection of the Device/PLC Type.
(2) To change the Device/PLC type, click on the desired external device.	

[When no Device conversion patterns are set] **(3) Click on the [OK] button.**	The conversion operation applies to all addresses in the selected Project (except for addresses that have been registered as symbols).

(4) Click on the [OK] button to exit the setting dialog box.	Once you change a project's Device/PLC type, you must re-enter that project's device addresses for Tags, D-script and alarms. Save each screen separately again when the Function Switch set up with the "Change Screen" function is used on the screen.

PROCEDURE	REMARKS
[When Device conversion patterns are set] **(3)Put a check mark in the "Convert Address" checkbox and click on the** ⬚ OK ⬚ **button.** *(Change Device/PLC Type dialog image)* **(4)Click on the** ⬚ Add Pattern ⬚ **button to set up the conversion pattern for the Device.** *(PLC Type Change dialog image)* ⬇ **Select the "Address Type" option and designate the available "Start Address" and "End Address" of the PLC before the conversion, as well as the available "Start Address" of the PLC after the conversion, and click on the** ⬚ OK ⬚ **button.** *(Edit Address Conversion Pattern dialog image)* ⬇	The conversion operation applies to all addresses in the selected Project (except for the addresses that have registered as symbols). Refer to the list of available devices of your PLC.

PROCEDURE	REMARKS

The new conversion pattern is added to the Address Table.

Added conversion pattern

<Editing a conversion pattern>
Select the conversion pattern you want to edit from the Address Table and click on the [Edit Pattern] **button.**

Designate the conversion pattern with the procedure described in Step (4) of [When Device conversion patterns are set].

PROCEDURE	**R** E M A R K S

The edited information is displayed in the Address Table of the conversion pattern.

<Deleting a conversion pattern>
Select the conversion pattern you want to delete from the Address Table and click on the [Delet Pattern] **button.**

<Saving a conversion pattern as a CSV file>
Select the conversion pattern you want to save from the Address Table, and click on the [Save Pattens] **button.**

P ROCEDURE	R E M A R K S

Designate the file name.
In the "File name" field, enter the name of the CSV file to which the data will be saved.

⇩

Click on the | Save | **button to confirm the destination file to which the conversion pattern will be saved.**

<Loading a conversion pattern from a CSV file>
Click on the | Load Patterns | **button.**

When the combination of the PLCs indicated in "Convert From" and "Convert To" specified in [PLC Type Change] differs from the data on the CSV file, the conversion pattern stored in the CSV file cannot be loaded. Selecting the CSV file and clicking on the | Open | button will not display any data in the Address Table.

⇩

Select the CSV file to be loaded, and click on the | Open | **button to confirm the selection.**
The content of the CSV file is displayed in the list of conversion patterns.

P ROCEDURE	R EMARKS

(5)After setting up the conversion pattern, click the
[Convert] **button to perform address conversion.**

Conversion Example (time)
[Conditions] (Contents of project file)
No. of screens: 1
No. of Tags/Parts placed: 50
No. of specified conversion patterns: 10
[Conversion time]
About 10 seconds

The conversion time increases/decreases in proportion with the number of screens.
It may also vary according to changes in the settings of other items.

[If no conversion error occurs]

(6)Click on the [OK] **button to exit the setting dialog box.**

[If a conversion error occurs]

(6)Detailed information on the conversion error is displayed.

Device address

**B screen:
Screen No. 0**

<Completing "Convert Address">

Click on the [OK] **button.**

PROCEDURE	REMARKS

Click the [OK] button to exit the dialog box.

```
PLC types are different                    [X]
  /!\   Save- As Plc Type different from previous
        type. Address conversion may have produced
        invalid addresses
              [   OK   ]
```

<Maintaining a history of conversion errors as text data>
Select the conversion error, and click on the [Export Error Address List] button.

```
Change PLC Type
 Error Cannnot Convert Device.. [B:11 [D0090000]        [   OK   ]
 The above converted errors were found.
 Are you sure to use this conversion?                   [ Cancel ]




                                                        [ Export
                                                          Error
                                                          Address
                                                          List... ]
 ||||||||||||||||||||||||||||||||||
```

⬇

Designate the file name.
In the "File name" field, enter the name of the text file to which the data will be saved.

⬇

Click on the [Save] button to confirm the destination file to which the conversion error will be saved.

⬇

Click the [OK] button to exit the dialog box.

```
PLC types are different                    [X]
  /!\   Save- As Plc Type different from previous
        type. Address conversion may have produced
        invalid addresses
              [   OK   ]
```

<Canceling the PLC and Address Change>
Click on the [Cancel] button.

⬇

P ROCEDURE	R EMARKS
The [PLC Type Change] dialog box appears on the screen and the settings are reset to the conversion pattern settings that existed before the conversion. ⇩ Click on the ⬚ Cancel ⬚ button to close all setting screens for changing the PLC.	

4.3 ▶ Project Compression/Decompression

Compressing a project file reduces the size of its data to accomodate a standard floppy disk's limited capacity. A compressed project file and its screens however, cannot be edited. To edit the screens, you must first de-compress the project file.

Usage Pattern

Start → **Programs** → **Pro-face** → **LT Editor** → **Pack Tool** →

[Action] → **[Compress Project File]/** → Designate a Project → Click on the
[Decompress Project File] file to be compressed or
decompressed.

or
Click on 🗐↓ or 🗐↑ .

| OK |

button.

A general description of the compression tool is as follows:

Displays the file name of the project to be compressed/ decompressed

Displays the status of the project file compression/decom- pression

Displays the overall progress of the project file compres- sion/decompression

| **4.3.1** | **Compressing a Project File** |

A Project file can be compressed to a smaller size. At this time, a large sized file can be divided into smaller files automatically according to the specified capacity. After a project file is divided into several files during compression, serial numbers are assigned to the first character of each file extension (or assigned to the first and second characters if the file number has two digits).

Example)   *.0lt, *.1lt...*.9lt, *.10t, *.11t

Enter the file name of the project file to be compressed, or select a desired file name from the list by clicking on the [Browse] button

Used to locate the project file to be compressed

Used to select the file size limit

The compressed project file is automatically divided into several files according to the specified file size

PROCEDURE	**R** EMARKS
(1) First, click the Windows [Start] button. Then, click on the [Programs]-[Pro-face] - [LT Editor] menu and click the [3. Pack Tool] menu item. You can also select [3.Pack Tool...] from the Utility pull-down menu.	

PROCEDURE	REMARKS
(2)Select the [Action] menu - [Compress Project File] command, or click on the ▣↓ icon.	

PROCEDURE	REMARKS
(3)Select the folder and project file to be compressed, or enter the file name. The file name of the desired project file will be displayed in the "Pack" screen.	To call up a menu of all the available folders, click on the Browse... button.

PROCEDURE	REMARKS
(4)To divide the project file during compression, click on the [Separate File] check box, and select the desired file size limit.	When [Separate File] is selected and the file size is set to "1.44 MB" as shown in the left, the data will be divided and stored on two or more floppy disks.

P ROCEDURE	R EMARKS
(5)Click on the [OK] **button.** If the same file name already exists, the system asks if the existing file must be overwritten. If you select [OK] , the existing file will be overwritten. If you select [Cancel] , the existing file will not be overwritten, and you will return to the previous dialog box.	The compressed project file will be stored in the same folder as the original project file.

Pack Project File

File Name `C:\Program Files\Pro-face\LT\database` Browse...

☑ Separate File   1.44 MB

OK   Cancel

Pack Tool

⚠ File 'C:\Program Files\Pro-face\LT\database\A Manufacturing System.0LT' already exists. Okay to overwrite this file?

OK   Cancel

(6) Select the [Action] menu - [Exit] command, or click on the [icon] **icon.**

4.3.2	Decompressing a Project File

A compressed project file (0LT file) cannot be edited. To edit the compressed project file, you must first decompress it.

Enter the file name of the project file to be decompressed, or select the desired file name from the list by clicking on the [Browse] button

Used to locate the project file to be decompressed

PROCEDURE	**REMARKS**

(1) Click on the Windows desktop's [Start] button. Then, point to the [Programs] - [Pro-face] - [LT Editor] menu and click on the [4. Pack Tool] menu.

(2) Select the [Action] menu-[Decompress Project File] command, or click on the ▤↑ icon.

P ROCEDURE	R E M A R K S
(3) Select a folder and Project file to be decompressed or enter the file name, and click on the [OK] **button.** If the same file name already exists, the system asks if the existing file must be overwritten. If you select [OK], the existing file will be overwritten. If you select [Cancel], the existing file will not be overwritten, and you will return to the previous dialog box.	To select a folder, click on the [Browse...] button. ⚠ *Important* ***To decompress a compressed project file that has been divided into several files, make sure that all divided files are available.*** ***However, when you specify the file name to be decompressed, the system displays the first file name (*.0LT) only.***

UnPack Packed File

File Name | Factory B.0lt | | Browse...

[OK] [Cancel]

⬇

Pack Tool

⚠ File 'Factory B.lte' already exists. Okay to overwrite this file?

[OK] [Cancel]

The decompressed project file will be stored in the same folder as the compressed file.

(4) Select the [Action] menu - [Exit] command, or click on the 🐞 icon.

4.4   Information Display

This section describes the types of screen and project information available.

4.4.1   Project Information

[Project Information] displays both the commands used to edit the current project, and the date and time of its last revision. To use this command, select the [Project] menu - [Project Information] command.

■ Project Information

◆ **Current Project**
Displays the file name of the currently selected project file.
◆ **Description**
Displays a comment about the current project.
◆ **Device/PLC Type**
Displays the Device/PLC selected in the currently opened project file.
◆ **Display Type**
Displays the LT type selected in the current project file.
◆ **Project Size**
Displays the data volume of the current project file.
If any Parts are placed in this file, the file volume will be increased.
◆ **Date & Time**
Displays the date and time when this file was saved last.
◆ **Size of Screen To Be Sent To LT**
Displays the total data volume that will be occupied in the LT unit panel, relative to the current project file. This item indicates the case where upload information is sent to the LT panel, and the case where upload information is not sent to the LT unit, separately.
The ratio of the current total data volume to the LT unit's total memory capacity is displayed in %. Referring to the LT unit's total memory capacity, you can calculate the approximate number of screens that can be accepted by the LT panel.
When the data volume is indicated as "????", select the [Project]'s - [Transfer] menu, and then select the [Prepare] command.

▼ Reference ◤ *7.2.3 Transfer Preparation*

Use this value only as a guideline. Depending on the size of the memory stored in the LT, a screen of allowable size may not be entirely transferred.

◆**Extended Screen Count**

Displays the number of screens that will be created in the LT unit, relative to the current project file. Since this value includes the LT unit's internal screens, it is larger than the number of screens that have been created with LT Editor for Windows 95. To display this information, set up the current project file in the "Transfer Preparation" mode. If the project file is not in the "Transfer Preparation" mode, the number of screens is indicated as "????"

■ **Screen Information**

This screen shows the number of screen types, alarm messages and channels contained in the current project.

The number of channels and the screen number that are used in the project are displayed

■ **SRAM Information**

The situation with the use of the backup SRAM in the current project is displayed on a function basis.

4.4.2 Screen Information

The [Screen Information] screen displays the settings for the currently open screen, as well as the date and time of its last revision. To use this command, select the [Project] menu's - [Screen Information] command.

■Screen

◆ **Project Name**
Displays the file name of the currently selected project file.

◆**External Device Type**
Displays the external device selected in the current project file.

◆**Current Screen**
Displays the screen type and screen number of the current screen.

◆**Description**
Displays the title of the current screen.

◆**Size**
Displays the data volume of the current screen. If any Parts are placed on this screen, the screen data volume will be increased.

4.4.3 Version Information

[Version Information] displays the LT Editor Project Manager and Editor's version information. To see this data, select the [Help] menu - [About] command.

<**Project Manager Version Information**>

4.5 Table Editor Character Strings

The Character Strings Settings and the Multi-language Display Feature are described in this section.

⚠ Important

- *Image fonts cannot be used in the table editor character strings.*

4.5.1 Overview: Multi-language Display Feature

Using Index Text for the text objects and part's labels allow you to easily switch the language and information displayed on the screen during operation (the diagram below describes the steps for switching the display language.) Switching between tables is performed with the Control Address (two or more tables cannot be specified at one time). Thus, you can easily switch the display language or displayed text items on the screen. Character strings are switched by selecting tables (a group of character strings). Registration of the Index Text and setting the Control Address can be performed with the Text Table Editor.

Example: Switching the display language for the label of a part

Table 1		Table 2	
1	開始	1	START
2	停止	2	STOP
3	次へ	3	NEXT

Use the Text Table Editor to create the Index Text in two languages.

Table 1		Table 2	
1	開始	1	START
2	停止	2	STOP
3	次へ	3	NEXT

When Table 1 is selected

When Table 2 is selected

GP

開始 停止

Table is switched with the Control Address

then a screen's text string is changed.

GP

START STOP

Index No. 1   Index No. 2

Index No. 1   Index No. 2

⚠ *Important*

- *Switching tables uses the same process as switching screens. Therefore, some screen displays drawn with tags may not be able to be refreshed.*

- *The following character strings cannot be changed even when the tables are switched.*

  – *[X-tag] character strings*

  – *Filing Feature*

  – *Logging Feature*

◆   **Precautions for switching tables with the Alarm function**

- When a table is switched while an alarm message (Flow display) is displayed, the switched table is not used until the next message is issued.

LT

日本語

A異常です

(Direction of the display flow)

Japanese to English   Switch the tables

ENGLISH

A PRESSURE ERROR

ENGLISH

異常ですTANK A PRESS

ENGLISH

Aタンク圧が異常

(Direction of the display flow)

- When the print setting is enabled for the Alarm Message Function (Flow display), the alarm message of the table (language) displayed at the moment when the alarm is triggered or reset will print.

- When a table is switched while real-time printing is set to print the alarm summary (a-tag) or log alarms (Q-tags), the switched table will be used starting from the next print job.

LT

ALARM A
ALARM B
ALARM C

Japanese to English

Switch the tables

LT

警告A
警告C
警告B

- When a table is switched while log alarms (Q-tags) are being written into the CF Card as a CSV file, the switched table is used immediately.

- The steps for switching tables are similar to those for switching screens. Therefore, the Sub Display, Cursor Display and Scroll Display that were displayed before the switching with the Log Alarm (Q-tag) will not be reproduced.

4.5.2   Table Editor Index Character Strings

The Table Editor is used to create a table's index character strings.

Table Editor Index Character Strings can be exported in CSV format. You can also import a CSV file to use as an index character string.

Operation procedures

Start → **[Screen/Setup]** → **[Text Table...]** → [Put a check mark in the "Text Table(ON/OFF)" checkbox.] →

Assign Control Address. → Select font from [Font Setting] menu. →

Enter index character string. → Save table data.

■ Table Editor Features

Put a check mark here to enter the mode in which Text Table Editor is enabled.

Click here to specify the Control Address

Select a table to enter character strings. Up to 16 tables can be registered

Index No.
Up to 3,000 character strings can be registered

After setting up the text, specify the line and click the [Go to] button to jump to the specified line.

Set the font (language) for the selected table

Double-click on this area to call up a message dialog box (Up to 1,200 characters)

■ **Using the Text Table Editor**

- When a check mark is placed in the "Text Table(ON/OFF)" checkbox (ON mode), the Table Editor is switched to input mode, enabling additional settings such as Table setting and Index Text registration.

- When the check mark is removed from the checkbox (OFF mode), the following warning message dialog box appears. Clicking the ☐ OK ☐ button deletes all Text Table data registered in the project. Click the ☐ Cancel ☐ button to retain the data.

■ **Entering ControlAddress Settings**

Specify the Control Address to switch the tables.

In the Control Address, store the Table No. you want to display.
The default text table is displayed when "0" is stored. To set up the default text table, select [Default Table Setup] from the [File] menu on the "Text Table Editor" dialog screen.

<Values stored in the Word Address>

Value in one Control Address	Table No.
0	Initial character string table
1	Table 1
2	Table 2
:	:
16	Table 16

Note: • **A table will not appear when you specify a table number for which nothing is set.**

■ Table Name

Up to 16 tables can be registered.

To change a table name, display the table whose name is to be changed onto the "Text Table Editor" screen. Next, click [Table Name Change] on the [File] menu.

Enter the desired table name and click the [OK] button to change the table name.

■ Font Settings

Specify one font (language) for each table (a table cannot contain more than one font [language]).

■ Entering Messages

On the Text Table Editor, double-click the column of the Index No. you want to set up. The screen below appears on the screen. Enter the Index Text for each Index Number.
Specify the message size [Characters] x [Lines] for each Index No.

Character Entry Area

Specify the number of characters in a line. (1 to 100 single-byte characters)

Specify the number of lines. (1 to 40 lines)

Note: • **The number of characters used in the index character string is determined by [Characters] x [Lines]. (Max. 1,200)**

[Characters] x [Lines] ≤ 1,200

• **Multiple display lines can be used for [Character string] and Parts [Label] only. For other features, do not specify an index number for which multiple display lines are set. If such an index number is specified, only the first line will be displayed.**

⚠ Important *The index characters for each index number [Characters] x [Lines] are available in all tables.*

■ Index Character String Registration

PROCEDURE	REMARKS
(1) In the Project Manager, select the [Screen/Setup] menu - [Text Table...] command.	
(2) Put a check mark in the "Text Table Editor" checkbox in the [Text Table(ON/OFF)] dialog box.	
(3) Click on the ▦ icon and enter the [Control Address].	The table name can be modified by selecting [File] menu - [Table Name Change].
(4) Select a font from the [Font Setting] menu . Select a table from ▼ on the right of the "Table 1" field and select a font (language) from ▼ on the right of the "Font Settings" field.	You can choose from the following five selections. • ASCII (Code Page 850) • CHINA (GB2312) • JAPAN(JIS) • KOREA (KS-C5601) • TAIWAN (Big5)
(5) Double-click the index character string entry area. 	
(6) Enter the desired [Characters] and [Lines] according to the index character string. 	The number of characters used in the index character string is determined by [Characters] x [Lines]. (Max. 1,200) [Characters] x [Lines] ≤ 1,200 Multiple display lines can be used for [Character string] and Parts [Label] only. For other features, do not specify an index number for which multiple display lines are set. If such an index number is specified, only the first line will be displayed.

Pᴿᴏᴄᴇᴅᴜʀᴇ	Rᴇᴍᴀʀᴋs
(7) Enter the index character string. **(8) Click the** [OK] **button to confirm the characters.** **(9) Repeat the same steps to set the index character strings for the other index numbers.** **(10)Repeat the same steps to create other tables.** **(11)Select the [File] menu - [Save] command or click on the ⊟ icon to save the setting.**	Up to 16 tables can be registered.

■ Importing/Exporting CSV files

You can export the contents of a table created using the Table Editor as a CSV file, or you can import a CSV file created using another table editor software into the Table Editor.

> **⚠ Important**
>
> ***To edit data exported into a CSV file, or edit data that has been previously exported, use an operating system that supports the font specified in [Font setting] of Table Editor Character Strings.***

◆ Importing CSV files

Select the [File] menu - [Import] command.

Use the following dialog box to select the desired file.

> **⚠ Important**
>
> • ***When a CSV file is imported, the existing index character string is overwritten.***
>
> • ***When [Characters/Lines] is selected***
> ***If the imported [Characters] x [Lines] of the CSV file setting values are lower/less than the index character string values set in the [Table Editor], any excess/remaining characters in the [Table Editor] will be deleted during import.***
>
> • ***When [Characters/Lines] is not selected***
> ***If the imported CSV file's setting values are higher/greater than the index character string values set in the [Table Editor], any excess characters in the imported data will be deleted during import.***

◆ CSV file format for character string tables

CSV file format

Header (Required for importing the file data)

Table Data				
Table	Table 1			
1	15	1	4	Abnormal pressure in tank A
2	15	2	4	Abnormal pressure in tank B

Table Name

Index Character String

Index No.   **Number of characters**   **Number of lines**   **Font (Language)**
0: Japanese
1: Chinese
2: Taiwanese
3: Korean
4: ASCII

4.5.3	Entering Settings via the Screen Editor

■ Selecting the drawing table

From the menu bar in the Screen Editor, select the table to use for drawing. When a table is changed, the character strings used in the Screen Editor also change.

■ Selecting the index character string

◆ Entering the index character string

Click on the [Index] to switch the screen to the one used to enter the index character string.

Select the desired index character string from those shown in the [Table Editor]. To add a new index character string, click the Add Index button to start the [Table Editor].

▼ *Reference* ◢ *4.5.2 Table Editor Index Character Strings* ■ *Index Character String Registration*

Place a check mark here to sort the Index character strings displayed in the pull-down menu in the order character code. (Single-byte and double-byte characters are discriminated.)

✎ *Note:* **The size of any text object placed on the drawing area automatically changes according to the size specified in the Table Editor ([Characters] x [Lines]). Switching tables does not change the text size.**

◆ **Designating Part's label**

Select [Index] in the Part's [Label] area to change to the index character string entry screen.

Select the desired [Index] from those specified in the [Table Editor]. To add a new [Index], click the [Add Index] button to start the [Table Editor].

▼ **Reference** ◢ *4.5.2 Table Editor Index Character Strings* ■ *Index Character String Registration*

Place a check mark here to sort the Index character strings displayed in the pull-down menu in the order character code. (Single-byte and double-byte characters are discriminated.)

Note: **The size of any text placed on the drawing area automatically changes according to the size specified in the Table Editor ([Characters] x [Lines]). Switching tables does not change the text size.**

◆ **Designating messages for the Message Display**

In the Message Display Settings, select the "Index" option in the [Messages] area.

Select the desired Index character strings (Index No.) from those specified in the Table Editor. To add new Index character strings, click on the [Add Index] button to activate the Table Editor.

▼ **Reference** ◢ *4.5.2 Table Editor Index Character Strings* ■ *Index Character String Registration*

Place a check mark here to sort the Index character strings displayed in the pull-down menu in the order character code. (Single-byte and double-byte characters are discriminated.)

Note: **The frame size of the Part will be displayed according to the Index character string (Number of characters x Number of lines) of the specified Index No. The frame size of a Part remains the same even if the Table is switched.**

◆ **Selecting Alarm Editor Messages**

First, select [Text Method] in [Alarm] in the [Alarm Editor] and change the character string setting mode to [Index].

Place a check mark here to sort the character strings in the order of character code. (Single-byte and double-byte characters are discriminated.)

When the character string setting mode is changed, all previously registered alarm messages are deleted.

Then, click ▼ in [Message/Summary Text] to view the list of [Index character strings] specified in the [Table Editor]. Select the desired Index Text from the Index Texts registered on the Text Table Editor.

[Index character strings] can also be selected by choosing [Add Alarm(s)] in [Edit].

If you want to add a new [Index], click the [Add Index] button to start the [Table Editor].

▼**Reference**◢ *4.5.2 Table Editor Index Character Strings* ■ *Index Character String Registration*

• *When messages are registered with the Alarm Editor, Direct Text and Index Text cannot be mixed.*

• *Do not set up an Index Text with two or more lines. Only the first line will be displayed, even if two or more lines have been set up.*

Important

Memo

5 ▶ CREATING AND EDITING ALARMS

This feature allows you to register text data to be displayed as alarm mesages. This chapter describes how to create and edit these alarm messages.

5.1 .... **Alarm Creation and Editing**

5.1 ▶ Alarm Creation and Editing

With this feature you can register the messages to be displayed in the "Alarm Summary" (Part menu's "Alarm Display") and "Alarm Message" (right to left scrolling display). You can also set up a monitor bit for each message. According to the monitor bit's ON/OFF status, the specified messages are then displayed in the "Alarm Summary" or "Alarm Message" mode.

The "Alarm Summary" lists messages in the Alarm Display Part.

▼**Reference**▲ *2.1.12 Alarm Display*

With "Alarm Message" text, the horizontal and vertical size of the text is specified in the [Setup Area's (Initial Setup screen)] menu or in the LT unit's [Setup] mode. Character sizes can be set to either "x 1", "x 2", or "x 4".

When the horizontal and vertical sizes are set to "1 x 1", an alphanumeric character occupies 16 x 8 dots, and a Chinese character occupies 16 x 16 dots.

The "Alarm Display" and "Alarm Message" will display on the LT unit's panel screen as shown below:

Alarm Summary
("Alarm Display" Part)

Alarm Message Display

```
Valve2 Alarm
Valve5 Alarm
Valve6 Alarm
```

```
Alarm No.
```

◁▭ **Right to left scrolling display**

Usage Pattern

[Screen/ → **[Alarm Editor]** → Select the alarm type:
Setup] or [Alarm Message/Sum- →
mary]

Click on ⊙ .

Enter a → Set up [Alarm → Save the Alarm
message. Message/Summary]. Editor.

5.1.1 ▶ Alarm Editor

Via the Alarm Editor, messages and monitor bits are registered for each alarm type. An example of an Alarm Message screen used for entering a message is as follows.

Note: **The tab width for each item in the Alarm Editor (messages) can be adjusted by positioning the mouse pointer on the border between items and then dragging it. The changed size will be saved, and used on the subsequently opened screens.**

■ **Alarm Message/Summary Screen**

Here, you can register the messages to be displayed as either "Alarm Summary" ("Alarm Display" Part) or as "Alarm Message" (right to left scrolling display). The message can be registered up to 8999 lines.

◆ **Bit Address**

Specifies the monitor bit. To specify the bit address for the "Alarm Summary" mode, select a device that can be specified in Word units.

▽**Reference**△ *Device/PLC Connection Manual*

◆ **Alarm Type**

The Alarm Editor provides two types of alarms: [Alarm Summary] and [Alarm Message].
The [Alarm Summary] mode lists messages specified by the Alarm Part.
The [Alarm Message] mode displays a scrolling message at the bottom of the LT's screen.
Up to 128 messages can be entered into the Alarm Editor. Any message beyond this setting range will not operate on the LT unit's panel screen.

◆ **Message**

Enter your message here. Up to 160 alphanumeric characters can be entered for one message. Index Text can be used to switch messages.

▽**Reference**△ *4.5.3 Entering Settings via the Screen Editor* ◆*Selecting Alarm Editor Messages*

◆ **Pop-up Keypad**

A pop-up keypad is displayed, allowing you to enter the bit address using the mouse.

◆ **Message Color**

Designates message's color. Select the display color (Fg) and background color (Bg), and specify whether to blinking (Blk) is used or not.

◆ **Automatic Address Increment**

After entering and registering a message in a line and moving to the next line, an address that is one bit larger will be automatically entered for the new line.

> ⚠️ **Important**
>
> ***When a variable (Logic symbol) is used as an address, the automatic address increment function must be turned off. Otherwise, the correct addition will not be performed.***

◆ **Jump to the designated line.**

Specify a line and click [Jump] to jump to the line.

◆ **Print**

An Alarm Message (like a bulletin board) can be printed out when the alarm is triggered and when recovered. Specify if the Alarm Message is printed out at the triggering of the alarm and at the recovery from the alarm, respectively. When [Summary] is selected, this setting becomes ineffective.

Trigger Time: Prints out the time when the Alarm Message started.
Recovery Time: Prints out the time when the Alarm Message is finished.

Printing Example

Trigger	10/15	16:07	No.1 error
Recovery	10/15	16:30	No.1 error
Trigger	10/21	11:25	No.1 error
Trigger	10/21	11:28	No.3 error
Recovery	10/21	15:45	No.1 error

> ⚠️ **Important**
>
> - ***Up to 1,000 Alarm Message triggering and recovery events can be stored in the LT. When the LT is not connected to a printer, up to 1,000 events will be stored in the LT, which enters a printing stand-by mode. When the number of the events exceeds 1,000, the excessive events will not be stored.***
>
> - ***When a printer becomes offline mode due to the running out of printing paper during printing, DO NOT turn the LT's power OFF. Refill the paper and return the printer to online mode. Event information stored in the LT in the printer offline mode will be output to the printer when the printer mode returns to online.***
>
> - ***If the printer's power is turned OFF during printing, event information transferred from the LT to the printer while the printer's power is OFF will not be printed.***

> **5.1.2** **Creating an Alarm**

This section describes how to create and register alarm messages using Alarm Editor.

PROCEDURE	REMARKS
(1) Via the Project Manager, select the [Screen/Setup] menu - [Alarm Editor] command, or click on the icon to open the Alarm Editor.	Entering data in the Alarm Editor only does not activate the "Alarm Summary" mode. To activate the "Alarm Summary" mode, you must place the Message Display on the Base screen where the message is displayed.
(2) Specify the bit address (monitor bit).	⚠ *Important* **When designating an Alarm summary's bit address, be sure to select a device that can use word designated units.**
(3) Enter a message. Enter the message to be displayed on the LT unit panel during alarm output. Select a message color, if desired.	▼*Reference*▲ *Device/PLC Connection Manual, 3_*_3/ 4_*_3 Supported Devices* *Note:* **The address to be entered varies depending on your LT and PLC type. Note that the sample screen in this manual is just one example.** Up to 160 alphanumeric characters can be entered for one Basic Alarm message. After selecting several messages by dragging the mouse, you can use the [Copy] and [Paste] commands

PROCEDURE	REMARKS
(4) Select the alarm type: Alarm "Message" or Alarm "Summary".	Up to 512 alarm messages can be registered. However, set the monitor bits within 128 words.
(5) After entering all the necessary items, select the [Alarm] menu - [Save] command, or click on the 🖫 icon. The specified alarm data will be stored in the currently opened project file.	If a message has not been entered, the Alarm Editor data cannot be saved, even if the bit addresses have been specified.

5.1.3   Editing Alarm Data

This section describes how to use the Alarm Editor's editing commands.

■ Cut/Move

Here, you can delete the selected line of alarm data and store it on the clipboard.

PROCEDURE	REMARKS
(1) Select the line of alarm data to be moved.	If a message has not been entered, Alarm Editor data cannot be saved, even if bit addresses have been specified.
(2) Select the [Edit] menu - [Cut] command, or click on the 🖴 icon to import alarm data to the Clipboard. The selected alarm data will be deleted and stored.	To select several lines, drag the mouse between the target lines, or click on the target line while holding down the Shift or Ctrl key.
(3) Select the insertion line.	To delete the selected line(s), perform steps (1) and (2) only.

PROCEDURE	REMARKS
(4) Select the [Edit] menu - [Paste] command, or click on the ▣ icon to paste alarm data to the destination from the Clipboard. If the same number already exists, the system asks if each file must be overwritten. If you select ⌑Yes⌑ , the desired data will be overwritten. If you select ⌑No⌑ , the desired file will not be overwritten, and the system will ask the same question for the next alarm. If you select ⌑Yes to All⌑ , all existing alarms will be over-written. If you select ⌑No to All⌑ , you will return to the menu screen.	

Confirm Alarm Replace

Alarm No 5 already exists! Overwrite?

[Yes] [Yes to All] [No] [No to All]

⬇

The selected alarm data is moved to the specified line.

	Bit Address	Type	Message
1	X0010	Summary	Tank A stops
2	X0050	Summary	Tank B stops
3		Summary	
4	X0052	Summary	
5	X0051	Summary	Tank C stops
6	X0054	Summary	
7	X0055	Summary	

■ **Copy**

Copies the selected line of alarm data, and stores it on the clipboard.

PROCEDURE	REMARKS
(1)Select the alarm line to be copied.	Even if bit addresses have been specified, if message data has not been entered, the Alarm Editor data cannot be saved.

	Bit Address	Type	Message
1	X00010	Bulletin	Tank A temperature UP
2	X00050	Summary	Tank B temperature UP
3	X00051	Summary	Tank C temperature UP
4	X00052	Summary	
5	X00053	Summary	

(2)Select the [Edit] menu - [Copy] command, or click on the ▣ icon to import alarm data to the Clipboard.
The selected alarm data will be copied to the clipboard.

To select several lines, drag the mouse between the target lines, or click on the target line while holding down the Shift or Ctrl key.

	Bit Address	Type	Message
1	X00010	Summary	Tank A temperature UP
2	X00050	Summary	Tank B temperature UP
3	X00051	Bulletin	Tank C temperature UP
4	X00052	Summary	
5	X00051	Bulletin	

(3)Select the destination line.

	Bit Address	Type	Message
1	X00010	Summary	Tank A temperature UP
2	X00050	Summary	Tank B temperature UP
3	X00051	Bulletin	Tank C temperature UP
4	X00052	Summary	
5	X00051	Bulletin	
6	X00054	Summary	
7	X00055	Summary	
8	X00056	Summary	
9	X00057	Summary	

(4) Select the [Edit] menu - [Paste] command, or click on the ▣ icon to paste alarm data to the destination from the Clipboard.
If the same data already exists, the system asks if each file (item) must be overwritten. If you select [Yes], the desired file will be overwritten. If you select [No] , the desired file will not be overwritten, and the system will ask the same question for the next alarm. If you select [Yes to All] , all existing alarms will be overwritten. If you select [No to All] , you will return to the menu screen.

PROCEDURE	REMARKS

Confirm Alarm Replace

Alarm No 5 already exists! Overwrite?

Yes / Yes to All / No / No to All

The selected alarm data is copied to the specified line(s).

1	X0010	Bulletin	Tank A stops
2	X0050	Summary	Tank B stops
3	X0051	Summary	Tank C stops
4	X0052	Summary	
5	X0053	Summary	
6	X0054	Summary	
7	X0051	Summary	Tank C stops
8	X0056	Summary	
9	X0057	Summary	
10	X0058	Summary	

■ Undo

This feature allows you to cancel the previously performed command, and return to the previous condition.

PROCEDURE	REMARKS
When an alarm has been unintentionally deleted: **(1) Select the [Edit] menu - [Undo] command, or click on the ⬚ icon.**	Edited message characters cannot be restored with the [Undo] command.

	Bit Address	Type	Message
1	X00010	Bulletin	Tank A temperature UP
2	X00050	Summary	Tank B temperature UP
3	X00051	Summary	Tank C temperature UP
4	X00052	Summary	
5	X00053	Summary	

■ **Adding Alarm Data**

Here, you can add alarms for the specified number of bits or words from the line whose item is enclosed with dotted lines. Addresses are automatically assigned to each alarm from the start address in series, according to the designated address adding increment. In addition, when messages have been entered, they are copied for all the alarms to be added.

⚠ *Important*

When a variable (Logic symbol) is used as a start address, set the add offset to 0. Otherwise, the correct addition will not be performed.

Add Basic Alarm

Start Address	X00000
Number of Bits to Add	16
Add Offset	0

Alarm Type
◉ Alarm Summary
○ Alarm Message

OK
Cancel
Help

☐ Message

Message Color
Fg ■■■■■■■□ Blk ☐
Bg ■■■■■■■□ Blk ☐

Print
☐ Trigger Time Printout
☐ Print Recovery Times

PROCEDURE	**R**EMARKS
(1)Select the address line where the specified number of addresses will be added. (Shown here with a dotted line around its border) | Bit Address | Type | Message 1 X0010 | Bulletin | Tank A temperature UP 2 X0001 | Summary 3 X0002 | Summary 4 X0003 | Summary 5 X0004 | Summary **(2)Select the [Edit] menu - [Add Alarm] command, or click on the 📥 icon.** **(3)After entering the necessary settings, click on the** OK **button.** If the same number already exists, the system asks if each file must be overwritten. If you select Yes , the desired file will be overwritten. If you select No , the desired file will not be overwritten, and the system will ask about the next alarm. If you select Yes to All , all existing alarms will be overwritten. If you select No to All , you will return to the menu screen. **Add Basic Alarm** Start Address 01/C0000000 Number of Bits to Add 16 Add Offset 0 Alarm Type ◉ Alarm Summary ○ Alarm Message OK Cancel Help ☐ Message Message Color Fg ■■■■■■□ Blk ☐ Bg ■■■■■■□ Blk ☐	If a symbol is specified for the start address, the added addresses will be displayed as follows: Example: Assume that the start address is TEST (← Symbol), and that the number of added bits is 4. The addresses are consecutively added as shown below: TEST TEST + 1 TEST + 2 TEST + 3

PROCEDURE	**R** E M A R K S

Confirm Alarm Replace

Alarm No 5 already exists! Overwrite?

| Yes | Yes to All | No | No to All |

■ **Changing Alarm Attributes**

You can easily change any alarm's attributes.

Change Alarm

Alarm Type
⊙ Alarm Summary
○ Alarm Message

OK
Cancel
Help

Message Color
Fg ▪▪▪□▪▪□□ Blk □
Bg ▪▪▪□▪▪□□ Blk □

PROCEDURE	**R** E M A R K S
(1) Select the line of the alarm to be changed. In this example, we will change an attribute of an item in the alarm message/alarm summary area.	If several lines are selected, the attributes of the selected lines can all be simultaneously changed. To select several lines, drag the mouse between the desired lines, or click on the desired line while pressing the $\boxed{\text{Shift}}$ or $\boxed{\text{Ctrl}}$ key.

	Bit Address	Type	Message
1	X00010	Bulletin	Tank A temperature UP
2	X00050	Summary	Tank B temperature UP
3	X00051	Summary	Tank C temperature UP
4	X00052	Summary	
5	X00053	Summary	

(2) Select the [Edit] menu - [Change Attributes] command, or click on the ▦ icon.

(3) After entering the necessary items, click on the
      ⌈ OK ⌋ **button.**

Change Alarm

Alarm Type
⊙ Alarm Summary
○ Alarm Message

OK
Cancel
Help

Message Color
Fg ▪▪▪□▪▪□□ Blk □
Bg ▪▪▪□▪▪□□ Blk □

■ Reflecting Device Comments

This feature is used to reflect all the comment information corresponding to a selected device in the Message field.

Procedure	Remarks
(1) Select an alarm for which comment information is to be reflected, on a row basis. Here, reflect the comment in the device for the alarm message/alarm summary. **(2) Select the [Edit] menu - [Apply Device Comment] command, or click on the ⬛ icon.** **(3) A confirmation dialog box appears. Click on the** ⬛ Yes **button to execute the command** **(4) The device comment corresponding to the address will be included in the messages.** 	

5.1.4	**Alarm Import/Export**

The created Alarm data can be exported to and saved as an ALA or CSV file. Then, by importing the saved alarm data, it can be shared among Projects. CSV files created via a text editor or Microsoft Excel can be imported and used on the Alarm Editor.Alarm data's CSV file formats are as follows:

"Block", "0"	**Reserved 1**
"Block1", "0"	**Reserved 2**
"Block2", "0"	**Reserved 3**
"Block3", "0"	**Reserved 4**
"Basic Alarm"	**Message/Summary settings**

"M0064", "Function A in suspension", "0", "0", "7", "0", "0", "0"

"M0065", "Function B in suspension", "1", "1", "1", "1", "2", "1"

"M0066", "Function C in suspension", "2", "0", "3", "0", "5", "1"

"Bit Address", "Message" "Reserved 5", "Fg", "Blk", "Bg", "Blk"

Reserved 1	0 fixed	
Reserved 2 to 4	0 fixed	
Reserved 5	0 fixed	
Message Colors	Foreground color (Fg), Background color (Bg)	0 to 7
	Blink (Blk)	0: Not blink 1: Blink 2: Not blink 3: Blink

■ **Alarm Export**

Alarm data is saved as ALA or CSV files.

PROCEDURE	REMARKS
(1) Select the Alarm Editor's [Alarm] menu - [Export] command.	

(2) Click on the [Yes] **button.**

(3) Specify the file name and file type (*.ALA or *.CSV) with which the exported alarm data is saved, and click on the [Save] **button.**

Enter a comment, if desired.

If the same ALA file name already exists, the system asks if the existing file must be overwritten. If it must be overwritten, select [Yes] . If it should not be overwritten, select [No] .

(5) Click on the [Close] **button to quit the Alarm export mode.**

■ **Alarm Import**

Alarm data saved as a file is imported to the currently open Alarm Editor. Files with the extension of "*.ALA" or "*.CSV" can be imported.

To import alarm data from a CSV file, only the specified type of alarm can be imported from all the registered alarm.

Pʀᴏᴄᴇᴅᴜʀᴇ	Rᴇᴍᴀʀᴋꜱ
(1) Select the Alarm Editor's [Alarm] menu - [Import] command.	
(2) Click on the [Yes] **button.**	
(3) Select a file (*.ALA or *.CSV) to be imported, or enter the file name. Then, specify an import method.	**[Overwrite]** All current alarm registration numbers (1 to 8999) will be overwritten. **[Add to End]** Imported messages will be added after the last message line. If there are any gaps between the current registration numbers, the sequence numbers will be re-assigned to fit into all existing lines, and the imported messages will be added after the last line.
(4) When selecting CSV file as imported file type, specify the type of alarm to be imported. Only the type of alarm specified here will be imported.	When selecting ALA file as imported file type, skip step (4).

PROCEDURE	REMARKS
(5) After entering all the necessary items, click on the <u>OK</u> **button.** If the selected Device/PLC is different between the currently open project and the imported ALA file, the system asks if the preset addresses should be overwritten. If the preset addresses must be overwritten, select <u>Yes</u>. If they must not be overwritten, select <u>No</u>. **(6) Click on the** <u>Close</u> **button to quit import mode.** Since you selected [Add to End] in this example, the imported messages were added after the last line.	⚠️ *Important* **Once you complete the [Import] command, it cannot be undone.**

⚠ !
Important

· *When alarm data does not have an identifier "Block*" for the first 4 lines which indicate Reserved 1 to 4, the alarm will not be imported.*

· *If the address(es) registered in the alarm data to be imported are incorrect, set correct addresses via the Symbol Editor.*

▼**Reference**◣ *4.2.6 Symbol Editor*

· *When the number of message characters exceeds the limit, the message is imported only for the effective number of characters.*

· *When data is imported from a file in which only a message is registered, the initial value is used as an address.*

Memo

6 LT INITIAL AND SYSTEM SETTINGS

You can select many of the LT unit's initial settings through the LT Editor for Windows program. This program area is called "System Settings". When "System Settings" data is sent to the LT unit, you will not need to manually perform the initial setup of the LT unit.
A description of each LT unit setting item is provided in your "LT Series User's Manual" (sold separately). For details, refer to that manual.

6.1 .... Menu Setting Items: LT Setup

6.1   Menu Setting Items: LT Setup

In the [System Settings] mode, you can easily select the LT unit's initial settings. By doing this, you don't need to manually set up the LT panel, since the [System Settings] data is sent to the LT panel automatically. After the [System Settings] data is sent to the LT panel, you can also change those settings via the LT unit itself.

▼*Reference*◣ *LT Series User's Manual (sold separately),*
Chapter 6: INITIALIZE

```
┌──────────────────────────────────────────────────────────────┐
│ Usage  Pattern                                                 │
│                                                                │
│  [Screen/    →    [LT Setup]    →   Enter each   →  Click on the│
│  Setup]                             parameter.                 │
│                      or                          ┌────┐        │
│                                                  │ OK │ button │
│                  click on System.                └────┘        │
│                                                  to register the LT│
│                                                  system settings.│
└──────────────────────────────────────────────────────────────┘
```

Some setting commands are supported by the LT unit but not by LT Editor for Windows, or vice versa, i.e. are supported by LT Editor for Windows but not supported by the LT unit. This section describes only the commands supported by LT Editor for Windows. For a description of other commands, refer to your "LT Editor User's Manual" (sold separately). For individual settings of each external communication device network, refer to the Device/PLC Connection Manual.

◆ **Setting commands Supported by Only the LT Unit:**
· Setting Date/Time
· Self-diagnosis command
· Font settings (English, Korean, etc.)[*1]

◆ **Commands Supported by Only LT Editor:**
· **LT Settings: [Checksum]**
  Enables checksum verification.
· **LT Settings: [Screen Level Change Flow]**
  Used to switch screens in the hierarchical display mode.
· **LT Settings: [Change to Screen No.]**
  Specify the number of the screen used to replace the current one after the preset standby time has passed. If you enter "0", no screen will be displayed.
· **I/O Settings: [Offline Mode]**
  Specify how to change from on-line mode to off-line mode.
· **I/O Settings [Printer Type]**
  Specify whether to use the LT's Tool Connector to perform print operations. If you select "Yes" (using the LT's Tool Connector), configure the printer type and detailed print settings.

---

*1 If any font setting other than "Japanese" is selected, "Font Setting" requires specifying whether alphanumeric characters and symbols are to be displayed at the high quality level.

· **Mode Settings: [Device/PLC]**

   Displays the name of the host (Device/PLC) connected to the LT panel.

· **Mode Settings: [Option]**

   ▼**Reference**▲   *Device/PLC Connection Manual*

· **Extended Settings: [Keypad Display Priority]**

   Designates the Keypad Display processing mode. "Standard" mode executes the processing of the Keypad Display once per scan time, and "Twice" mode executes the processing two times per scan time.

· **Extended Settings: [Backup Settings]**

   Used to back up the LT panel's LS area data. Specify the initial address of the backup range, and the number of words used.

· **Extended Settings: [Delete Error Display](Only for programless type)**

   Displays an error message when an communication error occurs with the LT unit panel, and deletes the error message when the communication error is reset. System errors however cannot be reset, regardless of this setting.

· **Extended Settings: [Watch Dog]**

   Monitors the communication status between the LT panel and Device/ PLC. The LT unit sends "00FF" to the External Device's word address at a specified time interval. The Device/PLC (ladder program, etc.) checks whether the communication is performed normally by confirming the "00FF" command at the specified time interval.
   The data that is checked should then be cleared to "0", in order to detect new data writes from the LT unit. However, if the LT's internal common relay (special relay) data (LS2032)'s bit 2 is ON, the LT will be unable to write.

· **Communication Settings: [Send Wait]**

   If the LT unit sends a command to the Device/PLC immediately after receiving a response from the Device/PLC, the Device/PLC cannot receive the command, which will cause a communication error, depending on the Device/PLC. In this case, enter a value for the transmission wait time. If a transmission wait time has been entered, the LT unit waits for the preset time duration after receiving the External Device's response, and then sends the next command to the Device/ PLC.

■ Tab Setting Items

Each tab's setting items are described here.

Note: **The setting items may differ depending on the LT type or Device/PLC being used.**

◆ LT Settings

System Setting Items

Designate the arbitrarily specified password (0-9999) or select the ON/OFF setting for the common password setting (1101).

◆ I/O Settings

Touch Panel Settings

LCD Settings

Printer Settings

◆ **Mode Settings**

Operating Environment
Settings

Node Information Settings

Customizing command
(n:1)

Operating Environment
Options

◆ **Initial Screen Settings**

Initial Screen Settings

◆ **Extended Settings**

Font Settings

Keypad Display Priority Settings

Watchdog Monitoring Address and Time Settings

Error Handling Settings

String Data Settings

System Area Backup Command Settings

LT Internal Memory Data Area Settings

Global Window Settings

◆ **Communication Settings Menu**

Communication Parameter Settings

Communication Monitor Time Settings

■ **LT System Settings**

PROCEDURE	REMARKS
(1) Via the Project Manager, select the [Screen/Setup] menu - [System Setup] command, or click on the [System] icon. **(2) Click on a desired menu tab.** Each tab's setting items will be displayed. 	
(3) After entering all the necessary items, click on the OK button. 	To reset each item to its default value, click on the Default button.

Memo

7 TRANSFERRING SCREENS

To display screens created with the LT Editor on the LT unit, or to run the created logic program on the LT unit, you must first transfer data to the LT. Conversely, you can also transfer the data stored in the LT unit back to the LT Editor.

This chapter describes how to transfer data to and from the LT unit.

7.1   Prior to Transferring Data

7.1.1   LT Screen Transfer Cable

You must first connect the Data Transfer Cable to the LT unit and your personal computer before you can transfer screen data.

Personal Computer (PC)
(or Lap-top)

Screen transfer cable
(Dsub 9-pin socket)

LT

To PC's serial
port

Mouse

To LT's Tool Connector

> **Important**
>
> - *To transfer LT Editor data to the LT unit, the optional screen transfer cable (GPW-CB02) is required. This cable does not come with any interface conversion adapter for the personal computer. Supply a connector conversion adapter compatible with the interface of your personal computer.*
>
> - *File Transfer requires approximately three times the hard disk space occupied by the Project file.*

> **Note:**
>
> - **Use a pin adapter that fits your personal computer's serial port.**
>
> - **If a serial mouse is used, be sure to connect the cable from the LT unit to a different serial port on your PC.**

7.2 Transferring Data and Logic Programs

This section describes how to transfer screen data created with the LT Editor program to and from the LT unit.

Usage Pattern
Project Manager → **[Project]** → **[Transfer]** → **[Setup]** → **[Transfer Settings]** → Specify the Setup and Communication parameters. or or Click on . Click on . **[Transfer]** → **[Prepare]** → Compile the LT Editor data LT unit data. → Click on the or icon to transfer screen data.

To display a screen (window) to perform data transfer, select the Project Manager's [Project] menu - [Transfer] command, or click on the icon.

Or, select the Screen Editor's [Screen] menu - [Transfer] command, or click on the icon. An example of this screen (window) is as follows:

The tool bar icons provide the following functions:

Send screen data and logic program

Send logic program only

Receive screen data from LT unit

Cancel Transfer

Transfer Setting

Quit Transfer Tool

> ⚠️ **Important**
> ***Do not turn OFF the PC or the LT unit, nor disconnect the transfer cable during the transfer of screen data. This can cause an error when the LT is started.***

7.2.1	**Transfer Settings**

This section describes the parameter settings necessary for screen data transfer between your personal computer and the LT unit. These parameters must be reset if your personal computer has been disconnected from the LT unit, if the LT unit has been shut down, or if a nonstandard system or protocol program has been used with the LT unit.

■ **Transfer Settings**

Select the [Setup] menu - [Transfer Settings] command, or click on the icon. Then, a dialog box to perform data transfer settings will appear.

Specify the kind of information to transfer with the screen data.

Select the PC serial port that will be used with the data transfer cable

Select a transfer speed.

Select the transfer mode

Select the setup mode

Sends the simulation protocol to the LT unit.

▼Reference◤*8.1 Overview*

Locate the setup information file

◆ **Transferring Information**

Upload Information

Check this box if you wish to send upload information to receive data from the LT unit.

> **Upload parameter data must be included to Receive data from the LT unit. If the LT unit's memory is insufficient to include the upload parameter data, data can still be transferred from your personal computer to the LT unit. However, if the upload parameter data is omitted, your personal computer cannot receive data from the LT unit.**

System Screen

Check this box if you wish to transfer LT system settings information along with other data to the LT unit.

LT Editor Ver. 2.0 Operation Manual - Screen Creation Guide

Control Data

Check this box if you wish to send logic programs along with other data to the LT unit. When transferring system programs or protocol programs, however, logic programs are always transferred regardless of the setting of this screen.

◆ **Communication Port**

Select a serial port to which the transfer cable is connected, and a transfer speed.

◆ **Transfer Method**

Send All Screens
Transfers all screen data in a Project File to the LT unit.

Automatically Send Changed Screens
Any screen data that have been updated in the current Project File are automatically transferred to the LT unit. This transfer mode is only effective when screens have been previously transferred to the LT unit.

Note: **When "Automatically Send Changed Screens" is used, screens that have been deleted (not just updated) from the Project File in the LT Editor program will not be automatically deleted from the Project File stored in the LT unit. To completely replace all screens of the Project File stored in the LT unit, be sure to use "Send All Screens".**

Send User Selected Screens
When transferring a screen to a Project File stored in the LT unit, you must specify the screen type.

Note: **No Filing Data and logged data can be specified to transfer them.**

To select screens, click on the names of desired screens while holding down the [Ctrl] key.

◆ **Setup**

Automatic setup :

Set up operation is performed if necessary, according to the LT's status. Normally, select this setup mode.

Force system setup :

Setup operation is performed every time screen data are transferred, regardless of the LT's status.

Do not setup :

Setup operation is not performed, and only screen data and logic programs are transferred.

Setup CFG file :

This is the file storing the setup information. Normally, you need not use this setup mode.

If you select "English" and perform setup, the OFFLINE screen on the LT unit will be displayed in English.

Important *If you have changed from Japanese to English or vice versa, be sure to force the system setup.*

Use Extended Program

When using the Simulation Function with the LT Type-C, you need to transfer a simulation protocol in advance.

▼**Reference**▲   *8.1 Overview*

| 7.2.2 | **Passwords** |

■ Registering a Password

You can enter a password to restrict user access to the data transfer function.

Important

- *Be sure to keep a copy of the password in a safe place. If you forget the password, the "Transfer" function cannot be executed.*

- *The password is limited to 24 characters and only alphanumeric data (no symbols) can be used.*

PROCEDURE	REMARKS
(1) Via the Project Manager, select the [Project] menu - [Transfer] command, or click on the **icon. Or, via the Screen Editor, select the [Screen] menu - [Transfer] command, or click on the** **icon.**	
(2) Select the [Setup] menu - [Password] command.	
(3) Enter a password.	
(4) Enter the same password again for confirmation, and then, click on the OK **button.**	If a password has already been registered, the [Change Password] dialog box will appear.

■ Changing a Password

The registered password can be changed or canceled.

PROCEDURE	REMARKS
(1) Via the Project Manager, select the [Project] menu - [Transfer] command, or click on the ⊞ **icon. Or, via the Screen Editor, select the [Screen] menu - [Transfer] command, or click on the** ⊞ **icon.**	
(2) Select the [Setup] menu - [Password] command.	
(3) In order to change a password, you must first enter the currently registered password.	

(4) Enter a new password. 	To cancel the password, after entering the currently registered password in step (2), DO NOT enter a new password in step (3) and simply click on the [OK] button.
(5) Enter the same password again for confirmation, and then, click on the [OK] button. 	

7.2.3   Transfer Preparation

The Project File (LTE file) data created with the LT Editor program is first compiled before it is transferred to the LT unit.
Select the [Project] menu - [Prepare] command to compile your data.

```
Transfer

Transfer  Setup  View  Options  Help

Project File:      Factory A.lte          Transfer Method:   Selected

Description:       Factory A             System Setup:      Automatic

                                         Send To:           LT

Transfer Status:                         Prepare Status:

                                         --- End Prepare ---




Overall Progress:



Ready                                                        NUM
```

Note: • **To prepare the transfer, about the 3 times the project file size is required in your computer's hard disk.**

• **After the [Prepare] command is finished, you can check the LT unit's current memory capacity with the [Project Information] feature.**

▼*Reference* *4.4.1 Project Information*

• **Once you use the [Prepare] command, you do not need to use it again for the same data, unless the data has been updated.**

• **If the Project File to be transferred is stored on your PC's floppy disk, copy it to your PC's hard disk prior to using "Prepare" to reduce transfer time.**

7.2.4	When Sending Screens and Logic Programs Together To the LT

To display screen created with LT Editor and to run created logic programs on the LT panel, you must first transfer data from the LT Editor to the LT unit.

The [All Send] command transfers the screen data and logic programs at the same time. You can also send logic programs alone.

▼ Reference ◣ *7.2.5 When Sending Logic Programs*

Important **In the case of LT Type C, if the LT is not connected to the external device when the screen data are transferred to the LT and the "Change State" function is set to "Yes", bit switches, toggle switches, lamps, and objects will not be displayed on the LT panel after data transfer.**

PROCEDURE	REMARKS
(1) Via the Project Manager, select the [Project] menu - [Transfer] command, or click on the [icon] **icon. Otherwise, via the Screen Editor, select the [Screen] menu - [Transfer] command, or click on the** [icon] **icon.**	Make sure that the LT unit is in the "Transfer Screen Data" mode or "RUN" mode. ▼ Reference ◣ *LT Series User's Manual (sold separately): CHAPTER 6 INITIALIZE*
(2) Select the [Transfer] menu - [Send] command, or click on the [icon] **icon.** If the currently open Project File has not been prepared for data transfer (the Project File has not been compiled), then the system automatically compiles the Project File before transferring it to the LT unit. To transfer a screen to the LT unit for the first time, set up the LT unit[*1] first, and then transfer the screen data. The number of screens transferred is displayed in [Transfer Status]. If the external device designated in the project file to be transferred is different from the LT's existing internal data, the following message will appear. When you click on the [OK] button, the system starts setup operation, and then transfers the screen data.	When transferring logic programs, you must first select [Control Data] in the [Transfer Settings] dialog box. ▼ Reference ◣ *7.2.1 Transfer Settings* To cancel the data transfer mode, click on the [icon] icon.
Protocol Download [✕] External Device type is Different. OK to Continue? [OK] [Cancel] **LT's Project File is Different** [✕] Sending All Files [OK] [Cancel]	
After set up is completed, the LT panel screen is automatically switched to the OFF-LINE mode. Confirm the initial setting on the LT panel, and adjust the settings as required.	Data transfer mode will automatically quit when the LT unit's internal memory capacity becomes insufficient.

*1 "LT setup" means to download the system program and protocol program from LT Editor to the LT unit so that the LT unit can operate in the specified environment.

PROCEDURE	REMARKS
(3) After screen data transfer is completed, select the [Transfer] menu - [Exit] command, or click on the ⬛ icon.	

■ Transferring a Screen Using a Password

If a password has been registered, you must enter it to transfer data to the LT unit.

PROCEDURE	REMARKS
(1) Via the Project Manager, select the [Project] menu - [Transfer] command, or click on the ⬛ icon. Or, via the Screen Editor, select the [Screen] menu - [Transfer] command, or click on the ⬛ icon. icon.	
(2) Select the [Transfer] menu - [Send] command, or click on the ⬛ icon.	If you enter an incorrect password three times or more, data transfer cannot be performed. In this case, repeat the transfer procedure from step (2).
(3) Enter the registered password, and click on the ⬛ OK button to confirm it. The data transfer operation will start.	**Invalid Password!** Please Retype password OK Cancel
(4) After screen data transfer is completed, select the [Transferring Data and Logic Programs] menu - [Exit] command, or click on the ⬛ icon.	To cancel data transfer mode, click on the ⬛ icon.

7.2.5	When Sending Logic Programs

You can also send logic programs alone to the LT that has been already set up.

Logic programs can be transferred from the Logic Program Editor as well.

▼**Reference**◣ *7.2.7 Sending Programs with the Logic Program Editor*

Before sending logic programs alone, be sure to select the [All Send] command.

▼**Reference**◣ *7.2.4 When Sending Screens and Logic Programs Together To the LT*

PROCEDURE	REMARKS
(1) Via the Project Manager, select the [Project] menu - [Transfer] command, or click on the [icon]. Otherwise, via the Screen Editor, select the [Screen] menu - [Transfer] command, or click on the [icon].	The LT unit must be set to [Screen Transfer mode] or [Running mode]. ▼**Reference**◣ *LT Series User's Manual (sold separately): CHAPTER 6 INITIALIZE*
(2) Select the [Only Control Send] command, or click on the [icon]. If a password has been registered, enter the password. **Password Entry** Enter Password: ****** OK Cancel Help	▼**Reference**◣ *7.2.2. Passwords* If you enter an incorrect password three times or more, data transfer cannot be performed. In this case, repeat the transfer procedure from step (2). **Invalid Password!** Please Retype password OK Cancel
(3) After the transfer is completed, select the [Transfer] menu - [Exit] command, or click on the [icon].	To cancel data transfer mode, click on the [icon].

7.2.6 **When Receiving Data From the LT**

Data stored in the LT unit can be received on a project file basis by the LT Editor.
To receive transferred data with the password registered, password entry is required when receiving the data.

! *Important* **Unless [Upload Information] is selected in the [Transfer Set-tings] dialog box when any data is transferred to the LT unit, the data cannot be received from the LT unit.**

PROCEDURE	REMARKS
(1) Via the Project Manager, select the [Project] menu - [Transfer] command, or click on the icon. Or, via the Screen Editor, select the [Screen] menu - [Transfer] command, or click on the icon.	
(2) Select the [Transfer] menu - [Receive] command, or click on the icon. If a password has been registered, enter the password.	▼*Reference*▲ ***7.2.2. Passwords*** If you enter an incorrect password three times or more, data transfer can-not be performed. In this case, repeat the transfer procedure from step (2).
(3) Specify a location (directory) and Project file to store the received data. Then, click on the ⎡ Save ⎤ but-ton. If the same Project File name already exists, the system asks if you wish to replace it; if so, select ⎡ Yes ⎤, otherwise select ⎡ No ⎤.	To cancel data transfer mode, click on the icon.
(4) After the data transfer is completed, select the [Trans-fer] menu - [Exit] command, or click on the icon.	

7.2.7 ▷ **Sending Programs with the Logic Program Editor**

The Logic Program Editor allows you to send (write) logic programs alone to the LT that has been already set up. You can also receive (read) logic programs from the LT.

⚠ **Important**

Before sending logic programs alone, be sure to select [Send Together] command.

▽ **Reference** △ *7.2.4 When Sending Screens and Logic Programs Together To the LT*

■ **Sending Logic Programs**

PROCEDURE	REMARKS
(1) **Via the Project Manager, select [Control] menu - [Editor] command, or click on the ⊡ icon to start the Logic Program Editor.** 	▽ **Reference** △ *1.2.3 Creating/ Editing/Saving a Logic Program*
(2) **Select the [Controller] menu - [Write to Controller] command, or click on the ⊡ icon to send logic programs.** If a password has been registered, enter the password. Logic programs alone are sent.	▽ **Reference** △ *7.2.2 Passwords*

■ **Receiving Logic Programs**

PROCEDURE	REMARKS
(1)Via the Project Manager, select [Control] menu - [Editor] command, or click on the ⬚ icon to start the Logic Program Editor.	▽*Reference*△ *1.2.3 Creating/Editing/Saving a Logic Program*
(2)Select the [Controller] menu - [Read from Controller] command, or click on the ⬚ icon to receive logic programs. If a password has been registered, enter the password. Logic programs alone are received.	▽*Reference*△*7.2.2 Passwords*

7.3 ▶ Options

In addition to transferring/receiving screen data, you can check the screen information on the connected LT Unit using the LT Editor program.

Usage Pattern

[Project Manger] → **[Transfer]** → **[Option]** → Select a desired item. → [OK] Click on the OK button.

or

Click on [Transfer].

7.3.1 ▶ LT Internal Screen Data Information

LT internal information will be displayed, here. Functions such as [Screen List], [Memory Info] and [LT Version] are included.

■ List Screens

The screen name, data volume and title of the screens stored in the LT unit are listed by screen type.

PROCEDURE	REMARKS
(1) Select the [Options] menu - [Screens List] command. Screens of the current project will be listed. **(2) After confirming the displayed information, click on the** [OK] **button to close the screen list.** **[Upload Information]: ..** Indicates if the upload information has been transferred to the LT unit or not. 	

■ **Memory Information**

The LT unit's current memory capacity for a specified memory area (bank) is displayed. Its maximum internal memory capacity is also displayed.

Pʀᴏᴄᴇᴅᴜʀᴇ	Rᴇᴍᴀʀᴋs
(1) **Select the [Options] menu - [Memory Info] command.** The receiving of memory information begins. (2) **After confirming the displayed information, click on the ☐ ᴏᴋ button to close the memory information window.** **[Max Block Size]** ....Displays the LT unit's allowable memory capacity. **[Used]** ....Displays the data volume currently used in the LT unit. **[Free]** ....Displays the amount of "Free" or remaining memory.	Number of banks provided in the LT is 32. The capacity for each bank is 59526 bytes. A single screen file cannot be stored in several banks. Therefore, the sum of the remaining memory capacity for each bank is not always equal to the transferrable screen data volume.

■ **LT Version Information**

This feature displays the LT unit version information.

PROCEDURE	REMARKS
(1)Select the [Options] menu - [LT Version] command. The receiving of version information begins. **(2)After confirming the displayed information, click on the** OK **button to close the version information window.** **Check Version** ☒ Display Type : GLC150 Version : Date : LT's Project File: A Manufacturing System.lte Date : 02/09/25 - 9:32 OK Help	

8 ▶ SIMULATION

8-1

Before transferring screen data to the LT unit and connecting the LT unit to the Device/PLC, you can check the LT panel operation by running a simulation of your LT Editor program.

This chapter describes the program simulation procedure.

8.1 .... **Overview**

8.1	**Overview**

Connect the LT unit to your personal computer via the transfer cable. Turn ON/OFF bits on the LT Editor program's Simulation screen, and change the data corresponding to the specified word address. Even if no external device is connected, you can check the operation in the LT unit and the data changes resulting from the Part functions.

Note: **The Simulation function can be used only when the LT is Type-C.**

Important ***The Simulation feature is provided for simulating Device/PLC operations on a PC. For this is only a simulation, its performance such as processing speed may differ from the actual one which is performed when the LT unit is connected with a Device/ PLC.***

Connecting method between your personal computer and the LT is the same as the one for data transfer.

▼ *Reference* △ *7.1 Prior to Transferring Data*

Personal Computer (PC)

Screen transfer cable (Dsub 9-pin socket)

LT

To the PC's serial port

To the Tool Connector

■ **Precautions**

When using the Simulation function keep in mind the following restrictions:

• The Simulation function can be used only when the LT is Type-C.

• When the external device is either THERMAC NEO Series (Omron) or Memory Link SIO Type", the simulation cannot be performed.

• Simulations of logic program's variables (Logic symbol) cannot be performed.

• To carry out a simulation, you need to transfer a simulation protocol at the LT set-up.

▼ *Reference* △ *8.1.2 Transferring Simulation Protocol*

• With a device specified in [System Setup], the simulation cannot be performed.

• If the backup function for the LS area is selected, or if a D-Script uses an LS area special relay for its start bit, no LS device can be simulated.

- If the LS device is frequently written using the D-script during the LS device simulation, actions such as a slide transition will be slow.

- DO NOT specify [System Setup]-[Extended Settings] tab-[Reset LT On Data Write Error].

- The screen on the LT panel cannot be changed.

- The simulation cannot be performed for any address greater than 32,768 (8000h). To perform a simulation for such an address, temporarily change the address to 32,767 or lower.

- Do not press any touch panel switch on the LT unit before the simulation has begun. Otherwise, a system error will occur.

8.1.1   General Description of the Simulation Screen

To perform a simulation, first transfer the screen data created with the LT Editor program and the "simulation protocol" to the LT unit.

▼ **Reference** ◢ *7.2 Transferring Screens*

Usage Pattern		
[Project] → [Simulation] →	Click on the [🔲] button to start the simulation. →	Click on the [🔲] button to stop the simulation. → Click on the [🔲] button to quit the simulation.

General description of the Simulation screen:

Enter the Base Screen number where device information is to be displayed

Select a function to display device information.

Displays negative values with a minus sign

Select which to screen to be displayed on the LT panel during the simulation

Selects the format of the display and input data

Starts/Stops the simulation

Register an address

Quits the simulation function

Blinks while the simulation is being executed

Displays the device information of Parts placed on each screen

Changes the device status

Changes the system status

Displays the current status of the system

The toolbar icons have the following functions:

Starts a simulation

Registers the address

Stops a simulation

Quits the simulation function

◆ **Chg. Scr.**

When the ☑ Check Box is marked, the LT panel screen is changed according to the Simulation screen. When this Check Box is ☐ , the LT panel screen can be separately changed, independent of the Simulation screen.

◆ **Displayed Function Selection**

The function used to display the simulation can be changed. In addition to the settings of each screen, the devices show in the following figure that have been set with the screen-independent global functions can slso be displayed.

```
Screen              ▼
Screen
Window Screen
Alarm
Data Sampling
Global D-Script
Filing
Data Logging
Registered Address
```

◆ **Format**

The data format of the device status (displayed in the "Status" cell) and the device data (displayed in the "Change" cell) can be selected for "Dec" (decimal), "Hex" (hexadecimal), or "Oct" (octadecimal) format.

◆ **+/−**

Marking the "+/−" check box adds a "- (minus)" sign to the displayed values, if the word address settings displayed in the "Status" cell are negative values.

◆ **Name/Comment**

ID number of a Part or any comment is displayed. To switch the ID number or comment display mode, select [Name] of [Comment] from the [View] menu.

◆ **Function**

A general description of the device function for each specified Part is displayed.

◆ **Address**

The device specified for each Part is displayed and you can change their word address settings.

◆ **Status**

The current status of each device (bit ON/OFF status or word address setting) is displayed, and you can change their word address settings.

◆ **Alter**

You can change each device status (bit ON/OFF) or the word address settings. Every time you click on the ⬚ icon, the bit ON/OFF status is switched. When you click on the ⬚ icon, the following Keypad will appear, enabling you to change the data.

```
Word Number Entry   ☒
I
Back  +/-      Clr
Ⓐ Ⓑ Ⓒ  7 8 9
Ⓓ Ⓔ Ⓕ  4 5 6
         1 2 3
         0  ENT
```

■ **Selecting a Display Type**

Select the types of Parts used to display device information.
Select the [Options] menu - [Display Type Settings] command.

Specify the Parts to be displayed.
When you select "All Type", information on all Parts will be displayed.

■ **Setting up the Device Memory**

Even after the simulation function has been closed, device information can
be saved to the Project File.
Select the [Options] menu - [Device Memory Settings] command.

When the "Backup" check box is marked ▣ , device information is auto-
matically saved when the simulation function is quit. When the simulation
starts up again, the same device status will be displayed.

Clicking on the ⎹ Device Clear ⎸ button resets all device settings to "0".

■ **Movement Settings**

LS devices can also be simulated in the range from LS0020 to LS2031 (excluding the read-in area). Select the [Movement Settings] command from the [Option] menu.

If the [LS Device] check box is marked, the Parts that use LS devices will be displayed when a simulation is executed.

■ **Address Registration**

Simulation can be performed for any registered address, not for each screen or function.
The simulation result is displayed by selecting the registered address from the display function pull-down list's [Address Registration].

To register/edit an address, select the [Simulation] menu - [Address Registration] command, or click on the [icon] icon.

Note: **The address to be entered varies depending on your LT and PLC type. Note that the sample screen in this manual is just one example.**

◆ **Adding a registered address**

You can add a new address. Click on the [Add] button, and the following dialog box will appear. Then, enter an address and the number of addresses to be added, and specify Bit or Word.

After entering a number of addresses to be added, addresses are added from the designated number in series.

You can enter a desired name as a function name with up to 20 half-sized characters.

◆ **Editing a registered address**

You can change the registered address settings. Select an address to be edited and click on the [Edit] button. Then, a dialog box that is the same as for the adding of a registered address will appear.

◆ **Deleting a registered address**

You can delete a registered address. Select an address to be deleted and click on the [Delete] button. Then, a dialog box will appear to confirm the command. If you execute the delete command, click on the [OK] button, and if you cancel it, click on the [Cancel] button.

◆ **Copying and pasting a registered address**

Select an address to be copied and click on the [Copy] button. Then, click on the [Paste] button to add the copied address at the end of the list.

8.1.2	Transferring Simulation Protocol

To simulate the LT panel's actual operation using the LT Editor program, transfer the screen data created with the LT Editor program along with the "simulation protocol" to the LT unit.

▼Reference◢ *7.2 Transferring Screens*

Usage Pattern

[Project Manager] → **[Transfer]** → **[Setup]** → **[Transfer Settings]** → Check ☑ the "Use Extended Program"area's "Simulation" Check Box.

or

Click on [icon].

or

Click on [icon].

→ **[Transfer]** → **[Prepare]** → Compile the Project File with the LT Editor program so that it is formatted for the LT unit used for the simulation. → Click on the [icon] icon to transfer the screen data and simulation protocol to the LT unit.

■ **Simulation Protocol**

Before executing the simulation, you must first transfer the simulation protocol to the LT unit, regardless of the Device/PLC specified for the project file.
Check the "Use Extended Program" area's "Simulation" Check Box in the [Transfer Settings] dialog box so that when screens are transferred, the simulation protocol will be transferred to the LT unit.

▼Reference◢ *7.2.1 Transfer Settings*

Note: **When a simulation is executed , you need to transfer the simulation protocol only for the first screen transfer.**

8.1.3	**Performing a Simulation**

To perform a simulation, first connect the LT unit to your personal computer using the Data Transfer Cable.

> **!** *Important*
>
> • ***Before performing a simulation, you must transfer the simulation protocol to the LT unit.***
>
> ▽ **Reference** △ *8.1.2 Transferring Simulation Protocol*
>
> • ***Be sure not to press the touch panel switch of the LT main unit before the simulation starts. Especially, be sure not to change the screen of the LT unit. Otherwise, a system error will occur.***

PROCEDURE	**R** E M A R K S
Connect the LT unit to your personal computer with the Data Transfer Cable.	Prior to starting simulation, set the LT unit to the RUN mode.

PROCEDURE

Connect the LT unit to your personal computer with the Data Transfer Cable.

(1) **Via the Project Manager, select the [Project] menu - [Simulation] command.**

(2) **Click on the [⊞] button to begin communication with the LT unit.**
The device information on the current LT panel screen is displayed.

You can check the LT panel operation by switching screens or changing the device settings using the [⊡] or [⊞] icon displayed in the [Alter] cell. Also, you can check the device status changes via the LT's touch keys.

(3) **Click on the [⊡] button to quit the simulation.**

(4) **Click on the [⊡▸] button to quit the simulation mode.**

REMARKS

Prior to starting simulation, set the LT unit to the RUN mode.

If the simulation protocol has not been transferred to the LT unit in step (1), the following dialog box will appear, and the simulation cannot be started.

> ⚠ The simulation protocol has not yet been transferred. Please designate the protocol in the screen transfer menu.
>
> [OK]

During communication, the [⊡] icon blinks, like this [⊠] .

▽ **Reference** △ *8.1.1 General Description of the Simulation Screen*

During simulation, screen data cannot be transferred. Click on the [⊡] icon and stop simulation before transferring screen data.

9 PRINTING

A printed copy of created screens and Part setting conditions is often useful when debugging. This chapter describes the printing procedure and print settings.

9.1 .... **Print Settings**

9.1 ▶ Print Settings

This section describes the procedure for printing created screens or a list of designated Parts, and options available when printing.

Usage Pattern				
Project Manager	→	**[Print]**	→	Select the appropriate items in the dialog box.	→	Select the data to be printed from the dialog box.

→	Specify the printing range, depending on the selected function.	→	Click on the [OK] button to start printing.

9.1.1 ▶ Printing

When you select the [Project] menu - [Print] command, the [Print] screen will be displayed.

■ Printing - [Print] Tab

Specify the printer type and other print settings on your personal computer. Only Windows-compatible printers that can be connected to your personal computer can be used to print with LT Editor for Windows.

Displays the printer name specified on your personal computer

Displays the printing-related [Property] dialog box

If this box is checked, instead of printing a hard-copy, the data is saved as a RTF text file (*.RTF), and can be edited with other text editing software**

Click on this button to display the Cover Page dialog box

Comments on the data printed can be entered to be printed out along with the data. To print comments, check this box

Enter the number of copies to be printed; the default setting is 1

Click on this button to display the [Options] dialog box

A cover page with a title, company name, date/time, name, and a bit map can be included with the document.

Select the Text Table to be printer

📝 ***Note:*** • **The printing setting information can be saved by clicking on the [Apply] button.**

• **The printing orientation is "Vertical" (Portrait).**

• **Only "A3", "B4", or "A4" paper can be used for printing.**

◆ **Cover Page Dialog Box**

Check this box to print a title on the cover page

Enter a title or a company name of up to 3 lines (40 characters per line)

Check this box to include the date and time of printing on the cover page

Check this box to include a Bit-map on the cover page

Check this box to print a company name on the cover page

Check this box to print a name on the cover page

Enter the name here

Click on this button to preview the cover page layout. When Bit-map printing is selected, the placement of the Bit-map on the cover page can be changed.

◆ **Comment Information Dialog Box**

Enter a comment of up to 40 lines (80 characters per line)

◆ **Options Dialog Box**

Settings in the Options dialog box allow you to format the pages of the document to be printed. You can specify the range of page numbers to be printed, the screen color, and margin size.

Prints the black/ white-reversed screen color

Check this box to print the page number on each page of the document

When printing page numbers, specify if the cover page is to be numbered

Enter the initial page number to be printed on the first page of the document

Specify the upper, lower, right and left margin sizes

■ **Printing - [Project Information] Tab**

You can check the created screens and Part designation status through printer output.

Prints a project information summary list

Prints the list of settings of the item marked with a check.

Displays the currently-selected item

◆ **Details**

Click on the [Detail...] button to specify detailed information of printing.

Screen List
Select the screen type to be printed.

Date Sampling Settings List
Select whether to print the summary or details of the data sampling settings.

■ **Printing - [Screen] Tab**

Select the screen type and contents to be printed.

Select the screen type to be printed

Specify the printing range using individual screen numbers. When you select [All], all screens will be printed.

Displays the currently-selected item

◆ **Details**

Click on the [Detail...] button to specify detailed information of printing.

Base Screen
Specify the printing items related to a Base Screen.

Prints a list of the screens loaded onto a specified screen

Prints a list of the Parts placed on the Base Screen. Select whether to print the summary or details of the Part list

Prints the address designation for Parts. Only the "preset addresses" can be printed

▼**Reference**◢ *2.7.7 Cross Reference/Global Cross Reference List*

Prints the D-Script settings

Outputs screen hard copies. The printing items can be specified

Select Information cahacter's printing size. When selecting [Small], 1/4-sized characters are used

When making a screen hard copy, The Parts' ON/OFF status can be specified. The same status is specified for all screens to be printed

Note: **When the summary of the Part list is printed, its right edge may get outside the paper. In this case, open the Option dialog box by clicking on [Options...] button in the [Print] tab, and then reduce the left margin.**

Window Screen

Specify the printing items related to a Window screen.

9.1.2 **Print Preview**

By selecting the [Project] menu - [Print Preview], you can preview the screen image to be printed.

Setting items are the same as those of printing. Instead of clicking on the [OK] button, click on the [Preview] button.

■ **Print Preview Screen**

Starts printing | **Previews the next page** | **Previews the previous page** | **Toggles between previewing one page per screen and previewing two pages per screen** | **Scales up/down the preview**

Closes the print preview screen

Print date and project file name

System Setup List 2002/10/09 15:42 A Ma
1. System Setup
   Check Sum On
   Touch Buzzer On
   Screen No. Data Type Bin
   Screen Level Change Flow Off
   Password None
   Standby Mode Time 0
   Change To Screen No. 0
   Com Port Start up Display 0

2. I/O Settings
   Offline Mode Top Left Corner On Forced R
   Contrast Adjustment On
   Brightness Adjustment On
   Reverse Display Off
   Touch Input Mode 2 Point
   Use Touch Panel After... No
   Refresh Rate 0
   Print From Tool Connector Not Use

3. Mode Settings
   System Start Address 01/C00000
   Machine Number 1
   Reading Area Size 0
   Link Protocol Type 1:1

4. Initial Screen Settings
   Initial Base Screen No. 1
   Alarm Character Size 4x4

Ready | TypeC | OMRON THERMAC NEO SERIES

Memo

10 ADVANCED FEATURES

The filing data (recipe) and logging functions are advanced features that increase the performance of your LT unit.

10.1 ▶ Filing Data (Recipe)

Setting data that you have created and stored on the LT can be easily transferred to the Device/PLC whenever necessary, using LT touch keys or by specifying bit addresses in the Device/PLC. Also, Filing (Recipe) Data that has been transferred to the Device/PLC can be then sent back to the LT, edited, and then transferred again to the Device/PLC.

■ **Overview**

- There are two methods of transmitting filing data to the Device/PLC. One is automatic transmission, where filing data is sent to the Device/PLC via a Device/PLC trigger. The other is manual transmission, where data selected on the LT screen is sent to the Device/PLC.

- When using manual data transmission, select the Filing Data Display from the Tool Box or [Parts] menus.

- Filing data can be controlled by file numbers for each project file.

- Filing data can be stored in the LT's internal memory.

- Filing data is stored in the Device/PLC in a series of addresses.

- Setting up filing data so that it is transmitted via an LS Area allows filing data to be edited on the LT panel and then written to the Device/PLC.

10.1.1 Filing Data (Recipe) Function

■ Filing Data Transfer Flow

Filing data is first written from the LT's internal memory, then to the LT's backup SRAM and then is transferred to the Device/PLC, either directly or via the LS area.

■ Managing Filing Data in Group

Filing data is organized into folders, files, blocks, and data. Also, to use as much filing data as possible, multiple folders can be used in the LT's internal memory to register multiple filing data items.

You can register multiple folders by selecting [Use Multiple Folders] from the [Filing Settings] menu.

◆ When multiple folders are not used

Only 1 folder is registered. In this case, the folder number is usually not designated, however, whenever it is necessary, the number is designated as 1.

◆ When multiple folders are used

Multiple filing data folders can be registered. In the LT, the folder numbers need to be designated to transfer data to the LT's internal memory and backup SRAM. Since only one filing data folder can be used on the LT at one time, select which folder will be used.

• Multiple folders can be registered in both the LT's internal memory.
• Up to 64 folders can be registered in the LT's internal memory.
• Select a folder to be used on the LT.
• Only one folder of data can be transferred to the LT's backup SRAM.

■ **Filing Data Registration Capacity**

When saving filing data, up to 2,048 filing data files can be registered, with up to 1,650 data blocks in each file, and up to 10,000 pieces of data in each block. (However, when the data format is 32 Bits, only 5,000 data items can be registered.)

Registration capacity, however, varies depending on the use of the backup SRAM or other settings.

Up to 59520 bytes of filing data can be stored in one folder in the LT's internal memory. (when storing only filing data to the backup SRAM).

◆ **SRAM Storage Capacity Calculation**

1 file = 96 (Fixed value) + (32 + 2 or 4 x number of data pieces) x number of data blocks

Use "2" for 16 Bit devices, and use "4" for 32 Bit device file calculation.

Total capacity of all files < 59520

The following shows Storage Capacity when using 16 Bit Device Data Format.

No. of files	No. of data pieces	No. of data blocks	Total capacity of all files
1	2	1650	59496
1	640	45	59136
1	10000	2	40160

◆ **Usage priority of backup SRAM**

1) **Data sampling**

2) **Trend graph**

3) **LS Area backup**

4) **Logging data**

5) **Filing data**

SRAM Memory is used starting from item 1).

To check the LT's available usage capacity,
▼*Reference*▲ *4.4.1 Project Information*

- *Data in backup SRAM is erased when:*
  - *The LT's memory is initialized.*
  - *Data is transmitted.*
  - *The LT system and protocol are set up.*
  - *LT's self-diagnosis "Internal FEPROM (screen area)" is performed.*
- *As the number of Addresses increases, the more time is required for writing data to the Device/PLC. Depending on the number of Addresses, it may take from 20 seconds to several minutes.*

- *When data is being written, screen displays, such as for Parts, may not be updated/refreshed or may appear slowly. Screen changes may also be performed slowly. If screens are changed at this time, screen data such as for Parts will also be read out, and data writing to the Device/PLC will be performed at a slower than normal speed.*

- *DO NOT perform any of the following operations at the same time.*
    - *Data transfer between the LS area and the Device/PLC*
    - *Data transfer between SRAM and the Device/PLC: via the File Name Display*
    - *Data transfer between SRAM and the Device/PLC: via the Control Word Address using Transfer Settings*

    Be sure to perform data transfer after the current data transfer is completed.

- *During the current data write, the succeeding data write operation cannot be accepted/received.*

■ LS Area Filing Data Structure

Designated address

Data transmitted between the backup SRAM and LS Area will overwrite the existing Block Name and Block data.

Data transmitted from the Device/PLC to the LS Area overwrites only file data and preserves the Block Name.

- **When a device is used with a 32 Bit system start Address, filing data cannot be transmitted to the Device/PLC via the LS Area.**

- **Block Name text characters are stored in order of the character input.**

  ▼Reference◣ *LT Series User's Manual 6.3.2 Text Data Settings*

■ Filing Data Transmission Methods

◆ Automatic Transmission

Filing data is transmitted from the LT to the Device/PLC via a Device/PLC trigger. Use the Control Word Address instead of using the Filing Data Display to transfer data between the LT and the Device/PLC (LT→Device/ PLC, Device/PLC→LT.)

(1) Device/PLC Trigger

  ▼Reference◣ *10.1.2 Filing Data Setting* ◆ *Control Word Address (Filing Data→ SRAM)*

(2) Device/PLC Trigger

  ▼Reference◣ *10.1.2 Filing Data Setting* ◆ *Control Word Address (SRAM ←→Device/PLC)*

![Important]
- *When a single folder is used, designate the folder number as 1.*
- *If the designated number's folder does not exist, data will not be transferred to backup SRAM. Also, the Write Completed Bit Address will not be turned ON.*
- *When data is not transferred to backup SRAM, the LT internal special relay (LS2032)'s bit 9 will turn ON.*

◆ **Manual Transmission - type 1**

Filing data is transmitted to the Device/PLC by touching a LT screen touch key. Use the Filing Data Display to transfer data to/from the Device/PLC, using the "SRAM→Device/PLC" touch key and the "Device/PLC→SRAM" touch key.

(1) Device/PLC Trigger

▼Reference◣ *10.1.2 Filing Data Setting ◆ Control Word Address (Filing Data→ SRAM)*

(2)Screen Touch Keys

▼Reference◣ *10.1.5 Manual Filing Data Transmission Example 1/*
■ *Filing Data Transmission Flow*

Note: **When filing data is sent back to the Device/PLC from backup SRAM, the newly sent data will overwrite the old. In order to prevent this, beforehand create another data block for the return value data (See the figure below) to send the filing data to and designate that block via the Control Word Address.**

File 0			
A	B	A Return Value	B Return Value
50	40	0	0
60	30	0	0

◆ **Manual Transmission - type 2**

Select the desired filing data via the screen's touch keys, perform any data changes, and then transmit the edited data to the Device/PLC. Use the Filing Data Display to transfer data to/from the Device/PLC, using the "LS→Device/PLC" touch key and the "Device/PLC→LS" touch key.

(1) Device/PLC Trigger

▼Reference◣ *10.1.2 Filing Data Setting ◆ Control Word Address (Filing Data→ SRAM)*

(2) Screen touch keys

▼Reference◣ *10.1.6 Manual Filing Data Transmission Example 2 (1) Writing filling data to SRAM*

(3) Screen touch keys

▽*Reference*△ *10.1.6 Manual Filing Data Transmission Example 2 (5) LS*
Area to Device/PLC

■ Filing Data Setup Procedure

```
┌─────────────────────────┐
│ (1) Filing data registration │
└─────────────────────────┘
            │
            ▼
┌─────────────────────────┐
│ (2) Enter Write Settings │
│   (for sending Filing Data to │
│   SRAM) │
└─────────────────────────┘
            │
            ▼
┌─────────────────────────┐        ┌─────────────────────────────┐
│ (3) Enter External Device & │       │ (4) Setup Filing Data Display and │
│   SRAM Direct Data │─────────▶│   their Screen Placement │
│   Transmission Settings │        └─────────────────────────────┘
└─────────────────────────┘                    │        ┌─────────────────────────┐
            │                                   │        │ (5) Setup Keypad Display and │
            │                                   │───────▶│   its Screen Placement │
            ▼                                   ▼        └─────────────────────────┘
┌─────────────────────────┐        ┌─────────────────────────┐            │
│ Automatic Data Transmission │       │ Manual Data Transmission 1 │           │
│ Completed │                        │ Completed │                           ▼
└─────────────────────────┘        └─────────────────────────┘  ┌─────────────────────────┐
                                                                 │ Manual Data Transmission 2 │
                                                                 │ Completed │
                                                                 └─────────────────────────┘
```

(1) Filing Data Registration via [Filing Data]/[Filing List]

(2) Setup of [Write Settings (Send Filing Data to SRAM)] via [Filing Data]/
[Filing Setting]

(3) When performing automatic data transmission, setup the [Device/PLC &
SRAM Direct Data Transmission Settings] via the same dialog box.
Automatic Data Transmission is completed here.

(4) When performing manual data transmission - type 1, setup the Filing
Data Display and designate its placement.

Manual Data Transmission - type 1 is completed here.

(5) When performing manual data transmission - Type 2, setup the Keypad
Display and designate its placement.
Manual Data Transmission - Type 2 setting is completed here.

10.1.2　Filing Data Setting

Use the following setting items to create multiple folders and a trigger for transferring data.

Select [Filing Setting] from the [Screen/Setup] - [Filing Data] menu.

◆ **Filing (ON/OFF)**

Check this check box in order to use the filing data.

◆ **Use Multiple Folders**

Check this check box in order to register 2 or more folders.

◆ **Write Settings (From Filing Data To SRAM)**

In response to a trigger, filing data stored in the LT's internal memory (screen data) is written to backup SRAM. This prepares for filing data transfer. In order to tranfer data to the Device/PLC, you need to first write data to backup SRAM. Only 1 item of filing data can be written to backup SRAM.

📝 *Note:*　**When using filing data, be sure to enter the "Write Settings" data.**

◆ **Control Word Address (Filing Data → SRAM)**

Designate a Word Address to use as a trigger, or designate the mode to use when writing to backup SRAM. This trigger controls the data write timing.

When using multiple filing data items, designate the folder numbers.

The Control Word Address will be as follows:

When Using Multiple Folders

+0	Trigger, Mode

When Not Using Multiple Folders

+0	Trigger, Mode	
+1	Folder No.	1 to 64

<Trigger, Mode>

	15 0
+0	Reservation All OFF

└── Trigger (ON: Write   OFF: Not write)

◆ **Write Completed Bit Address (Filing Data → SRAM)**

Designate a specific Bit Address to be turned ON when the data write to LT backup SRAM is completed.

Note: **If data cannot be transmitted to backup SRAM due to insufficient memory, LS2032's Bit 9 will be turned ON. When data is transmitted to backup SRAM again, use either the designated communication cycle time or 150ms, whichever is longer, as the trigger's OFF time.**

For communication cycle time details,

▼ Reference ▲ *Device/PLC Connection Manual, 1.1.4/2.1.3 Special Relays*

	Write Completed Bit Address	LS2032 Bit 9
Normal data transmission	ON	OFF
Data transmission error	-	ON

◆   **Device/PLC & SRAM Data Transmission Settings**

Here, select the method used to transmit filing data either from backup SRAM to the Device/PLC, or from the Device/PLC to backup SRAM. Select this setting when performing automatic data transmission using the Contorl Word Address feature.

◆   **Device/PLC Controlled Transfer (SRAM ←→ Device/PLC)**

When this check box is selected, automatic data transmission via the External Device's trigger is set up. If this box is not checked, data must be transmitted manually using the Editor area Toolbox's Filing Data Display.

◆   **Control Word Address (SRAM ←→ Device/PLC)**

Designates a Word Address where the filing data transmission trigger and mode data are stored.

Control Word Address

| 15 | 10 9 8 7 | 1 0 |

+0	Reservation All OFF		Reservation All OFF	

Trigger (ON: Transmit   OFF: Not transmitted)

Transmission

	9	8	Mode
+1	File No.		OFF	OFF	SRAM→External Device
+2	Block No.		OFF	ON	External Device→SRAM

◆   **Transmit Completed Bit Address (SRAM ←→ Device/PLC)**

Designates the Bit Address that will be turned ON when filing data transmission is completed.

Note: • **Use binary numbers to designate file and block numbers.**

• **If data transmission cannot be performed, LS2032's Bit 10 is turned ON. To transmit data to the Device/PLC, use either your standard communication cycle time or 150ms, whichever is longer, as the trigger OFF time.**

For Communication cycle time details,

▼**Reference**◣ *Device/PLC Connection Manual 1.1.4/2.1.3 Special Relay*

	Transmit Completed Bit Address	LS2032 Bit 10
Normal data transmission	ON	OFF
Data transmission error	-	ON

10.1.3 Filing Data List

Filing Settings can be added, edited and deleted on the [Filing Data List] screen.

Usage Pattern				
[Screen/ Setup] →	**[Filing Data]** →	**[Filing List]** →	ADD or Edit or Delete →	[Close] or [Esc]

■ Filing Data List

Below is the overview of the screen on which you can make filing settings.

◆ When using a single folder

Adds folder and file settings.

Edits folder and file contents.

Copies folder and files.

Pastes copied folders and files.

Deletes folders and files.

Lists registered filing settings.

◆ When using multiple folders

"Internal Memory" indicates the screen data stored in the internal memory. "1-Filing Data" folder indicates the File Settings.

Adds folder and file settings.

Edits the contents of folder and file settings.

Copies folder and file settings.

Pastes copied folder and file settings.

Deletes folder and file settings.

Lists registered folders and files.   Lists registered filing settings.

■ Registering Filing Data

Here, the procedure of adding Filing Data Setting is explained.

◆ **Registering Folders**

When multiple folders are used, select [Internal Memory] and click on Add to display the screen for creating a new folder.

Folder No. (= Filing data number)
A value between 1 and 64 can be set.
Folder Title
Enter a title. (Commas"," are not allowed.)

◆ **Registering Filing Data**

When multiple folders are not used, the filing data setting screen is displayed. When multiple folders are used, you can display the filing data setting screen by selecting [1-filing Data] and click on the Add button.

File No.
Filing data is controlled in individual file units. Here, designate the file numbers of filing data to be registered. Up to 2,048 files can be registered.

Data Storage Start Address
Enter the first Address where the transferred filing data is stored. Data storage areas will be saved in series, starting from the Start Address for the number of filing data items.

Note: **The address to be entered varies depending on your LT and PLC type. Note that the sample screen in this manual is just one example.**

No. of Data Blocks
Designate the number of blocks to be registered in one file. A maximum of 1,650 blocks can be designated. (The maximum number will change depending on the number of data blocks.)

No. of Data Items
Designates the number of data items registered in one block. A maximum of 9,999 data items can be registered. (The maximum number will change depending on the number of data blocks)

> ⚠️ **Important**
> **When a variable (Logic Symbol) is used as a data storage start address, an integer array must be designated. For an integer array, an appropriate size required for consecutive addresses needs to be allocated.**

Data Format

Select either 16 or 32 bit data.

Display Format

Select a filing data display format.

Code +/-

"- (minus)" display becomes effective when this check box is checked.

Import

Other file data (CSV format) can be imported and used as filing data.

Export

Filing data can be exported and saved in the CSV format.

<Output Example using CSV Format>

"Filing Data"		Filing CSV data's Header.
"Description"	"Filing Data"	(This is necessary for data import.)
"No of Data Blocks"	"3"	
"No of Data Items"	"5"	
"Address"	"D0200"	
"Data Format"	"0"	16 Bit: 0, 32 Bit: 1
"Display Format"	"0"	Dec: 0, Hex: 1, BCD: 2
"Code"	"0"	+: 0, ;/-: 1
"Block0"	"Block1"	"Block2"
"Data1"	"Data2"	"Data3"
"0"	"10"	"1000"
"2"	"20"	"2000"
"4"	"30"	"3000"
"6"	"40"	"4000"
"8"	"50"	"5000" — If this data is incorrect, CSV data cannot be imported.

■   **Setting up Filing Data**

Entering File No., Description, No. of Data Blocks, No. of Data Items and Data Storage Start Address.

File No.: 1
Description: Heat Control
No. of Data Blocks: 3
No. of Data Items: 10
Data Storage Start Address: D00100

◆ **Filing List Display**

<When using multiple folders>   **<When using a single folder>**

Filing Data List

Folder

⊟◈ Internal	1	Temperature Settings
└🖬 1-Filing Data		

Add
Edit
Copy
Paste
Delete
Close
Help

Filing Data List

1	Temperature Settings

Add
Edit
Copy
Paste
Delete
Close
Help

10.1.4   Automatic Filing Data Transmission

Here, data transmission via the external device's trigger (automatic data transmission) is explained.

Previously entered filing data is transmitted to the Device/PLC as shown below.

Filing Data

File No. 1   No. of Data Blocks 3

Description: Heat Control   No. of Data Item 3

Data Storage Start Address   D00100   Data Format   16Bit

	Block0	Block1	Bl
Block Name	~20°C	21~35°C	36°C
D00100	200	30	55
D00101	202	30	56
D00102	205	28	62

Display Format   Dec

Clear

■ **Data Transmission via Device/PLC Trigger (Automatic Data Transmission)**

Block 1's data is transmitted when the Control Word Address changes.

Filing Setting

☑ Filing (ON/OFF)
☑ Use Muliple Folders

┌Write Settings(From Filing Data To SRAM)
  Control Word Address   00/0000
  Write Completed Bit Address   00/000000

┌External Device & SRAM Direct Data Transmission Settings
  ☐ External Device Controlled Transfer
  Control Word Address   00/0000
  Transmit Completed Bit Address 00/000000

OK   Cancel   Help

Write Settings (From Filing Data to SRAM)
 Control Word Address: D00200
 Write Completed Bit Address: M00001
Device/PLC & SRAM Direct Data Transmission Settings
 Control Word Address: D00201
 Transmit Completed Bit Address: M00002

Note: **When using multiple folders, the Control Word Addresses will be D00200 to D00201, which overlap with the following Device/PLC & SRAM Direct Data Transmission Settings, Control Word Address (D00201).**

■ **Filing Data Data Transfer**

LT

| Internal memory (Filing data) | → | Back up SRAM | | → | External Device |

◆ **Filing data → SRAM**

When the "0" Bit of a data transmission's Control Word Address (D00200) is turned ON, all the filing data is written to SRAM.

**Trigger Bit Address
1 to D00200**

**Write Completed Bit Address
M0001**

Data processing

◆ **SRAM → Device/PLC**

When the "0" Bit of the data transmission's Control Word Address (D00201) is turned ON, the designated filing data is written to the Device/PLC.

To designate filing data, prior to transferring filing data a file number is stored in D00202 and a block number is stored in D00203, directly following the Control Word Address.

**Trigger Bit Address
1 to D00201**

**Write Completed Bit Address
M0002**

Data processing

Written into PLC's D00100 to D00102

D00201	0001
D00202	0001
D00203	0001

Control Word Address

File Number 1		
Block 1	Block 2	Block 3
200	30	55
202	30	56
205	28	62

D00100	200
D00101	202
D00102	205

Transfer

10.1.5 Manual Filing Data Transmission Example 1

The following explains how to transfer data by selecting the desired screen setting (Manual Transmission 1).

The same filing data as in "10.1.4. Automatic Filing Data Transmission" is used.

■ Screen Example

In this example, data from File No. 1's Block No. 3 is sent by touching the LT screen.

■ Filing Setting Example

When [Device/PLC Controlled Transfer] is not checked, manual transfer is performed.

Write Setting (From Filing Data To SRAM)

Control Word Address: D00200
Write Completed Bit Address: M00001

Device/PLC & SRAM Direct Data Transmission Setting

Device/PLC Controlled Transfer: Not selected

■ **Filing Data Display Settings**

When manual data transmission is performed, you must place the Filing Name Display.

▽*Reference*△ *2.1.12 File Name Display*

◆ **General Settings**

Description: Heat Control
Use LS Area
Use LS Area: Not selected
Since, in this example, data is transmitted from SRAM to the Device/PLC, it is not transmitted via the LS Area. Keep the default setting.
Top Write Word Address: Not selected
Not designated. Since this example does not use the LS area, this Address does not need to be designated. When using the LS area, designate the Top Address of the LS area where data is stored.

Device/PLC Transfer
Use Transfer Completed Bit Address: Not selected
The example does not turn the Device/PLC Transfer Completed Bit Address ON when the data transfer is completed between the LS area and Device/PLC, and SRAM and Device/PLC. (No information is sent when data transfer is completed.)
When using the Transfer Completed Bit Address, after the Bit ON condition is detected, turn the corresponding Bit OFF on the Device/PLC. Also, when the Transfer Completed Bit Address is used, the special relay (LS2032)'s bit 10 will turn ON when data transfer is not completed normally, between the Device/PLC and LS area, or between the Device/PLC and SRAM.
▽*Reference*△ *Device/PLC Connection Manual; Chapter 1*

Device/PLC Transfer Completed Bit Address: Not designated
Since this example does not use the Transfer Completed Bit Address, this Address does not need to be designated. When using the Transfer Completed Bit Address, designate an Address that will be turned ON when data transfer is completed.

ID No.: 0
> In this example, where only one Filing Data Display is placed, the ID No. does not need to be entered. Keep the default setting. When placing two or more Filing Data Displays on the currently displayed screen, be sure not to use the same ID No. for multiple Filing Data Displays.

File No.: 1
> Enter the previously entered filing data number.

◆ **Display**

No. of Display Lines: 3
No. of Display Characters: 10
Direct Selection: Selected
Cursor Position Control: Selected

<Cursor Position Control>

- Even when the screens are changed on the LT monitor, the current File Name Display's cursor position can be preserved.

- Cursor Position Control can be designated when setting up the File Name Display.

- When the LT's main power is turned ON or the LT is reset, the cursor will appear on the first line.

- The cursor position will be stored for each ID No. (The storage area of an ID No. and its cursor position correspond to each other.) To retain the cursor position, be sure that the File Name Display ID Nos. do not overlap each other on any of the screens. For more detailed information about the File Name Display,

▼*Reference*▲   *2.1.12 File Name Display*

◆ **Style/Color**

Border Type: Outer and inner borders
Display Color: Select desired colors.
> Select the desired colors for Fg (foreground), Bg (background), and Blk (blink).

Erase Color: Select the desired color.
> Select the display area color to use when a Filing Data Display is cleared. When using a monochrome LT, select "Black".

◆   **Switch Settings**

Send To Device/PLC From SRAM: Selected
Send To SRAM From Device/PLC: Selected
Roll Up: Not selected
Roll Down: Not selected
Send To LS From SRAM: Not selected
Send To SRAM From LS: Not selected
Send To LS From Device/PLC: Not selected
Sending To Device/PLC From LS: Not selected

◆   **Switch Type/Color**

Border Color: Select the desired color.
    Select the desired color for the Filing
    Name Display's border.

■ **Place**

Click on the [Place] button to display the Filing Name Display. If desired, change the Part's size via its sizing handles.

✎**Note:** **To change the Filing Name Display's layout or attributes, first ungroup it.**

■ **Filing Data Transmission Flow**

◆   **Filing Data to SRAM**

All the filing data is written into the SRAM when the Trigger Bit is turned ON.

Control Word Address 1 to D00200

Write Completed Bit Address M0001

Data processing

◆ **SRAM → Device/PLC**

Filing data selected by the LT's touch key is written to the Device/PLC.

■ **Actual Process**

1) Select an item. (Here, select Block 3 "36°C -".)

2) Touch "SRAM → PLC" key.

SRAM -> PLC

3) Filing data is transmitted from SRAM to the Device/PLC.

LT

File Number 1		
Block 1	Block 2	Block 3
200	30	55
202	30	56
205	28	62

Device/PLC

D00100	55
D00101	56
D00102	62

10.1.6   Manual Filing Data Transmission Example 2

Here, select an item using the File Name Display from a screen and fine-tune (minutely adjust) the data via the LS area, and then transfer the data (manual transfer: 2).

■ **Screen Example**

■ **Filing Setting Example**

When the check box of [Device/PLC Controlled Transfer] is off, manual data transmission is performed.

Write Setting (From Filing Data To SRAM)
    Control Word Address: D00200
    Write Completed Bit Address: M00001

Device/PLC & SRAM Direct Data Transmission Setting
    Device/PLC Controlled Transfer: Not selected

■   **Filing Name Display Settings**

When manual data transmission is performed, you must place the Filing Name Display.

▽*Reference*△ *2.1.12 Filing Name Display*

◆ **General Settings**

Description: Heat Control

Use LS Area
    Use LS Area: Selected
    Filing data is first transferred to the LT's LS area before being transferred to the Device/PLC.
    While filing data is being transferred from SRAM to LS, and LS to SRAM, the LT internal special relay (LS2032)'s bit 11 will be turned ON.

Device/PLC Transfer
    Use Transfer Completed Bit Address: Not Selected
    Enables/disables the Transfer Completed Bit setting.

ID No.: 0
    In this example, where only one Filing Name Display is placed, the ID No. does not need to be entered. Keep the default setting. When placing two or more Filing Name Displays on the currently displayed screen, be sure not to use the same ID No. for multiple Filing Name Displays.

File No.: 1
    Enter the previously entered filing data number.

◆ **Display**

No. of Display Lines: 8
No. of Display Characters: 15
Direct Selection: Selected
Cursor Position Control: Selected

◆ **Cursor Position Control**

- Even when the screens are changed on the LT monitor, the current File Name Display's cursor position can be retained.

- Cursor Position Control can be designated when setting up the File Name Display.

- When turning the LT's main power switch ON or resetting the LT, the cursor will appear on the first line.

- The cursor position will be stored for each ID No. (The storage area of an ID No. and a cursor position are in correspondence with each other.) To retain the cursor position, be sure that the File Name Display ID Nos. do not overlap each other on any of the screens. For more detailed information about the File Name Display,

▼**Reference**▲ *2.1.12 File Name Display*

◆ **Switch Settings**

Send To Device/PLC From SRAM: Not Selected
Send To SRAM From Device/PLC: Not Selected
Roll Up: Selected
Roll Down: Selected
Send To LS From SRAM: Selected
Send To SRAM From LS: Selected
Send To LS From Device/PLC: Selected
Sending To Device/PLC From LS: Selected

■ Place

Click on the Place button to display the Filing Name Data Display. Change the size of placed Part, if desired. Settings Display must be placed to correspond with the storing address of the filing data.

Release Grouping

✎*Note:* **To change the Filing Name Display's layout or attributes, first ungroup it.**

1) Writing filing data to SRAM

All filing data is written to SRAM when the Trigger Bit is turned ON.

Trigger Bit Address D00200001

Write Completed Bit Address M0001

Data processing

2) Selecting a file name

Select the desired setting by touching Block 2's LT screen data.

3) Backup SRAM → LS Area

Touching the "SRAM → LS" key will transmit data from SRAM to the LS Area.

4) Data Editing

Touch the Keypad Display to display the Pop-up Keypad. Adjust the data using the Pop-up Keypad.

5) LS Area to Device/PLC

The edited data is transmitted to the Device/PLC by touching the "LS → DEV" key.

10.2 Logging

The Device/PLC data is loaded to the LT's backup area (SRAM) at bit-based or time-specified timings to display it in a tabular form on the screen or print it on the printer.

Logging data can be displayed via a Logging Display.

▼*Reference*▲ *2.1.13 Logging Display*

Logging data can be displayed with its Total, Average, Max., and Min. values, which can be set via the Data Calculation Settings.

Logging data can be entered into a database for data analysis.

10.2.1 Logging Function

■ Data Logging Flow

This flow chart shows the logging data flow and each trigger condition.

(1)Logging by the Device/PLC Trigger Bit Address or at designated timing

▼*Reference*▲ *10.2.3 Data Logging Settings ■ Trigger Settings*

(2)Data display and edit via the Logging Display

▼*Reference*▲ *10.2.4 Display Settings*

(3)Data transmission to LS Area via the Control Word Address

▼*Reference*▲ *10.2.3 Data Logging Settings ■ Write to LS*

■ **Managing Groups of Logging Data**

Logging data is grouped into files and blocks.

Up to 32 words can be logged in one time. These logged words are called "data".

A group of data is called a "block" and a group of blocks are called a "file". Be aware that the number of pieces of data in each block is considered to be the same.

File 1	
Block 1	Block 2
Data 1	Data 1
Data 2	Data 2
Data 3	Data 3
Data 4	Data 4

■ **Backup SRAM's capacity**

Backup SRAM's capacity is limited (Approximately 95KB) and all blocks and records set up must be within these limits.

The capacity of Backup SRAM to be used for logging setting is calculated by the following formulas. The formula varies depending on whether loop operation is performed or not.

▼*Reference*▲ *10.2.1 Logging Function ■ Loop Operation*

◆ **Without Loop Operation**

Used backup SRAM capacity (byte)

= 128 + 20 + {(12 + 2 X Number of logging data pieces[1]) X Frequency of data logging} X Number of blocks

◆ **With Loop Operation**

Used backup SRAM capacity (byte)

= 128 + 20 + {(12 + 2 X Number of logging data pieces[1]) X Frequency of data logging} X Number of blocks + (12 + 2 X Number of logging data pieces)

For example, when loop operation is not selected, the number of block is 1, and the number of logging is 2048, the capacity available is approximately 32 KB, assuming that the logging data consists of 2 words. If the number of pieces of data is 32 (the maximum) the memory required becomes approximately 153 KB, which is too high.

---

1 Regardless whether loop operation is designated or not, when the number of logging data items is an odd number, add 1 to the above calculation. For example, when the number of logging data items is 7, it is considered as 8 Words.

◆ **Backup SRAM usage priority order**

1) Data sampling
2) Trend graph
3) LS Area backup
4) Logging data
5) Filing data
Memory area is used starting from 1).

To check the amount of memory available,
▼**Reference**▲ *4.4.1 Project Information*

⚠ **Important**

Data stored in backup SRAM is erased at the following times:

- *When initializing LT memory*
- *When transmitting screen data from your PC to the LT.*
- *When setting up the LT system and protocol*
- *When performing LT's self-diagnosis "Internal FEPROM (screen area)"*

■ **Loop Operation**

Loop operation can be designated in logging mode. With loop operation selected, when data logging capacity becomes full, logging data will repeatedly be overwritten from the 1st (top) data area (loop operation). Also, the LT's backup SRAM (storage area) becomes one large storage area that has a linked, buffer-like structure.

<Without Loop Operation>

Block 0	Logging Data 1
	Logging Data 2
	Logging Data *n*

Block 1	Logging Data 1
	Logging Data 2
	Logging Data *n*

Block m-1	Logging Data 1
	Logging Data 2
	Logging Data *n*

Each logging data item uses the same number of Words.
The range of the number of Words is from 1 to 32.

📝 *Note:* • **When data logging is performed for the designated number of blocks, the LT will turn the File Full Bit Address ON and data logging will stop.**

• **To resume data logging, turn the Data Clear Bit Address ON from the Device/PLC. The LT then clears all logging data and will start data logging from the beginning.**

◆ **With Loop operation**

When data logging is performed to the end of a loop cycle, data logging repeats from the beginning, and overwrites the existing data.

Only one block is used, which has a linked, buffer-like structure. and is similar to the link buffer.

After data logging is completed (and control jumps from the end of the block to the beginning), the LT will turn the File Full Bit Address ON. Turning this Address ON simply indicates that data logging has been performed from the beginning to the end one time and that data logging will continue.

Block
(Single)

Logging Data 1
Logging Data 2
Logging Data 3
Logging Data *n*

Using loop operation, each logging data item also uses from 1 to 32 words.

⚠ Important

- *After the Device/PLC detects the File Full Bit's turning ON, turn the Bit OFF.*

- *When the Data Clear Bit Address turns ON from the Device/ PLC, the LT clears logging data and repeats data logging from the beginning. When logging data is cleared, the LT turns the Data Clear Bit Address OFF.*

| 10.2.2 | **Logging Data Read Timing** |

Note:
- **All the charts shown above are the basic image of LT's logging data read timing. They do not show the exact time intervals of logging data read.**
- **If a communication error occurs during logging data read, "**" is displayed on the Logging Display, representing that there is no data.**

■ When designating a Bit Address

Logging data is read only one time for each trigger.

When designating a Bit, logging data is read out if the Device/PLC Trigger Bit has been turned ON when the main power is turned ON.

1) Data is set to the Device/PLC Word Address.

2) The Device/PLC Trigger Bit Address is turned ON.

3) The logging data is read out (one time).

4) The LT_ACK Bit Address is turned ON.

5) Device/PLC detects the LT_ACK Bit Address is turned ON and the Device/PLC Trigger Bit Address is turned OFF.

6) LT detects the Device/PLC Trigger Bit Address is turned OFF and the LT_ACK Bit Address is turned OFF.

7) The Device/PLC confirms that the LT_ACK Bit Address is turned OFF.

Prior to performing steps 1) and 2) with the Device/PLC, be sure to confirm that the LT_ACK Bit Address has been turned OFF. Also, assuming that the main power may be turned OFF for some reason, be sure to take appropriate countermeasures such as turning the Device/PLC Trigger Bit and LT_ACK Bit OFF when starting operation.

■ When designating time

Logging data is read only one time at the designated timing.
When designating time without using loop operation, a Block's Finish Bit Address is turned ON when a block's data logging is completed, in order to start data read at the read start time. Logging data in the Device/PLC Word Address is cleared by the external device.

10.2.3 Data Logging Settings

Set up items in the [Trigger Setting], [Display], and [Write Settings] tabs.

Select the Project Manager's [Screen/Edit] menu - [Logging Setting] command.

■ Trigger Settings

◆ Trigger Settings (Bit Method)

Logging (ON/OFF)
Check this check box when performing data logging.

Bit Method
Select this option when using a Trigger Bit to start data logging.

Data Logging Start Address
Designate the Start Address of the Device/PLC device where data to be logged is stored.

No. of Words
Designate the desired number of words from the Start Address. Up to 32 words can be designated.

When a variable (Logic Symbol) is used as a logging start address, an integer array must be designated. For an integer array, an appropriate size required for consecutive addresses needs to be allocated.

Read Count
Designate the frequency of data logging. Data is logged at the frequency designated here and then handled as a block.

Block Count

Designate the number of data blocks. Data is logged for the number of blocks designated here and then handled as a file.

$1 \le$ Times x Blocks ≤ 2048

Trigger Bit Address

Designate a Bit Address to be used as External Device's trigger. (Device/PLC to LT)

LT_ACK Bit Address

Designate the Device/PLC Bit Address. When data logging is completed one time, LT turns ON the Bit Address designated here. (LT to Device/PLC)

File Full Bit Address

Designate the External Device's Bit Address. When data logging is performed for the designated number of blocks, the Bit Address designated here is turned ON. (LT to Device/PLC) After the Device/PLC detects the Bit Address is turned ON, turn it OFF.

Data Clear Bit Address

Designate the External Device's Bit Address. When the Bit Address designated here is turned ON, data stored in the backup SRAM is deleted. After the backup SRAM data is deleted, LT turns OFF this Bit Address.

(Device/PLC to LT, LT to Device/PLC)

Loop

Selecting this feature means when data logging is completed, it will begin again from the top-most data address and overwrite the existing data.

◆ **Trigger Settings (Time Method)**

Time Method

Select this option when performing data logging by triggering logging start at the designated timing.

Data Logging Start Address

Designate the Start Address of the Device/PLC device where data to be logged is stored.

No. of Words

Designate the desired number of words counted from the Start Address. Up to 32 words can be designated.

Start Time
> Designate the first data logging start time.

Duration
> Designate the time period that data logging is performed periodically. "S (second)" setting options are "00", "15", "30", and "45", with 15 second intervals. When designating data logging time, data logged from the start to end times is handled as 1 block.

Read Count
> Designate the frequency of data logging between the Start time and End time. Based on the frequency set here, the End time is determined.

Block Count
> Designate the number of data blocks. Data logged for the number of blocks designated here is handled as a file. When designating data logging time, data for a block is logged per day.
> $1 \leq$ Times x Blocks ≤ 2048

Data Logging Auth. Bit Address
> Designate the External Device's Bit Address. When the Bit Address designated here is turned ON and it becomes the designated logging time, data logging is performed. (Device/PLC to LT)

Block's Finish Bit Address
> Designate the External Device's Bit Address. When data logging is completed one time, the Bit Address designated here is turned ON. (LT to Device/PLC) After the Device/PLC detects that the Bit Address is turned ON, turn it OFF.

File Full Bit Address
> Designate the External Device's Bit Address. When data logging is completed for block, the Bit Address designated here is turned ON. (LT to Device/PLC) After the Device/PLC detects the Bit Address is turned ON, turn it OFF.

Data Clear Bit Address
> Designate the External Device's Bit Address. When the Bit Address designated here is turned ON, data stored in the backup SRAM is deleted. After the data is deleted, LT turns OFF the Bit Address. (Device/PLC to LT, LT to Device/PLC)

Loop

Selecting this feature means when data logging is completed, it will begin again from the top-most data address and overwrite the existing data.

■ Trigger settings with Loop operation

Trigger settings will differ depending on the type of Loop operation designated.

◆ **Bit Method**

Item (Trigger Settings)	Without Loop Operation	With Loop Operation
Data Logging Start Address	Designated by user	Designated by user
No. of Words	1 to 32 Words	1 to 32 Words
Read Count	1 to 2048 [*1]	1 to 2048
Block Count	1 to 2048 [*1]	1 (fixed)
Trigger Bit Address	Designated by user	Designated by user
LT_ACK Bit Address	Designated by user	Designated by user
File Full Bit Address	Designated by user	Designated by user
Data Clear Bit Address	Designated by user	Designated by user

*1. The maximum number of logging Words in all blocks is 2048.
   Number of blocks $\times$ frequency ≤ 2048

◆ **Time Method**

Item (Trigger Settings)	Without Loop Operation	With Loop Operation
Data Logging Start Address	Designated by user	Designated by user
No. of Words	1 to 32 Words	1 to 32 Words
Start Time	Hour/Min.	Hour/Min.
Finish Time	No Setting [*1]	No Setting [*1]
Duration	Hour/Min./Sec.	Hour/Min./Sec.
Read Count	1 to 2048 [*2]	1 to 2048 [*2]
Block Count	1 to 2048 [*2]	1 to 2048 [*2]
Data Logging Auth. Bit Address	Designated by user	Designated by user
Block's Finish Bit Address	Designated by user	No Setting
File Full Bit Address	Designated by user	Designated by user
Data Clear Bit Address	Designated by user	Designated by user

*1. The end time is automatically calculated using the time period and frequency.
*2. The maximum number of logging Words in all blocks is 2048.
   Number of blocks $\times$ frequency ≤ 2048
   When using loop operation, the number of blocks needs to be designated to decide the Logging area size.

> **Important**
>
> *The Device/PLC monitors bits at approximately 150 ms intervals. Therefore, a slight time delay may occur until the LT detects the Trigger, or the Data Clear Bit. Set these Bit change intervals to the length of communication cycle or to 150ms, whichever is longer.*

Note:

• **Each piece of data to be logged inside the record is only 16 Bits long. When the Device/PLC device uses 32 Bit length addresses, only the lower 16 Bits of data are logged.**

• **The LT's internal clock controls time using the last two digits of the year display. Therefore, the logging data's year is controlled by these digits.**

• **When the Start and End times are the same, or when the time interval is "0", data logging is performed once for each block.**

• **Data stored in the backup SRAM is cleared via the Data Clear Bit Address, when the Clear Bit changes from OFF to ON.**

• **When the LT's power is turned ON, if the Data Clear Bit Address's Bit has been turned ON, the LT deletes the backup SRAM logging data and turns OFF the Clear Bit.**

• **With loop operation and time setup designated, when Data Logging Auth. Bit Address is turned OFF or when the LT's power is turned OFF, after the logging period elapses loop operation becomes the same status as non-loop operation.**

(e.g.) Start time 09:00   End time 18:00   Time period 3 hrs.

If the 15:00 logging was skipped due to the LT's power being turned OFF:

<Without Loop Operation>   **<With Loop Operation>**

Block 1

09:00	Logging
12:00	Logging
15:00	Read Error
18:00	Logging

Logging at 09:00	
Logging at 12:00	
Read Error	(15:00)
Logging at 18:00	

Block 2

09:00	Logging
12:00	Logging

Data logging at 15:00 is stored as a read error.

Data logging at 15:00 is stored as a read error. (Same as without loop operation)

■ **Display**

Display (ON/OFF)

Click on this check box to display data using the Logging Display, or when saving data to a CF Card.

Row Settings

Display Block Name

Check this check box to display data together with its Block Name.

No. of Block Name Rows

Enter a value here to display block names in multiple rows. Up to 3 rows can be set up.

No. of Data Rows

Set up the number of rows in the data display area.

No. of Calc. Rows

Set up the number of rows in the calculation area. Up to 4 rows can be set up.

Column Settings

Display Block Name

Check this check box to display data together with its Block Name.

No. of Char./Item

Designate the maximum number of block name characters.

No. of Data Col.

Designate the number of data display columns in the data display area.

Data Char. Size

Designate the character size for each data in the data display area.

No. of Char. / Data

Designate the number of characters in the data display area.

Preview

The setting contents can be preview.

◆ **Maximum Number of Rows and Columns**

Up to 60 columns and up to 2100 rows of data can be entered. However, since the file capacity is approximately 58KB, depending on the No. of Block Name Rows and No. of Char./Name designated for the cells, these column and row limits will decrease.

<Row/Column Settings>

◆ **Row Setting When Using Loop Operation**

When the loop feature is used, regardless of the logging frequency, the data display will always be only one row.

The display row settings used during loop operation are as follows:

Data Display Row Only

Data Display (1 row)

Block Name Row + Data Display Row

Block Name
Data Display (1 row)

Data Display Row + Total Row

Data display (1 row)
Total Row(s) (1 to 4 rows)

Block Name Row + Data Display Row + Total Row

Block Name
Data Display Row (1 row)
Total Row(s) (1 to 4 rows)

E.g.

◆ **Row Setting Display When Using Loop Operation**

When using the loop feature, the Data Logging Display is as follows:

E.g.   When frequency is set to 4
Logging Data (Backup SRAM data)

Data Logging Display (Changes over Time)

Here, the oldest (acquired earliest) logging data is displayed in the top-most cell. When a single cycle of data logging is completed from beginning to end, data display rows will then shift upwards one row, every time data is logged.

When using the loop feature, the Total (Total, Average, Max., Min.) rows will disappear. However, these Total values will be the totals of backup SRAM data at that one pointing in time. Therefore, the new data that over-writes the old data will not be included in the Total values.

■Print

Print (ON/OFF)
> Click on this check box to print out the logging data.
> **Block Unit**
> Logging data is printed in block units. Printing is started via the Control Word Address.
> **Realtime**
> Logging data is printed out each time it is logged.

Copy from Display
> Click on this button, when the display format has already been set up, to use that format for printing.

Row Settings
> **No. of Data Rows**
> Designates the number of rows in the data print area.
> **No. of Calc. Rows**
> Designates the number of rows in the calculation area.

Column Settings
> **No. of Data Col.**
> Designates the number of rows in the data print area.

Header
> Click on this button to display the header edit window. Enter text on this window. The maximum text entry size is 160 characters for each row and the total of 40 rows.

Footer
> Click on this button to display the footer editing window. Enter text in the footer section. The maximum entry size is 160 characters for each row and the total of 40 rows.

Preview
> Click on this button to view the printing image of the data, header, and footer areas.

Control Word Address
> When data is printed out for each block, the printing starts with the Trigger Bit turned ON. This setting designates that Word Address.

Print Completed Bit Address

Designates the Bit Address to be turned ON at the end of printing, when data is printed out for each block. After confirming that this Bit Address is turned ON, perform the next printing.

Left Margin

Designates the left margin size to be used when printing out the data. The space for the number of the characters designated here is saved as a blank. This setting controls only the data print area.

Note:
- ▼*Reference*◢ For dialog printing settings, refer to *9.1 Print Settings.*
- ▼*Reference*◢ For hardware printing settings, refer to *LT Series User's Manual.*
- **When using loop operation and performing real time printing, the Total section will not be printed.**
- **When using loop operation to perform real time printing, if the logging frequency is not very high or a printer has not yet been connected, printing cannot be performed at the speed the logging data is created, thereby causing a difference between the two. Please note that the first cycle's logging data will not be printed out when data logging is performed to the end of a loop cycle and then repeats from the beginning, overwriting the existing data.**

■ **Write to LS**

Write Settings (When Writing to LS Area)

Stores logging data in the LS area. Displays logging data items in combination with Keypad Display.

Perform Data Write (On/Off)

Although all logging data can be displayed at a single time via the display settings, using the LS Area allows each piece of logging data to be displayed separately, together with Keypad Display. Click on this check box to use this setting.

Control Word Address

Designate a Word Address that is the trigger or mode change for writing data to the LS Area. This Trigger Bit is turned ON or OFF by the Device/PLC. When writing backup SRAM logging data to the LS area, logging data transfer is performed by designating a Block No. (when using loop operation, set to "0") and turning the Trigger Bit OFF and then ON.

Write to LS Address

Designates the LS Area Address where data is written to.

Write Complete Bit Address

Designates the Bit Address that will be turned ON when data write to the LS Area is completed. After turning the Bit Address ON is detected, use the Device/PLC to turn it OFF. When there is no designated Block No., the Perform Data Write Bit Address is not turned ON.

Write Settings (Total)

Writes each column's total value for each block to the LS area. The Total value is written to the LS area via the Control Word Address, according to the Logging Settings' Display Settings.

Perform Data Write (On/Off)

Designates whether or not the Total value is written to the LS area.

Control Word Address

When writing the Total value to the LS area, transfers the Total value data to the LS area by designating a Block No. and turning the Trigger Bit OFF and then ON.

Write to LS Address

Designates the LS Area Address used when writing data.

Write Complete Bit Address

Designates a Bit Address to be turned ON when data write into the LS Area is completed. After the Bit Address ON condition is detected, turn it OFF via the Device/PLC. When there is no designated Block No., the Perform Data Write Bit Address is not turned ON.

◆ **Data to be Written to LS Area**

Block and data structures to be transmitted to the LS Area are as follows:

Block

Logging data 1	
Logging data 2	
:	
:	
Logging data n	

Logging data

15   0

+0	Code	Flag
+1		Year
+2	Month	Day
+3	Hour	Minute
+4		Second
+5	Data Enabled/Disabled Bit	
+6	Data Enabled/Disabled Bit	
+7	Word data 1	
+8	Word data 2	
	:	
	:	
+(n+6)	Word Data n	

*See below.

Stored last two digits using the BCD format.

* See below
* See below

15   ·   8 7   ·   0

+0	Code	Flag

Read flag
0: Data read incomplete
1: Data read completed

Read Error Code
0: Normal finish
1: Read error

Word Data Enabled/Disabled Bit

15   0

	16	15	14	13	12	11	10	9	8	7	6	5	4	3	2	1
+5	16	15	14	13	12	11	10	9	8	7	6	5	4	3	2	1
+6	32	31	30	29	28	27	26	25	24	23	22	21	20	19	18	17

Each Bit in a Word represents a data number.
When a Bit is "0" the Bit is Disabled. When a Bit is "1" the Bit is Enabled.

When using loop operation, logging data is transferred starting with the oldest piece of data.

Logging Data Process (in Backup SRAM)

Here, (1) to (6) represent logging data.

(1)
(2)
(3)

In this case, logging data is written to the LS area in the order of (1), (2), and (3).

(5)
(6)
(3)
(4)

When using the Loop feature, logging data is written in the order of (3), (4), (5), and (6).

If a data block's size exceeds the LS Area size, that data block cannot be transmitted.

◆ **Display Setting Example for Writing to LS Area**

The following is an example of the display settings used when writing each logging data column's total value data to the LS area. (block units)

<Total Value Data and Average Value Data Display>

When using the above display settings, the Total value data will be written to the LS area as follows. The Total values (Total, Average, Max., and Min.) are all written as 32 bit data. Also, the Total values will be written from the left column. All values (except Data and Item) will be automatically shifted to the left in a column.

Note: **If the size of the Total value data exceeds the LS Area size, that data cannot be transmitted.**

10.2.4   Display Settings

■ **Display Settings**

In the [Display Settings] dialog box, the settings made in the [Display] tab can be viewed and edited.

Display Setting dialog box

Note: **When using loop operation, regardless of the logging frequency, the data display row will be designated as only a single row.**

◆ **Settings**

Rows and columns can be selected to change their attributes.

◆ **Add**

Select a Data row or Value column and click on the [Add] button, to create a new row or column.

◆ **Copy**

Copies the currently selected Data row(s) or Value column(s)' data is copied to the Clipboard.

◆ **Paste**

Pastes data row or Value column data copied to the Clipboard with the [Copy] button in the desired position.

◆ **Cut**

Deletes the currently selected Data row(s) or Value column(s).

■ **When copying row or column data with the same attribute multiple times:**

1. Designate the No. of Block Data and No. of Char./Col.

2. Set the attributes for a row or column to create the original data for copying.

3. Select that row or column.

4. Click on the [Copy] button.

5. Select the destination row or column to paste the copied data to. When copying multiple times, select multiple rows or columns.

6. Click on the [Paste] button to paste the same attribute to all the selected rows/columns.

1) Item Name Settings (Display)

■ **Enter Item Names**

Enter the Item Names for each cell.

■ **Attribute Settings**

To change the Item Name attributes, select the Item Name title area and click on the [Settings] button.

◆ **General Info.**

This tab page provides information about the current settings for the Item Name.

◆ **Color**

Block Name Color

Select the desired colors for Fg (fore-ground), Bg (background), and Blk (blink) display.

2) Column Settings (Display)

■ Attribute Settings

To enter column attribute data, click on a Date/Time or Value title (top bar) and then click on the [Settings] button.

◆ **General Info. [Column Type : Date/Time]**

This tab page provides information about the current Column settings.

Column Type

Select the desired display item from Value, Date/Time, or Char.Col.

◆ **Data Format**

Date

Displays the date.

Time

Displays the time.

Display Format

Select the desired time/date display format.

Note: **There are two types of settings in the Date/Time settings, i.e. date settings and time settings. Time is expressed only by the 24 hour system.**

- **For date:**
  mm/dd/yy
  mm/dd
  yy/mm/dd
  dd/mm/yy
- **For time:**
  hh:mm
  hh:mm:ss

◆ **General Info. [Column Type : Value]**

Value
Selecting this option displays actual logging data in the Display Settings area.

◆ **Data Format (Absolute)**

Absolute
Displays Logging Address area Address data.
Address Offset
The Logging Address is changed by the offset value entered here. For example, when the number of logging words is 4, the offset value becomes 0 to 3.
Display Data Format
Select the desired data format from Dec, Hex, and BCD.
Code +/-
Check this check box when displaying negative values. Only available when selecting the Dec data format.

◆ **Data Format (Relative)**

Relative

Data stored in the Address entered in the Logging Address area is converted according to the Input Range area's values and the converted data values are displayed.

Address Offset

The Logging Address is changed by the offset value entered here. For example, when the number of logging words is 4, the offset value becomes 0 to 3.

Bit Length (1-16)

Enter the Enabled Bit length of data to be stored in the Logging Address.

Input Code

No Code

Displays positive values only.

+/-2's Complement

Uses 2's complement to express negative values.

Code +/-

Check this check box when displaying negative values. Only available when selecting the Dec data format.

Round Up

The decimal point numbers created during relative value range conversion will be rounded up or off. When this option is not selected, those numbers will be rounded off.

Input Range

Min. Value

Max. Value

Designates the range of values stored in the Logging Address. The possible ranges vary depending on the Input Code Format.

Display Range

Min. Value

Max. Value

Designates the range of values displayed in the N-tag. The possible ranges vary depending on the Display Format and Code +/- settings.

◆ **Size/Style**

Display Format

No. of Display Digits

Designates the number of digits for the display within the range of characters designated in the Display tab, usually as 1 to 16 digits. The length designated here includes digits after the decimal point, but not the decimal point itself.

Decimal Places

Designates the number of digits displayed after the decimal point, usually as 0 to 14 digits. This setting is valid only for Dec and BCD formats. Enter "0" when not displaying decimal place numbers.

Color Settings

Select the desired colors for Fg (foreground), Bg (background), and Blk (blink). When the Alarm option is selected, the color attributes designated here are used for normal display.

Display Style

Shift Left

Shift Right

Select the display style from the Shift Left and Shift Right. The data will appear, starting from the side designated here. Shift Left has been selected as the default setting.

Zero Suppress

Check this check box to omit the leading zeros of display data. (e.g) When the Display Length is 4 and the Zero Suppress is NOT selected, "25" appears as 0025.

Input Style

Auto Clear OFF

In this mode, the previously entered values are not cleared and newly entered values are added to those values. To clear the previously entered values, press "CLR" of the touch keyboard.

Auto Clear ON

When the first character of a value is entered (excluding moving the cursor, entering ENT, DEL, and BS), the previously entered value is cleared.

> **Note:** Date/Time and Value data, except for the text characters, are centered. Also, a 2 dot space is automatically inserted in the upper, lower, left and right sides.

2 dots ← ... → Cell

5 dots

For example, when the number of characters are 7 and the number of numeric value's digits are 5 in a cell, space for one character is saved on both left and right sides and displayed data is centered.

◆ **Alarm Settings**

Alarm Display (On/Off)
Select this check box to display the Alarm display.

Alarm Range
Min. Value
Max. Value
When the Alarm Type is set to Direct, designate the Alarm Range. When selecting Relative value display, the Display Range designated in the Data Format tab is used as normal display's Min. and Max Values automatically. The possible Alarm ranges varies depending on the Data Format selected.

Alarm Color
If the data exceeds the Alarm Range, the Alarm display appears in the designated colors.

<Alarm Range List>

Data Format		Code+/-	Alarm Range
16Bit	Dec	+/-	-32768 to 32767
		+	0 to 65535
	Hex		0 to FFFF(h)
	BCD		0 to 9999

◆ **Size/Style**

Color Settings
Select the desired colors for Fg (foreground), Bg (background), and Blk (blink).

◆ **General Info. [Column Type : Char. Col]**

Char.Col
Displays text.

3) Row Settings (Display)

■ **Attribute Settings**

Select either Item Name or Data row, and click on the [Settings] button to edit each row's attributes.

◆ **General Info. [Selecting Item Name Row]**

The General Info. page provides information about the current settings for Item Name Settings.

◆ **Color**

Color Settings

> Select the desired colors for Fg (fore-ground), Bg (background), and Blk (blink).

Note: **The row color settings have priority over the column color settings.**

◆ **General Info. [Selecting Data Row]**

The General Info. page provides information about the current settings for Data settings.

Row Type

> Select the desired type of display from the Data and Char.Col. settings.

4) Totals (Display)

■ Attribute Settings

To set up the calculation attributes, select the Totals cell and click on the [Settings] button.

◆ General Info.

The General Info. page provides information about the current settings for Totals Settings.

Data Calculation Settings

Select the desired calculation item from Total, Average, Maximum, and Minimum. The calculation attributes can be set up for the entire Data row or Value column. At this time, the applicable column's attribute is Date/Time or Char.Col., and the Data Calculation Settings cannot be designated. Data calculation is performed via the 32 Bit format.

◆ Size/Style

Display Format

No. of Display Digits

Enter the number of display digits. The numbers displayed after the decimal point is also included. (However, the decimal point is not included itself.) Enter a value in a range from 1 to 16.

Decimal Places

Enter the number of digits after the decimal point in a range from 0 to 14. This setting is Enabled only when the Data Format is designated as Dec or BCD. If the values after the decimal point are not displayed, enter "0".

Color Settings

Select the desired colors for Fg (foreground), Bg (background), and Blk (blink). When the Alarm option is selected, the color attributes designated here are used for normal display.

Display Style
Shift Left
Shift Right
Select either shift type. Data is displayed from the selected position. The default setting is Shift Left.
Zero Suppress
When 0 suppression check box is checked, all unnecessary 0s are not displayed. When this check is removed, 0s are added to the front of numbers to match the display length designated in the No. of Display Digits area. (e.g. When the No. of Display Digits is 4 and 0 suppression is OFF, value 25 appears as "0025".)

■ Display Settings Maximum File Size

The display settings' file size capacity is approximately 58KB. However, depending on the specific setting combination, the user's file size may exceed this capacity. The following example is the standard display setting size.

• Enter the Block Name in the 1st column and then up to 8 single-byte characters in each column.

• Enter the Block Name in the 1st row and then up to 8 single-byte characters in each row.

• Four rows are available for totals. (Total, Average, Max., Min.)

No. of value columns

	Block Name	Date	Time	Value	Value	------	Value
Block Name		ABCDEFGH	ABCDEFGH	ABCDEFGH	ABCDEFGH		ABCDEFGH
Data display	ABCDEFGH						
Data display	ABCDEFGH						
Data display	ABCDEFGH						
Data display	ABCDEFGH						
Total (Total)	ABCDEFGH						
Total (Average)	ABCDEFGH						
Total (Max.)	ABCDEFGH						
Total (Min.)	ABCDEFGH						

No. of data display rows

When using the pattern shown above, the maximum number of value columns and data display rows are as follows:

No. of Value Columns	No. of Data Display Rows	Remarks
32	1007	When the No. of value columns (number of logging words) is the maximum (32 columns).
16	1116	When the No. of value columns (number of logging words) is the maximum (16 columns).
8	1170	When the No. of value columns (number of logging words) is the maximum (8 columns).
4	1197	When the No. of value columns (number of logging words) is the maximum (4 columns).

⚠ Important *When designating the columns as the block name display and entering characters in each column, the file size will become extremely large. Depending on the number of characters entered and other items designated, approximately 1000 rows can be used for the pattern shown above.*

10.2.5 Print Settings

In this dialog box, the current Print Settings applied in the Print screen can be viewed and edited.

▼*Reference*◣ For hardware printing settings, refer to *LT Series User's Manual*.

Print Settings dialog box

When using the Loop, regardless of the logging frequency, the data display row will be designated as a single row.

◆**Settings**

To change row/column attributes, select the desired row or column and click on the Edit button.

◆**Add**

Select a row or column and click on the Add button, then one row or column is added.

◆**Copy**

Copies the currently selected row or column data to the Clipboard.

◆**Paste**

Pastes the copied row or column data to the desired position.

◆**Cut**

Deletes the currently selected row(s) or column(s) are deleted.

1) Column Settings (Print)

■ Attribute Settings

To set up column attributes, select either a Ruled Line, the Date/Time, or a String(Char.Col.), and click on the Settings button.

◆General Info.

The General Info. page provides information about the current Column Settings in use.

Column Type

Select the desired display item from Value, Date/Time, Char.Col. or Border.

◆General Info. [Column Type : Value]

Value

When this option is selected, numeric data is printed out.

◆Data Format

Absolute

Data stored in the Address displayed in the Logging Address area is directly printed out. This data is handled as an absolute value.

Address Offset

The Logging Address is changed by the offset value entered here. For example, when the number of logging words is 4, the offset value becomes 0 to 3.

Display Data Format
Select the desired data format from Dec, Hex and BCD.
Code +/-
Check this check box when printing negative values. Only available when selecting the Dec data format.

Relative
Data stored in the Address entered in the Logging Address area is converted according to the Input Range area's values and the converted numeric data is printed out.
Address Offset
The Logging Address is changed by the offset value entered here. For example, when the number of logging words is 4, the offset value becomes from 0 to 3.
Bit Length
Enter the Enabled Bit length of data to be stored in the Logging Address.
Input Code Format
No Code
Displays positive values only.
+/-2's Complement
Uses 2's complement to express negative values.
Code +/-
Check this check box when displaying negative values. Only available when selecting the Dec data format.
Round Up
Round up displaying or printing values.
Input Range
Min. Value
Max. Value
Designate the range of values stored in the Logging Address. The possible ranges vary depending on the Input Code Format settings.

Display Range
  Min. Value
  Max. Value
  Designate the range of values displayed in the N-tag. The possible ranges vary depending on the Display Format and Code +/- settings.

◆**Size/Style**

Display Format
  No. of Display Digits
  Designate the number of digits for the display within the range of characters designated in the Display Setting area, usually 1 to 14 digits. The length designated here includes digits after the decimal point, but not the decimal point itself.
  No.of display digits=1~((No. of data char.)-(Code+/-)-(Decimal places))
  Decimal Places
  Designates the number of digits displayed after the decimal point usually as 0 to 16. This setting is valid only for Dec and BCD formats. You can designate the value from 0 to 16. Enter "0" when not displaying decimal place numbers.
  Decimal Places=0~(No.of display digits-1)
  No. of Char./Col.
  Designates the cell size. Enter a value in a range from 1 to 32 (digits).
Display Style
  Shift Right
  Shift Left
  Select either shift type. Data is displayed from the selected position. The default setting is Shift Left.
  Zero Suppress
  When 0 suppression check box is checked, all unnecessary 0s are not displayed. When this check is removed, 0s are added to the front of numbers to match the Display Length. (e.g. When the No. of Display Digits is 4 and 0 suppression is OFF, value 25 appears as "0025".)

Note: Date/Time and Value data, except for text data, is printed in the middle of a cell. When the center point cannot be designated due to the number of characters, text is shifted to right for one character. When designating Char. Col. for Column Type, data is printed being shifted left.

◆**General Info. [Column Type : Date/Time]**

Date/Time
Prints out Time and Date data.

◆**Data Format**

Date
Prints out date data.
Time
Prints out time data.
Display Format
Select the desired time/date display format.

Note: Date/Time settings have two settings, i.e. Date settings and Time settings. Time data is printed out only via the 24 hour system.
• For date:
  mm/dd/yy
  mm/dd
  yy/mm/dd
  dd/mm/yy
• For time:
  hh:mm
  hh:mm:ss

◆**Size/Style**

No. of Char./Col.
Designates the cell size. Enter a value from 5 to 16 (digits).

◆**General Info. [Column Type : Char. Col.]**

Char. Col.
Prints out the text.

◆**Size/Style**

No. of Char./Col.
Designates the cell size. Enter a value from 5 to 16 (digits).

◆**General Info. [Column Type : Border]**

Border
Prints out the borders.

2) Row Settings (Print)

■ Attribute Settings

To set up row attributes, select Border, String (Char. Col.), Data (Value), or Total, and click on the Settings button.

Print Settings

	orde	Char. Col.	orde	Date/Time	orde	Valu
Border	+	--------	+	--------	+	--------
Char. Col.	|		|		|	
Border	+	--------	+	--------	+	--------
Data	|		|	yy/mm/dd	|	*****
Border	+	--------	+	--------	+	--------

◆**General Info.**

Row Settings

General Info.

Row Number   1

Row Type   ○ Data   ○ Char. Col.   ◉ Border

[OK] [Cancel] [Help]

The General Info. page provides information about the current settings for Row Settings.

Row Type

Select the desired print item from Data, Char. Col., and Border.

Note:
• **With the real-time printing, if the Loop is not used, the header is also printed when the first item of logging data is printed. When the last item of logging data is printed, the footer and total value(s) are printed.**

• **With both real-time and block printing, when the Loop is not used, after the last item of logging data is printed, page feed is performed.**

• **The maximum number of columns is 60 and the maximum number of rows is 4200. However, since the setting data file capacity is approximately 58KB (maximum), the number of rows will depend on the No. of Char. Col. to be designated for the number of borders and cells.**

60 columns

4200 rows

Note: • **If the Windows system's font setting is either Korean (Hangul), Taiwanese or Chinese, image data is printed out.**

• **Regardless of the printer's color settings, all data is printed in black and white.**

• **Alarm printing and screen hard copy commands are accepted even during real-time printing. Therefore, during real-time printing, DO NOT enter other printing commands.**

• **While multiple lines of data are being printed, if logging data is cleared, data printing is interrupted. Also, if the LT's power is turned OFF during printing, the remaining data will not be printed out even if the LT's power is turned ON again.**

• **The printing format consists of the three areas, i.e. header, main data, and footer. Up to 160 characters can be printed per line.**

Header

Data

Footer

Note: **The following is an example of logging data printout. (The Loop is not used.)**

```
                               +------+------+------+
                               | Appr. | Check | Create |
                               +------+------+------+
                               |      |      |      |
                               |      |      |      |
                               |      |      |      |
                               +------+------+------+



         +--------+--------+--------+--------+--------+
         |  TIME  | VOLTAGE|  TEMP 1 |  TEMP 2 |PRESSURE|
         +--------+--------+--------+--------+--------+
         |  09:00 |  3228  |  30.3  |  25.3  |   6.1  |
         |  10:00 |  3236  |  26.4  |  26.4  |   6.4  |
         |  11:00 |  3244  |  28.6  |  27.6  |   6.2  |
         |  12:00 |  3202  |  30.7  |  28.7  |   6.5  |
         |  13:00 |  3210  |  26.9  |  29.9  |   6.3  |
         |  14:00 |  3219  |  29.2  |  24.0  |   6.0  |
         |  15:00 |  3227  |  31.1  |  25.1  |   6.3  |
         |  16:00 |  3235  |  27.3  |  26.3  |   6.1  |
         |  17:00 |  3243  |  29.4  |  27.4  |   6.4  |
         +--------+--------+--------+--------+--------+
         | TOTAL  | 29044  | 259.7  | 240.7  |  56.3  |
         | AVERAGE|  3227  |  28.9  |  26.7  |   6.3  |
         | MAX.   |  3244  |  31.1  |  29.9  |   6.5  |
         | MIN.   |  3202  |  26.4  |  24.0  |   6.0  |
         +--------+--------+--------+--------+--------+
```

When using the Loop, regardless of the logging frequency, the data display row will be designated as a single row. Also, Char. Col., Border and Total sections cannot be set.

```
Print Settings
  [ Settings ]    [ Add ] [ Copy ] [ Paste ] [ Cut ]
            Char. Col. Date/Time Char. Col.  Value  Char. Col.  Value  Char. Col.
   Data                yy/mm/dd              *****              *****
```

<Real Time Printing - using Loop>

```
| 10:00 | XXXX | XX.X | XX.X | X.X |
| 11:00 | XXXX | XX.X | XX.X | X.X |
| 12:00 | XXXX | XX.X | XX.X | X.X |
| 13:00 | XXXX | XX.X | XX.X | X.X |
| 14:00 | XXXX | XX.X | XX.X | X.X |
| 15:00 | XXXX | XX.X | XX.X | X.X |
| 16:00 | XXXX | XX.X | XX.X | X.X |
| 17:00 | XXXX | XX.X | XX.X | X.X |
| 10:00 | XXXX | XX.X | XX.X | X.X |
| 11:00 | XXXX | XX.X | XX.X | X.X |
| 12:00 | XXXX | XX.X | XX.X | X.X |
| 13:00 | XXXX | XX.X | XX.X | X.X |
```

Prints the data display rows only when data logging is performed. The header, footer and other items will not be printed.

Note: **With real time printing, when using the Loop, the data display row will be designated as a single row.**

Important

• *When using the Loop, only real time printing can be used.*

• *When using the Loop and performing real time printing, the Total section will not be printed.*

• *When using Loop and performing real time printing, if the logging frequency is not very high or a printer has not yet been connected, printing cannot be performed at the speed the logging data is created, thereby causing a difference between the two. In this case, only part of a single cycle's logging data will not be printed.*

■ **Print Settings Maximum File Size**

The print settings' file size capacity is limited. Therefore, depending on the specific setting, the user's file size may exceed this capacity. (The setting file contains the print header, print footer and print data areas' settings.) The maximum number of characters that can be entered per row is 160. The following is the standard print setting size.

- Enter the Block Name in the 1st column and then up to 8 single-byte characters in each column.
- Enter the Block Name in the 2nd row and then up to 8 single-byte characters in each row.
- Four rows are available for totals (Total, Average, Max., Min.)

No. of value columns

	Char. Col.	Date	Time	Value	Value	~	Value
Border	- - - - - - - -	- - - - - - - -	- - - - - - - -	- - - - - - - -	- - - - - - - -		- - - - - - - -
Char. Col.		ABCDEFGH	ABCDEFGH	ABCDEFGH	ABCDEFGH		ABCDEFGH
Border	- - - - - - - -	- - - - - - - -	- - - - - - - -	- - - - - - - -	- - - - - - - -		- - - - - - - -
Data display	ABCDEFGH						
Data display	ABCDEFGH						
Data display	ABCDEFGH						
⋮							
Data display	ABCDEFGH						
Border	- - - - - - - -	- - - - - - - -	- - - - - - - -	- - - - - - - -	- - - - - - - -		- - - - - - - -
Total (Total)	ABCDEFGH						
Total (Average)	ABCDEFGH						
Total (Max.)	ABCDEFGH						
Total (Min.)	ABCDEFGH						
Border	- - - - - - - -	- - - - - - - -	- - - - - - - -	- - - - - - - -	- - - - - - - -	- - - - - - - -	- - - - - - - -

No. of data display rows (bracket spanning the Data display rows)

When using the pattern shown above, the maximum number of value columns and data display rows are as follows:

No. of Value Columns	No. of Data Display Rows	Remarks
17	282	The maximum number of characters that can be entered per row is 160. Therefore, when 8 characters are entered for each column, the number of value columns available will be 17.
16	295	When the No. of value columns (number of logging words) is the maximum (16 columns).
8	482	When the No. of value columns (number of logging words) is the maximum (8 columns).
4	683	When the No. of value columns (number of logging words) is the maximum (4 columns).

⚠ *Important* ***When designating the columns as the block name display and entering characters in each column, the file size will become extremely large. Depending on the number of characters entered and other items designated, several hundreds rows can be used for the pattern shown above.***

APPENDICES

This section contains a list of error messages and corrective actions, as well as address conversion tables.

A.1   Error Messages

■ Project Manager Errors

This section describes error messages that will be displayed during operation of the LT Editor and how to solve these problems. If malfunction still occurs after the measure is taken, describe the problem in the attached Software Trouble Report and send it to us by facsimile.

		Error Message	Cause/Solution
B		Because of the change in PLC type, a part of the device address used in the project may be converted into a device address that cannot be used with the current PLC. Double-check all device addresses used in the project and modify them as required.	This warning message is displayed every time an attempt is made to change the Device/PLC type and addresses. Double-check all device addresses used in the project and modify as necessary.
C		Can't edit - Insufficient memory	The memory area for editing is insufficient. Quit other applications, then begin editing your file again.
		Cannot edit the files because the filing mode [Use Multiple Folders] setting is not selected! Click on [Use Multiple Folders].	When the filing mode settings ' [Use Multiple Folders] was not selected, you attempted to open 2 or more kinds of filing data directly from the Project Manager having nesting screen display by double-clicking. Select [Use Multiple Folders].
		Cannot start up Internet browser	The browser settings are not correct or the memory area for the browser is insufficient. Check the settings of the startup browser. If the browser settings are correct, quit all other applications and restart the browser.
		Cannot read system file	The program file data required for setup cannot be opened or read, or the file's data is not correct. The file may be corrupt, or a disk error may have occurred. After solving the problem, reinstall the file.
		Cannot read the file's system information	The project file is corrupt. Use LT Editor ' s rebuilding tool to repair the file. After repair is completed, read the file again.
		Current Color Depth Not Supported Convert to 256 colors or less	Only bit maps of 256 colors or less can be used by this software.
D		Destination screen number is too high. Reduce the number of destination or source screens	Set (Copy source end number - copy source start number) >= (8999 - copy destination start number).
E		Exceeds Data Backup Area Limit. Please adjust your settings to fit this area's size limitations	The backup settings, backup area used cannot exceed 2031. Set (Backup start address + the number of devices) to less than or equal to 2031.
		External Device File Type Error	The External Device table file format is not the same as the LT's, or the file is corrupt. Select an External Device from the master disk and reinstall the file.
G		Grouping Nesting Limit Reached. Unable to group more than these objects	You are attempting to nest grouped objects more than 10 times. Only 10 levels of nesting are allowed.

	Error Message	Cause/Solution
I	**Internet Browser Not Selected Yet.** **Please select a Browser**	An Internet browser has not been selected yet. After clicking on the error message's OK button, select a browser from the dialog box that appears.
	Invalid Address !	Before entering the device address, check that the value is within the allowable range and that the device is supported by the External Device.
	Invalid External Device table	The External Device table file format is not the same as the LT's, or the file is corrupt for some reason. Select an External Device from the master disk and reinstall the file.
	Incorrect External Device Table Format	The External Device table file format is not the same as the LT's, or the file is corrupt for some reason. Select an External Device from the master disk and reinstall the file.
N	**Non-LTE File**	A file has been selected that is not recognized by LT Editor for Windows 95. Be sure to select only Project (.lte) files.
O	**Old External Device table and some functions may not work properly.** **Please use latest table**	The External Device table file from an old version is being used. Select a new External Device from the master disk and reinstall it.
S	**Screen number to copy from must be greater than screen number to copy to.**	Enter a "copy to" screen number that is greater than the "copy from" screen number.
	Selected project is the same as current project.	You cannot copy data within the same project file. Be sure to specify a project file other than the current project file.
	Specified address is not used for screen properties that can be displayed.	When opening the screen via the Global Cross Reference List, designate an address within the valid range of screen addresses.
	System error	The program file data required for setup cannot be opened and read, or the file's data is not correct. The file may be corrupt, or a disk error may have occurred. After solving the problem, reinstall the file.
	System file is corrupt	The program file data required for setup cannot be opened and read, or the file's data is not correct. The file may be corrupt, or a disk error may have occurred. After solving the problem, reinstall the file.
	System open error	The program file data required for setup cannot be opened and read, or the file's data is not correct. The file may be corrupt, or a disk error may have occurred. After solving the problem, reinstall the file.
	System write error	The program file data required for setup cannot be opened and read, or the file's data is not correct. The file may be corrupt, or a disk error may have occurred. After solving the problem, reinstall the file.

	Error Message	Cause/Solution
U	Unable to convert file. Please check disk.	The destination disk does not have sufficient free space. Prepare a disk that has sufficient space and re-try.
	Unable to read current project information	The project file is corrupt. Use the LT Editor rebuilding tool to repair the file, and then read the file again.
	Unrecognizable Bitmap File may be corrupted	The selected bit map file is either corrupted or unusable by this software.

■ Screen Editor Errors

	Error Message	Cause/Solution
C	Can't edit - Insufficient memory	The memory area is insufficient for editing. Quit all other applications and resume editing.
	Can't open more than 20 screens	The screen editor can have up to 20 screens open at one time.
	Cannot place screen on itself	You cannot call the screen being edited.
	Change request will exceed maximum number of Parts. Changes canceled	This change will exceed the Parts upper limit.
	Current Color Depth Not Supported. Convert to 256 colors or less	Only bit maps created with 256 colors or less can be used in this system.
D	Device address out of range	When the specified command is performed, the device address exceeds the upper limit. Specify an address within the allowable range.
E	Exceeded maximum screen size. Changes canceled	This change will exceed the screen size upper limit. ▽*Reference*△ 1.5 Screen Editor
	Exceeds alarm limit	Only one alarm can be used on a single screen.
	Exceeds keypad limit	Only one keypad screen can be called to a Base screen.
	Exceeds time display limit	Only one time display can be used on a single screen.
	Exceeds screen size limit	The screen size exceeds the upper limit, and you cannot create any more graphic data. The last data created will become invalid. Store the screen data, and then open a new screen and call the stored screen using [Load Screen] in the [Draw] menu.
	Exceeds Part Library limit.	If the number of Part Libraries used exceeds the limit, Part Library data cannot be transferred to the LT. Reduce the number of Part Libraries. ▽*Reference*△ 2.1 Parts ■ Maximum Number of Automatically Created Part Libraries
F	Filing displays with the same ID No. cannot be placed on a screen if [Cursor Position Control] is selected.	Multiple filing displays with the same ID No. with [Cursor Position Control] selected cannot be placed on one screen. Either deselect [Cursor Position Control] or change each filing display' ID No. so that the ID Nos. do not overlap.

■ **Screen Editor Errors (from previous page)**

	Error Message	Cause/Solution
G	Grouping Nesting Limit Reached. Unable to group more than these objects	You are attempting to nest grouped objects more than 10 times. Only 10 levels of nesting are allowed.
I	Invalid Screen (Number)	The effective screen number is within the range from 1 to 8999. Re-enter the screen number.
L	Logging Display and Keypad Input Display cannot be placed on a screen simultaneously.	Check whether a Logging display or Keypad Input Display has already been placed on the screen.
P	Parts are not valid objects.	A library item containing Parts cannot be used in a Picture Display.
S	Screen No. is out of range. Re-enter a different Screen No.	Screen No. used after conversion is out of the Screen No. range. Enter the correct number.
	File write error	This file cannot be written to the destination media. Please check the designated drive name and directory.
T	The sum total of all the data saved by the LT's data backup features now exceeds the backup memory unit's limit. Please reduce this amount.	The backup size exceeds the SRAM capacity. Reduce the number of sampling data, or set this item's backup setting to "None".
	The area available for data sampling has been exceeded. Please re-enter this item's settings.	The storage address used exceeds 2031. Set (Storage start address + the number of sampling data) to less than or equal to 2031.
	The amount entered for the data sampling feature is combined with the number of Trend graph channels created, and their combined total cannot exceed 20.	When 20 channels are preset, the Add button is clicked in the data sampling setting list display dialog box. Delete unnecessary settings so that the total of Trend Graph channel settings and the data sampling settings will be within 20.
	There are no screens created for this screen type.	The screen that you attempt to open cannot be created with the specified screen type. Open a new screen.
	The designated screen does not exist.	The screen that you attempted to open cannot be found in this project. Select a screen from different existing project.
	This object has a non-black background and may not display properly on the LT. Also, be sure that your loaded screen's center point is aligned with the object (loaded to) screen's center point.	If this screen is used as the screen for the background color, be sure to align its center point correctly with the destination screen.
U	Unrecognizable Bitmap File may be corrupted	The selected bit map file is either corrupted or unusable by this software.

■ Library Item Placement / Save Errors

		Error Message	Cause/Solution
G		Grouping Nesting Limit Reached. Unable to group more than these objects	You are attempting to nest grouped objects more than 10 times. Only 10 levels of nesting are allowed.
N		Not a library file	The library file selected in the library browser cannot be used in this system. Select a file with a CPW extension.
O		Out of memory	Memory is not sufficient to execute the operation. Quit other applications, re-allocate memory, and then restart the operation.
S		System error	An error occurs when the library file is being stored. Reserve sufficient free disk space and restart the operation.
U		Unable to convert memory block into cell	The memory is not sufficient to execute the operation. Quit other applications, re-allocate memory, and then restart the operation.
		Unable to create cell list	The library file is corrupt for some reason. Use the provided rebuilding tool to repair the file and then restart the list creation.

■ D-Script Errors

		Error Message	Cause/Solution
C		Constant value out of range:	The preset constant value exceeds the specified range. Enter a correct value.∗
D		D-Script function name has not been entered. Please type the function's name in the description field.	Do not click OK without entering the function name; you must first specify the function name. Enter the function name.
E		Expression too complex. See HELP screens for assistance.	Simplify the D-Script expression.
I		if ' expression requires a non-empty statement	An expression is required in { } in the if clause. If no expression is specified, the if clause is ignored.∗
		Illegal Expression	The entered expression contains an error and will not be recognized.∗
		Illegal syntax	The entered D-Script expression has a syntax error.
		Illegal address	The entered address setting contains an error. Enable the syntax help in the option setting menu and enter the address by clicking the icon, or enter it from the keypad.
N		Negative numbers not supported - select correct data type	A negative number cannot be used as a constant. Enter a positive number.∗
T		This script expression is not legal (it will not download). Do you still want to register this data and quit the D-Script editor?	The preset D-Script expression has an error. Even if this script is registered, the operation will be not performed.
W		WARNING: Statement has no effect and has been removed	The entered instruction is ignored because it will not influence the expression.

∗ These messages are displayed only when the syntax check in the option setting menu is selected.

■ Alarm Editor Errors

		Error Message	Cause/Solution
C		Can't Add Messages - Insufficient memory	Memory is not sufficient to add the messages. Quit other applications, re-allocate memory and try to add the messages again.
		Can't import more alarm message/summary. Alarm message/summary limit has been reached.	During message import, the number of alarm message/summary has exceeded the designated limit. Delete the messages currently set and adjust the setting range so that the messages to be imported can be stored.
D		Data in Blocks 2 and 3 cannot be uploaded to the LT.	Since the "Block" feature was turned OFF when this data was downloaded, please delete Blocks 2 and 3.
L		Low Memory - not all messages can be pasted!	Memory is not sufficient to paste all the messages. Quit other applications, re-allocate memory and paste the messages again.
		Low Memory - not all alarms were copied! Try copying a smaller group.	Memory is not sufficient to paste all the messages. Quit other applications, re-allocate memory and paste the messages again.
N		Not enough memory to perform undo! Do you want to continue?	Memory is not sufficient to undo the messages. The deleted message(s) cannot be undone (restored).
		Not all alarms were saved. Insufficient disk space	Disk capacity is not enough to store the data. Create more free disk space and store the data again.
		Not all alarms were read. Insufficient memory	Memory is not sufficient to read the alarm messages. Quit other applications, create more memory and read in the alarms again.
S		Some data is incorrect and all data cannot be imported.	The format of CSV data to be imported is incorrect. Data in and below the line with the incorrect data will not be imported. Check Alarm data's CSV format.

■ Symbol Editor Errors

	Error Message	Cause/Solution
A	Addresses cannot be used as symbol names!	Enter a standard address in the address column.
D	Disk space is insufficient.	The disk in which the data is stored has no free space. Create more free space and try again.
T	This Symbol Name is already in use. Please choose another name.	A symbol of the same name has already been defined. Rename the symbol.
	This is not a symbol file. Please choose the correct format file.	The chosen file is not a file that can be used for symbol import. Please choose a file that is this format, or modify the chosen file so that it becomes this format.
	This is not a device comment file. Please choose the correct format file.	The chosen file is not a device comment import file. Please choose a file that is this format, or modify the chosen file so that it becomes this format.
	This symbol name is already registered as a Logic symbol. Please choose another name.	You attempted to change an existing symbol name. Be sure that your symbol name used is not one of those designated in the Word Symbol area's Logic Word or Real areas.
	The total number of Logic symbols is over 2048 and a Save cannot be performed. Please delete all unneeded symbols.	The maximum number of symbols has been exceeded. After deleting unneeded symbols, please retry saving the data.
S	Some data is incorrect and all data cannot be imported.	The format of CSV data to be imported is incorrect. Data in and below the line with the incorrect data will not be imported. Check Alarm data' CSV format.
	Symbol **** 's number of characters is over 20, and cannot be imported.	You attempted to import a symbol with a name over 20 characters long. Please reduce this name to less than 20 characters.
%	%s cannot be found, or cannot be performed.	The file(s) required to perform this action cannot be found. Please re-install the application software.

■ Screen Transfer Errors

	Error Message	Cause/Solution
A	A different Extended Program is present in the LT. The LT's setup cannot be performed.	This extended program can only be sent to a LT containing the same program. Please change the LT type, or install the extended task's program in the LT.
	A different Extended Program is present in the LT. Do you wish to continue?	A different type of Extended Program is present in the LT. Press OK to overwrite this program, or Cancel to stop the transfer. Selecting OK will change the LT's internal Extended Program.
C	Cannot transmit data at 115.2Kbps - used a slower speed. Change Data Transfer Speed to 38400 when sending data.	This error occurs when the speed of 115.2Kbps cannot be used. Change the Data Transfer Speed setting to 38400 and re-try.

■ **Screen Transfer Errors (from previous page)**

		Error Message	Cause/Solution
C		Command Parameter ERROR	Retry data transfer to the designated LT using "Auto Setup". If this message appears again, the PC has a command-related problem. Or, there may be an error in the cable or in the PC. Check both and retry data transfer. If the problem persists, the cable may be damaged. If necessary, contact your local LT distributor.
		Connected Device is not correct LT!	A device other than the LT or one that is not supported by LT Editor is connected. Check the model of the connected device.
		Core - ID Command failed	An error has occurred during data transfer from the PC. The cable may be disconnected or the LT is OFF. Retry data transfer.
D		Data Transfer Port initialization error.	Initialization of the communication port has failed. Check the transfer serial port settings and transfer cable connection.
		Do you want to download the simulation protocol?	When you want to transfer the simulation protocol, click OK. Otherwise, click cancel.
E		ERROR, Out of Memory	The LT's internal memory is full. Delete any unnecessary screens.
		ERROR, Incomplete Transmission	Screen transfer to the LT has been aborted. Refer to the error message code.
		ERROR, No Configuration File	The file required for setup was not found in the specified folder. Re-install the system from the Master disk, or check the transfer path settings. (Transfer Settings area)
		ERROR, Cannot Transfer Data	A communication error has occurred and transfer has failed. Reset the LT and PC and retry data transfer.
		ERROR, Cannot open Screen	The system is trying to transfer the screen to the LT but cannot open the Project File.
H		Handshaking ERROR – LT not Responding	The LT power supply is turned OFF, the data cable is unplugged, or the LT may be in OFFLINE mode. Check all these points. When the LT main unit is in OFFLINE mode, reset it to transfer mode. Also, check the serial port.
I		Invalid address substituted for unknown aliases, or invalid address error	When using a symbol in the device address, use the symbol editor to enter the actual symbol addresses.

■ **Screen Transfer Errors** (from previous page)

		Error Message	Cause/Solution
N		Network Connection Failed	Connection to the specified party node is failed. Check the PC network settings and the network cable connection. If the problem still remains, contact the network manager.
		No Upload Information in LT Data File	Because the LT does not have the data required for sending the data to the PC, the PC cannot receive the screen. The screen originally may have been sent with the upload information set to "Not transfer". A screen that is not sent together with the upload information cannot be received.
P		PGO command failed PLD command failed	The power supply to the LT may have been turned OFF, or the cable has been un-plugged. Reset the LT and the PC and retry data transfer.
		Protocol file not found	The External Device protocol file to be sent to the LT is not found in the system's directory. Re-install the LT's system starting from the master disk.
S		Send SIO Error - Unable To Open a Com Port	The COM port cannot be used. In the transfer setting menu's serial port setting, specify the available serial port, and retry data transfer.
		Send File Error - Bad File Data	The data to be sent is not correct. The data created in the temporary file cannot be read correctly. Check that the disk has sufficient free space and it is not corrupt, and retry file transfer.
		Simulation data file cannot be found.	The CSV file is not stored in the directory as the execution file. The simulation information file may be deleted, or the file may have not been created. Set the simulation feature when transferring the screen and retry data transfer.
		Simulation data file read-in error.	The CSV file cannot be read into the system. The simulation information file may have been deleted, or the file may have not been created. Set the simulation feature when transferring the screen and retry data transfer.

■ **Screen Transfer Errors** (from previous page)

■ Screen Transfer Errors (from previous page)

		Error Message	Cause/Solution
T		The Extended Program cannot be found.	The Extended Program required for setting up the LT cannot be found. Please check the CFG file's directory. Also, you may need to change the LT's type.
		The Extended Program cannot be found in the LT. The LT's Setup cannot be performed.	Unable to locate the program's destination LT for setup. Check the LT type settings and the LT type selected. Change the LT type, if needed.
		The currently selected Device/PLC does not support the Simulation feature.	The currently selected Device/PLC does not support the Simulation feature. This feature cannot be used with the destination LT. Deselect this feature and re-send the data.
		This LT does not support Extended Programs. The LT's setup cannot be performed.	The destination LT does not support Extended Features. Either change the LT Type, or send data that is designed for the designated LT type.
		Timeout Error	Communication timeout has occurred. Reset the LT and re-try data transfer.
W		Write Error	An error has occurred while reading the data to LT internal memory. Re-try data transfer. If the error occurs again, use the LT's self-diagnosis feature and identify the problem. If necessary, contact your local LT distributor.

■ Project Compression and Execution Errors

		Error Message	Cause/Solution
D		Disk Error - File Error During Read	The file cannot be opened. The most probable cause is corruption of the file or disk failure. Solve the problem and try again to read the file.
		Disk Error - File Error During Write	The disk is write-protected. Take off the write protection. This error also occurs when the disk is defective.
U		Unable to open file '***'. Would you like to try to find it elsewhere?	A portion of the file cannot be found. To recover divided files and recreate the original project file, all the divided files are required.
		Unable to open file ' *** ' for reading, aborting...	The file cannot be opened. The file is corrupt or the disk has a problem. After correcting the problem, re-try opening the file.

* The file named is inserted here ***.

■ Rebuild Tool Errors

		Error Message	Cause/Solution
F		File version does not match	The specified file contains settings for a version which is not supported by this rebuilding tool. Re-specify a project file (LTE file).
R		Rebuilding the File has Failed	Recovery of the file has failed. This file is damaged and cannot be rebuilt.
S		LTE header is destroyed	The file header information is corrupt. This file cannot be rebuilt and cannot be used.

■ DXF File Conversion Errors

The error messages generated during DXF file conversion are as follows:

(xynn) <message> (line = ????)

x :	Conversion direction (1: DXF → LT / 2: LT → DXF)
y :	Procedure (1: Read 2: Conversion 3: Write)
nn :	Error code
(line = ????) :	Line No. of the DXF file causing the error

■ DXF File Conversion Errors

Error Code	Error Message	Cause/Solution
01	Length Over in 1 record (line, ????)	The single record length of the DXF file exceeds 256 characters. Edit the error line so that the length is less than 256 characters.
02	DXF Format Error (line, ????)	Non-DXF data may be included. Correct the format of the data at the error line.
03	HEADER SECTION Not Found	The header section of the DXF file to be read is not found. Add the header section.
04	$LIMMIN Not Found	The header section of the DXF file to be read does not have a $LIMMIN setting. Set the option DXF size to " Use $EXTMIN, $EXTMAX " and re-execute the program, or add the $LIMMIN setting.
05	$LIMMAX Not Found	The header section of the DXF file to be read does not have a $LIMMAX setting. Set the option DXF size to " Use $EXTMIN, $EXTMAX " and re-execute the program, or add the $LIMMAX setting.
06	$EXTMIN Not Found	The header section of the DXF file to be read does not have a $EXTMIN setting. Set the option DXF size to " Use $LIMMIN, $LIMMAX " and re-execute the program, or add the $EXTMIN setting.
07	$EXTMAX Not Found	The header section of the DXF file to be read does not have a $EXTMAX setting. Set the option DXF size to " Use $LIMMIN, $LIMMAX " and re-execute the program, or add the $EXTMAX setting.
08	EOF Not Found	The EOF record is not specified at the end of the DXF file to be read. Add the EOF record.
0A	ENDSEC Not Found	The ENDSEC record is not specified at the end of the DXF file to be read. Add the ENDSEC record.
0B	ENDTAB Not Found (line, ????)	The ENDTAB record is not specified at the end of the TABLE section of the DXF file to be read. Add the ENDTAB record.
0C	(W) SEQEND Not Found (line, ????)	SEQEND to be used as a pair with VERTEX following the POLYLINE entity is not specified. Add the SEQEND record to the error line.
0D	Insufficient Data (line, ????)	The essential data for the element of each entity is insufficient. Add the required data to the error line.

■ **DXF File Conversion Errors(from previous page)**

Error Code	Error Message	Cause/Solution
0E	LTYPE Not Defined (line, ????)	The line type name specified when the entity line type is individually set is not defined in the TABLE section. Add the data of the preset line name to the TABLE section.
0F	LAYER Not Defined (line, ????)	The layer name set in the entity is not defined in the TABLE section. Add the preset layer name to the TABLE section.
10	STYLE Not Defined (line, ????)	The character style name used in the entity is not defined in the TABLE section. Add the character style name to be used to the TABLE section.
11	BLOCKS Not Defined (line, ????)	The composite picture name which is referenced by the INSERT and DIMENSION entities is not defined in the BLOCK section. Add the data of the preset composite picture name to the BLOCK section.
21	Application Error	An unexpected data case is found in the intermediate file. (This does not occur normally.) The temporary file created during conversion may not have been written. Check the free disk space and disk condition and retry conversion.
22	BLOCKS Not Found	The specified composite picture is not found when converting the INSERT and DIMENSION entities. Add the preset composite picture data to the BLOCK section.
23	(W) BLOCKS - Over Nesting Limit	The reference layers of the composite picture are more than 10 layers. A compound graphic with more than 10 layers cannot be converted. Correct the graphic data so that the number of layers will be 10 or less.
24	(W) Conversion Data is Over 16 Kbytes	The output LT screen size (after conversion) exceeds 16 K bytes. The subsequent data cannot be converted.
41	Format Error	The format of the LT data is not correct. LT data which is not supported may be involved, or the screen data is corrupt. Use the Editor to save the screen again and retry conversion.
42	(W) Check Sum Error	The checksum of the LT screen read is not correct. The data may be corrupt. Use the Editor to save the screen again and retry conversion.
43	(W) Library Screen Not Found ????	The screen being called is not found in the project. Create a destination screen or delete the data which calls the screen.
44	(W) Mark Screen Not Found ????	The mark screen being called is not found in the project. Create the destination mark screen or delete the data which calls the mark.

■ DXF File Conversion Errors(from previous page)

Error Code	Error Message	Cause/Solution
45	(W) Library Screen Type Error (0x????)	The type of the screen used in the screen call menu is not a base, mark, image, or a window screen. LT data which is not supported may be involved, or the screen data may be corrupt. Use the Editor to save the screen again and retry conversion.
46	(W) Screens – Over Nesting Limit	The screen calling layers are greater than 10. Screens with more than 10 layers cannot be converted. Correct the data so that the number of layers will be 10 screens or less.
81	Disk Full	When writing the temporary file or output file, the disk has become full. Increase the amount of free disk space for the temporary file and output file.
82	Insufficient Memory	The process is interrupted because of insufficient memory area during operation. Close all other applications and retry the operation.
FF	User Abort	The user has interrupted the operation during conversion.

■ File Management Errors

	Error Message	Cause/Solution
C	Cannot Write File ????	The data cannot be written to the specified output file name. Check the amount of free disk, or if the disk is write-protected.
I	Input File Name Format Error	The specified input file name is different from the file name created by the editor. Specify the correct file name.
	Input File Not Found	The specified input file is not found. Check the file name and specify the existing file.
O	Output File Name Format Error	The specified output file name cannot be recognized by the editor. Specify the correct file name.
W	Work Directory Not Found ????	The folder in which the temporary file is created is not found. Specify the existing folder using the environment variable TEMP.

■ Simulation Errors

		Error Message	Cause/Solution
	C	Cannot read data in project file.	The screen data cannot be read from the project file. Quit other functions and re-execute.
		Cannot write simulation information data. Unable to start simulation.	The system cannot write the data to the simulation information file. Check that the simulation file (TAGDATA.CSV) is not used in other applications and that the directory in which EXE exists is not write-protected.
	N	Not enough memory. Please close other applications.	Retry this action after closing other active applications.
	P	External Device Data File cannot be found.	The External Device table file does not exist in the specified directory. The External Device table file is deleted or it is not for the LT. Select the External Device file from the master disk and reinstall the file.
	S	Simulation start failed.	The LT does not respond to the simulation start command. The LT may be in another mode, or data transfer may have failed. Check the communication port settings, cable connections, LT unit power supply, and then retry the simulation data transfer.
		Simulation data file cannot be found.	The simulation information file (TAGDATA.CSV) does not exist in the specified directory. Check (turn on) the Transfer menu [Settings] area's [Simulation] selection, then retry the Simulation.

■ Filing Data Errors

		Error Message	Cause/Solution
	C	Cannot import CSV file. Data is out of range or format is incorrect.	The number of blocks or data amounts is inappropriate in the CSV file to be imported. Enter the correct value(s).
	D	Data is larger than designated data range. Please check the data settings.	Data from outside the Filing Data's range is present. Check the designated data range settings and change them if necessary.
	E	Exceeds folder addition limit.	Up to 64 folders can be stored in the internal memory and up to 8999 folders can be stored in the CF card. Any folder cannot be added because the number of folders will exceed the limit.
	I	Internal memory is not sufficient to save data. Please reduce the block or data settings.	The current settings will overflow the LT's memory. Please reduce either the block or data settings.
	P	Please enter a Block name.	Nothing has been entered for the Filing Data's Block data. Please enter a name.
	T	The currently selected data range exceeds the maximum amount allowed. Paste cannot be performed.	Please reduce either the amount of data copied or the number of blocks copied.
	W	When using 32 bit data settings the maximum number of data items is 20. OK to delete items over 20?	When using 16 bit data, up to 40 items can be used; with 32 bits, maximum is 20. Be sure the data type fits your data needs.

■ Logging Data Errors

	Error Message	Cause/Solution
A	Address Entry limit reached. No more addresses can be entered.	Reduce the number of device addresses used.
C	Character size is too large. Please use a different size.	Designated character is larger than LT's character matrix. Please select a smaller size.
D	Display file data size is over maximum.	Reduce the size of the designated display.
P	Paste failed.	The current paste settings (range, etc.) are not the same as the paste destination. Or, the paste action may delete a column or effect another data item's settings.
	Printer file data size is over.	Reduce the size of the area/amount of data to be printed.
T	Time settings cannot exceed 24 hours. Please adjust the settings.	Change the settings so that the time value is 24 hours or less.
	The no. of times x no. of blocks should be less than or equal to 2048.	Be sure the number of times and number of blocks produces a result that is 2048 or less.

A.2 Troubleshooting

This section describes how to solve problems generated when using LT Editor.

Before you begin troubleshooting, please check the following items again. If you answer "Yes" to all the questions, start troubleshooting. If you answer "No" to any one of the questions, set the required item and then start troubleshooting.

If the error still occurs after troubleshooting, fill the details of the error in the provided trouble report sheet and follow the directions stated in Appendix 4.

Item	Check
Is your personal computer's OS Windows 95/98/Me/NT4.0/2000 or XP?	
Is the memory capacity greater than 32 Mbytes?	
Is your PC hard disk's amount of free space sufficient?	

Error	Cause/Solution
LT Editor will not start up	Are all the environment settings correct? ▼ **Reference** ◢ LT Editor CD Jacket
	Is your personal computer hard disk's free space amount sufficient? Double-click on the Windows icon. Double-click on the drive in which LT Editor has been installed. Use the [File] menu's [Property] feature to check the amount of free disk space. If the free disk space is insufficient, empty the trash box or delete unnecessary files from the hard disk.
	Is the PC's RAM memory capacity sufficient? Memory of 16 M byte or more is required. Click the Windows 95 [Start] button first, and then click on the [Settings], [Control Panel], and [System] selections. Click the virtual memory button in the system property dialog box and check that "Auto Setting (recommended)" is selected. If "Manual Setting" is selected, change the setting to "Auto Setting (recommended)". Restart the PC and then restart LT Editor.
	Some applications do not work well with LT Editor and such an application may interfere with the startup of LT Editor. Quit all running applications and delete them from the Startup menu ([Startup] in the Windows 95 [Program] menu. Restart the PC and then restart LT Editor.
	Do the trigger commands (Config.sys, Autoexec.bat, etc.) operate correctly? Restart the PC. Press [F8] when "Starting windows" appears. When the menu appears, select "Step-by-step Confirmation" to check that the commands all operate normally. If an error message appears, correct the error. For details, refer to the PC's operation manual.

Error	Cause/Solution
Cannot draw graphic data	Is the LT Editor's screen open? With LT Editor, you must select the project file and open a drawing screen before you can draw any objects. Create a new a screen or open an existing one.
	Does the disk have enough free space? Prepare a disk which has enough free space.
	Is the symbol editor started? The screen editor and the symbol editor cannot be started at the same time. Check that the symbol editor window has been closed.
Cannot save the screen file's data	Is the file write-protected? Check whether the floppy disk is write-protected using the [Property] feature.
	Does the disk you are saving to have enough free space? Prepare a disk which has enough free space.
Cannot communicate between the PC and the LT	Is the proper cable being used? Be sure to use the DIGITAL transfer cable (option).
	Is the LT in the "Screen Data Transfer Mode" or "Run Mode"? If not, communications between the PC and the LT will not be possible. ▼*Reference*▲ LogiTouch Series User Manual
	When receiving data from the LT, does your PC's hard disk have enough space? Prepare the disk so that it has enough free space.
	Is the communication port setting correct? Check that the transfer cable's serial port matches the port set in [Transfer].
	Does another application use the same communication port? Check whether there is competition between the LT and a modem, or other applications which require the communication port.
If:the Buzzer won't stop. The LT won't display data. Data transfer fails.	The Data Transfer cable may be loose or connected to the wrong COM port. Also, the System Data area may be incorrectly accessed, or the LT may be incorrectly set up. For details, see the next page's Appendix 2.2.
The printer does not run/ hard copy is not printed	Is the OS's (Windows) printer setting correct? Check the printer setting using the Control Panel's printer property.
The desired External Device and LT type are not listed when creating a new project	Did you select the required External Device and LT type when installing LT Editor? (Custom Installation) When customizing the system installation, you can select the External Device and the LT types. You cannot install an External Device or a LT type if it has not been selected previously. Re-install the system with the desired External Device and LT type.
Simulation cannot be performed	Possible causes are that LS area data is being backed up to the LT, via the [System Setup], or that an LS area Special Relay is being used by D-Script start up bit. If any of these are true, the simulation cannot be performed. Deselect the [Option] menu - [Settings] - [LS Device Simulation].

A.2.2	**Buzzer will not Stop/No Display on the LT/Transfer Disabled**

■ Error Pattern by Symptom

Error Pattern	Buzzer Sound (Symptom)	LT Screen	Probable Cause
1	Pip, pip, pip, … (Continues to beep intermittently or beeps every second.)	Blank (Black)	There is no startup program or the startup program has been corrupted.(When the LT is powered on)
2	None	Normal Display	Transfer cable was removed. Improper COM port was used.
3	None	Blank (Black)	The system for the target model has not been downloaded. (When the LT is powered on)
4	None	Blank/	Invalid access is made to "+9" or "+14" of the
	Buzzer sounds continuously	Normal	System Data Area.

Refer to Solution 1 when error pattern 1 is observed.
Similarly, Solution 2 corresponds to Error Pattern 2.
When error pattern 3 is observed, try the procedure described in Solution 3.
If Solution 1 or 2 does not solve the problem with error patterns 1 and 2, try Solution 3 as well.
Refer to Solution 4 when error pattern 4 is observed.

◆ Solution 1

1. Transfer from the PC

   Transfer programs and screen data from the PC (LT Editor) to the LT while the buzzer of the LT sounds. (Be sure that your PC and the transfer cable are able to transfer programs and data to the LT.) LT Editor has been programed to handle a variety of problems and retry data transfer repeatedly if the LT fails to respond successfully. In this case, LT Editor will try repeatedly to complete handshake mode (it may take more than a minute in some situations). After handshaking is completed, LT Editor will begin to transfer the Memory Loader program, system program, communication protocol program, expansion program and screen data.

◆ Solution 2

   The transfer cable is improperly connected or has been removed. The improper COM port may have been selected. Confirm that the cable and port are set up properly for data transfer and try again.

◆ **Solution 3**

If error pattern 3, 4 or 5 has been observed, or Solution 1 or 2 does not solve the problem, perform a forced transfer from your PC. Perform the transfer even if the buzzer is sounding. (Confirm that the cable and PC are configured for successful transfers.)

1. Select [Setup] from the [Setup] menu on the [Screen Transfer] to display the [Transfer Settings] dialog box on the screen.

2. Select "Force System Setup" from the "Setup" field and click the [OK] button.

3. Select [Screen Transfer] from the [Transfer] menu and perform a forced transfer.

4. When the message "No System Program on the LT" is displayed on the screen, click the [OK] button.
   This message will not be displayed if the protocol has not been downloaded to the LT.

5. The message "Select Type" is displayed on the screen. Select the model type and click the [OK] button.

   Usually, the system automatically selects the connected model. However, confirm the model type of the connected LT.

> **If an improper model type is selected here before a forced transfer, the symptoms will recur.**
>
> *Important*

6. Check the LT type and click the [OK] button. The system begins transferring the System Program, Protocol Program and screen data.
   The restoration is completed when the transfer is completed successfully.
   In some cases, the "handshaking" (transfer to the LT unit) with the LT may not be successful.
   If handshaking is unsuccessful, the system displays the following message on the screen to ensure successful handshaking with the LT.

Power the LT OFF and ON again. The system will automatically resume the transfer.

◆ **Solution 4**

Check whether an incorrect value has been entered into the LT in "+9" or "+14" of the System Data Area, or an invalid Start Address has been assigned for the System Data Area.

A.3	## Address Conversion Tables

Addresses can or cannot be converted depending on the address combination. The combinations which cannot be converted vary with the external device manufacturers. See the following address global conversion table to convert the addresses correctly.

■ How to Read the table

The symbols used in the table have the following meanings:

○ : When the address conversion device type is set to [Word], the system converts both Word and bit devices. When the [Bit] setting is used, only bit device addresses are changed.

◆ : When the selected conversion mode is [Word], only Word addresses are converted. Selecting [Bit] will convert only bit addresses.

★ : When [Word] mode is selected, the system converts only word addresses.

■ : When [Bit] mode is selected, the system converts only bit addresses.

(Blanks cannot be converted)

For the timers and counters, the bit indicates the contact or coil used, and the word indicates the current value (elapsed value) or setting value

■ Address Conversion Table List

Memory link SIO Type

		After conversion
		LS
Before conversion	**LS System Area**	○

■ Mitsubishi Electric FREQROL Series

		After Conversion			
		-	P	All devices except for parameter	LS
Before Conversion	Parameter except for FR-S500, E500's Pr-37	○	○	○	○
	P	○	○	○	○
	Parameter for FR-S500, E500's Pr-37	○	○	○	○
	All devices except for parameter	○	○	○	○
	LS System Area	○	○	○	○

■ Yokogawa Electric FACTORY ACE

		After Conversion																
		X	Y	I	E	M	L	T	C	TP	CP	TS	CS	D	B	R	Z	W	LS
Before Conversion	X Input Relay	❍	❍	❍	❍	❍	❍	■	■	★	★	★	★	❍	❍	❍	❍	❍	❍
	Y Output Relay	❍	❍	❍	❍	❍	❍	■	■	★	★	★	★	❍	❍	❍	❍	❍	❍
	I Internal Relay	❍	❍	❍	❍	❍	❍	■	■	★	★	★	★	❍	❍	❍	❍	❍	❍
	E Common Relay	❍	❍	❍	❍	❍	❍	■	■	★	★	★	★	❍	❍	❍	❍	❍	❍
	M Special Relay	❍	❍	❍	❍	❍	❍	■	■	★	★	★	★	❍	❍	❍	❍	❍	❍
	L Link Relay	❍	❍	❍	❍	❍	❍	■	■	★	★	★	★	❍	❍	❍	❍	❍	❍
	T Timer (contact)	■	■	■	■	■	■	■	■					■	■	■	■	■	■
	C Counter (contact)	■	■	■	■	■	■	■	■					■	■	■	■	■	■
	TP Timer (current)	★	★	★	★	★	★			★	★	★	★	❍	❍	❍	❍	❍	❍
	CP Counter (current)	★	★	★	★	★	★			★	★	★	★	❍	❍	❍	❍	❍	❍
	TS Timer (setup)	★	★	★	★	★	★			★	★	★	★	❍	❍	❍	❍	❍	❍
	CS Counter (setup)	★	★	★	★	★	★			★	★	★	★	❍	❍	❍	❍	❍	❍
	D Data Register	❍	❍	❍	❍	❍	❍	■	■	★	★	★	★	❍	❍	❍	❍	❍	❍
	B File Register	❍	❍	❍	❍	❍	❍	■	■	★	★	★	★	❍	❍	❍	❍	❍	❍
	R Joint Register	❍	❍	❍	❍	❍	❍	■	■	★	★	★	★	❍	❍	❍	❍	❍	❍
	Z Special Register	❍	❍	❍	❍	❍	❍	■	■	★	★	★	★	❍	❍	❍	❍	❍	❍
	W Link Register	❍	❍	❍	❍	❍	❍	■	■	★	★	★	★	❍	❍	❍	❍	❍	❍
	LS System Area	❍	❍	❍	❍	❍	❍	■	■	★	★	★	★	❍	❍	❍	❍	❍	❍

R Joint Register is only for FA-M3.

■ Yokogawa M&C UT100 Series

Device		After conversion	
		D Register d	LS
Before conversion	D Register d	❍	❍
	LS Area	❍	❍

■ **Yamatake Yamatake SDC Series/DMC10**

		After Conversion	
		Data	LS
Before Conversion	Data	❍	❍
	LS System Area	❍	❍

■ **Rika Kohgyou CB/SR-Mini Series**

		After Conversion	
		0000 to 02EE	LS
Before Conversion	0000 to 02EE	❍	❍
	LS	❍	❍

■ **Rika Kohgyou CB/REX-F/LE100 Series**

		After Conversion			
		CB	REX	LE	LS
Before Conversion	CB	❍	❍	❍	❍
	REX	❍	❍	❍	❍
	LE	❍	❍	❍	❍
	LS	❍	❍	❍	❍

■ **Omron THERMAC NEO Controller**

		After Conversion				
		C0	C1	C3	A	LS
Before Conversion	C0	❍	❍	❍	❍	❍
	C1	❍	❍	❍	❍	❍
	C3	❍	❍	❍	❍	❍
	A	❍	❍	❍	❍	❍
	LS	❍	❍	❍	❍	❍

■ Shinkoh Technos   C/FC/FIR/GC/FCL/PC-900 Series

		After Conversion			
		___	S	C	LS
Before Conversion	--------	❍	❍	❍	❍
	Setting Value Memory	❍	❍	❍	❍
	Channel	❍	❍	❍	❍
	LS Area LS	❍	❍	❍	❍

■ Fenwal Controls of Japan Temperature Controller AL Series

		After Conversion	
		All Devices	**LS**
Before Conversion	**All Devices**	❍	❍
	LS Area LS	❍	❍

■ JT Engineering Moisture Meter JE-70 Series

		After Conversion			
		M	**D**	**R**	**LS**
Before Conversion	**M**	❍	❍	❍	❍
	D	❍	❍	❍	❍
	R	❍	❍	❍	❍
	LS Area LS	❍	❍	❍	❍

■ Fuji Electric FRENICS, FVR Series

		After Conversion									
		F	**E**	**C**	**P**	**H**	**A**	**o**	**S**	**M**	**LS**
Before Conversion	**Fundamental Function F**	❍	❍	❍	❍	❍	❍	❍	❍	❍	❍
	Terminal Function E	❍	❍	❍	❍	❍	❍	❍	❍	❍	❍
	Control Function C	❍	❍	❍	❍	❍	❍	❍	❍	❍	❍
	Motor 1 P	❍	❍	❍	❍	❍	❍	❍	❍	❍	❍
	High-level Function H	❍	❍	❍	❍	❍	❍	❍	❍	❍	❍
	Motor 2 A	❍	❍	❍	❍	❍	❍	❍	❍	❍	❍
	Option O	❍	❍	❍	❍	❍	❍	❍	❍	❍	❍
	Command Data S	❍	❍	❍	❍	❍	❍	❍	❍	❍	❍
	Monitor Data M	❍	❍	❍	❍	❍	❍	❍	❍	❍	❍
	System Area LS	❍	❍	❍	❍	❍	❍	❍	❍	❍	❍

■ Fuji Electric Micro Controller X

		After Conversion					
		0	1	30	40	31	41
Before Conversion	0	■	■	■	■	■	■
	1	■	○	○	○	○	○
	30	■	○	○	○	○	○
	40	■	○	○	○	○	○
	31	■	○	○	○	○	○
	41	■	○	○	○	○	○
	LS Area LS	■	○	○	○	○	○

■ Mitsubishi Electric MELSEC-F₂

		After Conversion							
		X	Y	N	S	T/TC/TS	C/CC/CS	D	LS
Before Conversion	X Input Relay	■	■	■	■	■	■	■	■
	Y Output Relay	■	■	■	■	■	■	■	■
	M Auxiliary Relay, Keep Relay	■	■	■	■	■	■	■	■
	S State	■	■	■	■	■	■	■	■
	T/TC/TS Timer	■	■	■	■	○	○	■	■
	C/CC/CS Counter	■	■	■	■	○	○	■	■
	D Data Register	■	■	■	■	◆	◆	○	○
	LS System Area	■	■	■	■	◆	◆	○	○

■ Mitsubishi Electric MELSEC-FX

	After Conversion							
Before Conversion	X	Y	M	S	TS/TN	CS/CN	D	LS
X Input Relay	○	○	○	○	◆	◆	○	○
Y Output Relay	○	○	○	○	◆	◆	○	○
M Internal Relay	○	○	○	○	◆	◆	○	○
S Step Relay	○	○	○	○	◆	◆	○	○
TS/TN Timer	◆	◆	◆	◆	○	○	◆	◆
CS/CN Counter	◆	◆	◆	◆	○	○	◆	◆
D Data Register	○	○	○	○	◆	◆	○	○
LS System Area	○	○	○	○	◆	◆	○	○

■ Toho Electronics TTM Series

	After Conversion																	
Before Conversion	00_	10_	100_	110_	120_	300_	1020_	SSV	END	STI	SOK	SWZ	SWT	SON	SOF	SRN	SEO	LS
00_	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○
10_	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○
100_	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○
110_	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○
120_	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○
300_	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○
1020_	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○
SSV	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○
END	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○
STI	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○
SOK	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○
SWZ	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○
SWT	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○
SON	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○
SOF	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○
SRN	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○
SEO	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○
LS	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○

■ SHIMADEN SR253/SR90/SR80/MR13/FP93/SD16/EM70 Series

		After Conversion	
		Data Address	LS Area
Before Conversion	**Data Address**	❍	❍
	LS Area	❍	❍

■ Matsushita Electric Industrial MINAS-A/S Series

		After Conversion	
		All Devices	LS
Before Conversion	**All Devices**	❍	❍
	LS Area LS	❍	❍

■ Yasukawa Electric G7/F7 Series and VS mini V7/J7 Series Variable-Speed Inverter (Varispeed)

		After Conversion		
		BR	——	LS
Before Conversion	**Bit Register BR**	❑	❑	❑
	Register ——	❑	❍	❍
	LS Area LS	❑	❍	❍

A.4 Software Trouble Report

■ When problems continue after following "Troubleshooting"advice

If following the steps outlined in the troubleshooting section does not solve your problem, please make a copy of the next page's Software Trouble Report, fill in any relevant information, and fax it to your local Pro-face service center.

Please include any relevant details, including project data and/or screens so that the problem can be duplicated. We guarantee all this data will remain confidential.

Also, please take the time to use the "OSCHECK" tool installed with your LT Editor software, and include a printout of its result with your fax.

Using the "OSCHECK" Program

This program, after it completes its test, produces a text file (*.txt). Please be sure to print out this data and include it with your Software Trouble Report.

1) Click on the Windows main screen's [Start] button and then on the [Run] selection.

2) Here, use the [Browse] feature to find the OSCHECK.EXE program, located in your PC's "LT Editor" folder. Once you find it, click on [OK] to start the program.

3) Designate the status report's Save folder and filename. Click again on [OK] and the text file will be created.

! *Important*

- *When inquiring, be sure to write down your software's serial No. Without your software's serial No., your question(s) cannot be answered.*
- *Understand that it may take some time for us to respond, since your question must be carefully checked and recreated.*

Pro-face FAX and Email Information:

- **Pro-face Europe:** FAX No. +31-(0)20-6464-358 Email: support@proface.com

- **Pro-Face Korea:** FAX No. +82-(0)2-3664-6839   Email: proface@proface.co.kr

- **Pro-Face Taiwan:** FAX No. +886-(0)2-8773-7892   Email: proface@proface.com.tw

- **Pro-face America** (North and South): FAX No. +1-630-351-1102
  Email: support@profaceamerica.com

Digital (Japan) FAX and Email Information:

- Digital Electronics Corporation: FAX No. +81-6-6613-5982 Email: support@digital.co.jp

Also, if you require instruction about the correct usage of your LT Editor software, please use the above information to contact your local LT Editor distributor.

Software Trouble Report	Date: Number of pages:

Company name_____ Department _____ TEL _____

Your name _____ FAX _____

Company Address _____

Software Serial No. ☐☐☐☐☐☐☐☐

* We cannot respond to any questions without your software's serial number.

Software name : LT Editor (   )   Other (   )

Ver.____   (   )

Your LT model: Type of Device/PLC:

PC: Manufacturer: Model:

Printer   Manufacturer: (   ) Model: (   )

Driver version: (   )

Describe the details and how to reproduce each problem. Also, please include a list of any related documents. Prepare one report sheet for each problem.

Error message details:

(This area is for Pro-face use only)	Processed by	Received by

INDEX

Index

Index